



CHINO VALLEY TO FOREST BOUNDARY TRANSPORTATION STUDY

Final Report

April 2017

Prepared for:



Prepared by:

BURGESS & NIPLE

State Route 89 Chino Valley to Forest Boundary Transportation Study

ADOT Task Assignment MPD 0034-16

Final Report

Prepared for:



AND



Prepared by:

BURGESS & NIPLE

April 2017

Project Leadership

Arizona Department of Transportation

206 S. 17th Ave, MD310B

Phoenix, AZ 85007

Dan Gabiou, Planning Program Manager

Email: DGabiou@azdot.gov

Telephone: 602.712.7025

1109 Commerce Drive

Prescott, AZ 86305

Randy Blake, Project Development Coordinator

Email: RBlake@azdot.gov

Telephone: 928.777.5873

Central Yavapai Metropolitan Planning Organization

1971 Commerce Center Circle, Suite E

Prescott, AZ 86301

Christopher Bridges, CYMPO Administrator

Email: Christopher.Bridges@yavapai.us

Telephone: 928.442.5730

Study Consultant

Burgess & Niple, Inc.

1500 N. Priest Drive, Suite 102

Tempe, AZ 85281

Jason Pagnard, PE

Email: Jason.Pagnard@burgessniple.com

Telephone: 602.244.8100

This report was funded in part through grants from the Federal Highway Administration, U.S. Department of Transportation. The contents of this report reflect the views of the authors, who are responsible for the facts and the accuracy of the data, and for the use or adaptation of previously published material, presented herein. The contents do not necessarily reflect the official views or policies of the Arizona Department of Transportation or the Federal Highway Administration, U.S. Department of Transportation. This report does not constitute a standard, specification, or regulation. Trade or manufacturers' names that may appear herein are cited only because they are considered essential to the objectives of the report. The U.S. government and the State of Arizona do not endorse products or manufacturers.

Table of Contents

Executive Summary	E1
Current and Future Conditions.....	E1
Plan of Improvements.....	E2
1.0 Introduction.....	1
1.1. Study Overview.....	1
1.2. Study Area.....	1
2.0 Relevant Plans and Studies.....	3
2.1. CYMPO Title VI Plan, June 2016.....	3
2.2. AASHTO U.S. Bicycle Route System, August 2015.....	3
2.3. CYMPO Regional Transportation Plan Update 2040, April 2015.....	3
2.4. Statewide Wildlife Crash Analysis and Proposed Action Plan, September 2014.....	3
2.5. Town of Chino Valley General Plan 2014, May 2014.....	4
2.6. 2014 Arizona Strategic Highway Safety Plan, 2014.....	4
2.7. Yavapai County Comprehensive Plan, September 2012.....	4
2.8. Chino Valley Extension Study, February 2009.....	4
2.9. State Route 89 Access Management Plan, June 1997.....	5
3.0 Current Conditions.....	7
3.1. Land Ownership and Jurisdiction	7
3.2. Land Use	7
3.3. Zoning.....	10
3.3.1. Open Zoning Cases.....	10
3.4. Residential Development.....	12
3.5. Activity/Employment Centers	14
3.6. Utilities	14
3.7. Transportation Network.....	14
3.7.1. Roadway Characteristics	14
3.7.2. Truck and Freight Movement.....	25
3.7.3. Bicycle and Pedestrian Network.....	26
3.7.4. Transit Network.....	26
3.8. Traffic Analysis	27
3.8.1. Existing Traffic Volumes	27
3.8.2. Traffic Operational Analysis	29
3.8.3. Crash Analysis	30
4.0 Environmental Considerations.....	38
4.1. Natural Resources	38
4.2. Water.....	38
4.3. Fish, Wildlife, and Plants	38
4.3.1. Fish	39
4.3.2. Wildlife.....	39

4.3.3. Plants.....	40
4.4. Critical Habitat.....	40
4.5. Wildlife Connectivity.....	40
4.6. Cultural Resources.....	40
4.7. Hazardous Materials.....	43
4.8. Air and Noise.....	43
4.9. Socioeconomic Profile	43
4.10. Section 4(f) properties	47
4.11. Topography and Drainage Features.....	47
5.0 Future Conditions.....	50
5.1. Utilities.....	50
5.2. Transportation Network.....	50
5.2.1. Roadway Network.....	50
5.2.2. Bicycle and Pedestrian Network.....	50
5.2.3. Transit Network.....	50
5.2.4. Freight Movement.....	51
5.3. Traffic Analysis.....	51
5.3.1. Travel Demand Model Land Use.....	51
5.3.2. Traffic Forecast and Annual Growth Factor Development.....	51
5.3.3. Design Hour Volume Factor.....	51
5.3.4. Traffic Operational Analysis.....	52
6.0 Identified Needs Summary	55
6.1. Safety.....	55
6.2. Access Management	55
6.3. General Considerations.....	55
7.0 Corridor Vision and Access Management.....	56
7.1. Perkinsville Road to Road 5N (MP 329.20 to 331.28).....	56
7.2. Road 5N to Sweet Valley Road (MP 331.28 to 336.69).....	57
7.3. Sweet Valley Road to Bramble Drive (MP 336.69 to MP 338.80)	57
7.4. Bramble Drive North (MP 338.80 to 341.42).....	58
7.5. Access Management Guidelines.....	58
8.0 Potential Improvement Strategies	59
8.1. Safety Analyst Analysis	59
8.2. Perkinsville Road to Road 5N (MP 329.20 to 331.28).....	59
8.3. Road 5N to Sweet Valley Road (MP 331.28 to 336.69).....	60
8.4. Sweet Valley Road to Bramble Drive (MP 336.69 to MP 338.80)	61
8.5. Bramble Drive to Study Limit (MP 338.80 to 341.42).....	62
8.6. Revised Project Concepts	62
8.7. Design Considerations.....	62
8.8. Estimate of Probable Cost.....	63
8.9. Other Considerations	65

9.0 Traffic Analysis	66
10.0 Potential Improvement Safety Analysis.....	69
10.1. Financial Benefit of Countermeasures	73
10.2. Benefit to Cost Ratio	76
11.0 Evaluation of Potential Projects	77
11.1. Potential Projects.....	77
11.2. Evaluation Criteria	79
11.3. Evaluation of Potential Improvements	79
11.4. Explanation of Ratings.....	81
12.0 Recommendations.....	85
12.1. Near-term (5-year)	85
12.2. Mid-term (10-year)	85
12.3. Long-term (20-year)	86
13.0 Field Review and Preliminary Scoping.....	89

Figures

Figure 1 – Study Area	2
Figure 2 – Recommended Chino Valley Extension.....	5
Figure 3 – Land Ownership and Jurisdiction.....	8
Figure 4 – Land Use.....	9
Figure 5 – Zoning.....	11
Figure 6 – Residential Development.....	13
Figure 7 – BNSF Railway Overpass	15
Figure 8 – Summary of Sufficiency Rating Factors.....	16
Figure 9 – Yavapai County Functionally Classified Roads.....	18
Figure 10 – Chino Valley Functionally Classified Roads	19
Figure 11 – Existing Traffic Volumes.....	28
Figure 12 – Crash Heat Map	31
Figure 13 – Hourly Distribution of Crashes South of Road 5N.....	35
Figure 14 – Hourly Distribution of Crashes North of Road 5N.....	37
Figure 15 – Topography	48
Figure 16 – Drainage Features	49
Figure 17 – Recommended Typical Section between Perkinsville Road and Road 5N	57
Figure 18 – Recommended Typical Section between Road 5N and Sweet Valley Road	57
Figure 19 – Recommended Typical Section between Sweet Valley Road and Bramble Drive	57
Figure 20 – Intersections Considered in Analysis.....	67
Figure 21 – Qualitative Project Evaluation.....	80

Tables

Table E1 – Project Recommendations.....	E4
Table 1 – Summary of SR 89 Access Management Recommendations.....	6
Table 2 – ADOT Access Management Guidelines Table 4.1 Connection Spacing Requirements .	20
Table 3 – ADOT recommended Corner Clearance –without Median.....	21
Table 4 – ADOT recommended Corner Clearance – with Median.....	21
Table 5 – Summary of Existing Intersections*	22
Table 6 – Summary of Existing Driveways	24
Table 7 – Corner Clearance Spacing Less than Recommended	25
Table 8 – Permits Issued between January 2015 and February 2016.....	26
Table 9 – 2016 AM & PM Peak Hour Capacity Analysis.....	29
Table 10 – Crash Severity	30
Table 11 – Multiple Vehicle Crashes	32
Table 12 – Other Vehicle Crashes	32
Table 13 – Crash Distribution by Day	33
Table 14 – Crash Characteristics South of Road 5N.....	33
Table 15 – Top Five Crash Locations South of Road 5N	34
Table 16 – Crash Characteristics South of Road 5N.....	34
Table 17 – Crash Lighting South of Road 5N	35
Table 18 – Crash Characteristics North of Road 5N.....	36
Table 19 – Crash Lighting North of Road 5N	36
Table 20 – Summary of Cultural Resource Surveys Previously Conducted within 0.5 Miles of the SR 89 R/W Between MP 328.45 and MP 341.92.....	42
Table 21 – 2014 Population and Racial Demographics	45
Table 22 – Age 60 Years and Over, Below Poverty Level, Disabled, and Female Head of Household Populations	46
Table 23 – 2021 AM and PM Peak Hour Capacity Analysis	52
Table 24 – 2026 AM and PM Peak Hour Capacity Analysis	53
Table 25 – 2036 AM and PM Peak Hour Capacity Analysis	54
Table 26 – Estimate of Probable Cost	64
Table 27 – 2036 AM and PM Peak Hour Build Capacity Analysis.....	68
Table 28 – Crash Modification Analysis for Intersection Improvements.....	70
Table 29 – Crash Modification Analysis for Segment Improvements	72
Table 30 – 2015 Arizona Crash Facts Summary Average Economic Cost per Incident.....	73
Table 31 – 2017 HSIP Application Crash Severity Unit Costs.....	73
Table 32 – Financial Benefit of Countermeasures using 2015 Arizona Crash Facts Cost per Incident	74
Table 33 – Financial Benefit of Countermeasures using HSIP Cost per Incident.....	75
Table 34 – Benefit to Cost Ratio for Potential Improvements.....	76
Table 35 – Project Recommendations.....	87

Appendices

Appendix WP1-1	Current Conditions Summary Map Book
Appendix WP1-2	Reference Document Catalog
Appendix WP1-3	Existing Traffic Counts
Appendix WP1-4	2016 HCS and SIDRA Results
Appendix WP1-5	2021 HCS and SIDRA Results
Appendix WP1-6	2026 HCS and SIDRA Results
Appendix WP1-7	2036 HCS and SIDRA Results
Appendix WP2-1	Recommendations Map Book
Appendix WP2-2	Project Probable Cost Derivation
Appendix WP2-3	2036 Capacity Analysis
Appendix WP2-4	Crash Modification Factors
Appendix WP2-5	Public Involvement Summary
Appendix FR-1	Prescoping Reports, Field Review Reports, and Field Summary Notes

Executive Summary

The State Route 89 (SR 89) Chino Valley to Forest Boundary Transportation Study was conducted by the Arizona Department of Transportation (ADOT) in partnership with Central Yavapai Metropolitan Planning Organization (CYMPO).

SR 89 is a high speed, two-lane roadway located in Yavapai County. SR 89 is a north-south oriented highway that links the City of Prescott (Prescott) and the Town of Prescott Valley (Prescott Valley) to Interstate 40 (I-40) via Chino valley. The Study Area is located along SR 89 from Perkinsville Road (milepost (MP) 328.95) to the Prescott National Forest (PNF) area (MP 341.42). It connects the Town of Chino Valley (Chino Valley), Paulden, and the PNF in Yavapai County.

In the next 25 years, the population of Chino Valley is anticipated to grow by 73% with a 100% increase in employment. This growth is due to general population growth as well as additional commercial and recreational traffic to I-40 and beyond. Many businesses and some residential areas are located along SR 89, where there are numerous access points with limited turning-movement accommodations. Crash data identified 203 crashes from 2010 to 2015 including 62 reported injuries and three fatalities. Rugged terrain, steep grades, and other physical features in northern portion of SR 89 affect traffic flow and reduce the number of passing opportunities. Due to area growth, increasing traffic volumes, limited turning movement accommodations, and high speeds, SR 89 is in need of operational and safety improvements.

This study included stakeholder outreach to inform and obtain meaningful input throughout the study. Stakeholders provided data, reviewed documents, provided guidance, and attended monthly progress meeting via teleconference. The following is a list of study Stakeholders:

- ADOT
- Arizona Game and Fish Department
- Arizona State Land Department
- Town of Chino Valley
- Chino Valley Fire Department
- Chino Valley Police Department
- CYMPO
- Town of Dewey Humboldt
- Department of Public Safety
- The Nature Conservancy
- Paulden Area Committee Organization
- City of Prescott
- Town of Prescott Valley
- United States Forest Service
- United States Fish and Wildlife Service
- Yavapai County

Two working papers were completed in conjunction with this Study: Working Paper 1 – Current and Future Conditions, and Working Paper 2 – Plan of Improvements. Both working papers were reviewed by Stakeholders and recommended improvements presented to the public.

Current and Future Conditions

Working Paper 1 (WP1) summarized completed and ongoing plans and studies impacting the Study Area. Known existing and future conditions within the Study Area were outlined, including:

- Land ownership and jurisdiction;
- Land use;
- Zoning;
- Residential development;
- Activity/employment centers;
- Utilities;
- Transportation network;
- Traffic analysis; and
- Environmental considerations.

Within the past five years, there have been over 200 crashes reported, including three fatalities within the analysis period; an additional fatality occurred immediately following the analysis period. The corridor has two distinct character areas where the crash patterns differ. The following summarizes the findings of the crash analysis:

- South of Road 5N (developed), the top three types of crashes include rear end, left turn, and sideswipe (same direction). Crashes were generally clustered around intersections. The top five locations, from south to north, include the intersections at Perkinsville Road, Palomino Road, Road 3N, Road 4N, and Road 5N. The Perkinsville Road and Road 4N intersections were recently reconstructed as roundabouts, which is anticipated to address safety concerns at these locations. The intersections at Palomino Road, Road 3N, and Road 5N, along with other locations, should be considered for safety related improvements.
- North of Road 5N (less developed), the top three types of crashes include fixed object, rear end, and animal. Crashes were generally clustered around intersections, with various intermittent crash locations throughout. The four fatalities reported in the Study Area occurred in this segment, where three of the four occurred at intersections. In addition to the intersections, clusters of crashes occur just south of the Del Rio Ranch Bridge (near MP 333), between Little Ranch Road and the Big Chino Wash Bridge (MP 335.7 to 336.2), and near the development just south of the BNSF Railway bridge (MP 337.0). In general, there is a need to reduce the number of single vehicle and nighttime collisions.

Provisions for access management for future development should be considered. Primarily south of Road 5N and at spot locations to the north, access point density, location, and type need to be addressed.

Plan of Improvements

Working Paper 2 (WP 2) addressed the primary needs of the corridor identified in WP 1 in light of stakeholder input. These needs included safety and access management improvements that consider environmental concerns, truck traffic, and the potential for growth. A long-term corridor vision, extending beyond the 20-year planning horizon of the study, was developed to accommodate growth and integrate access management. The corridor vision, divided into four segments, should guide improvement along the corridor and accommodate future development as it occurs. Potential improvement strategies were developed that would blend with the long-term vision, minimize "throw away" infrastructure considering the corridor vision, and address the identified needs.

Safety countermeasures were identified that may improve safety performance by focusing on the crash types having the greatest potential for mitigation. The corridor was analyzed by ADOT Traffic Safety Section staff using Safety Analyst and the following recommendations were made:

- Strong need for access management due to high rear-end crashes in urban areas.
- Reduce the high number of run-off road / fixed object crashes in rural areas.
- There is a need for appropriate wildlife fencing.
- Implement wildlife crossing signage (especially between MP 334 – 342).

These recommendations were considered when developing the potential improvements. The safety benefit of the potential improvements was evaluated by using Crash Modification Factors (CMF)s. When combined with probable constructions costs and costs associated with differing crash severities, CMFs provide a basis for cost-benefit analysis.

Ten candidate projects were developed which incorporate various CMFs and enhance access management. The projects were evaluated against the following criteria to determine feasibility and to facilitate prioritization:

- Engineering Features;
- Property Impacts;
- Environmental Compatibility;
- Public Input;
- Safety Impact; and
- Access Management Impact.

Based on the evaluation, projects were prioritized across three horizons: 1) Near-term (5-year), 2) Mid-term (10-year), and 3) Long-term (20-year).

Projects should be implemented based on need, funding opportunities, and other conditions that may change or be unknown at the time this paper was completed. This study serves as the first step in the project development process. The results of this study are preliminary in nature; changes may be necessary as the recommendations advance. The following general steps should be taken to implement the recommendations of this study:

- Finalize the recommendations implementation schedule.
- Incorporate recommendations into existing and future planning documents.
- Complete scoping and final design phases of the project development process. The recommendations illustrated herein are conceptual in nature; formal project scoping will need to be completed, including required typical local, state, and federal agency approvals. Additional research, analysis, coordination, and/or permitting will be required prior to construction. Future design and construction will need to be coordinated with stakeholders and emergency responders.

These recommendations are summarized in **Table E1**.

Table E1 – Project Recommendations

Project	Project Limits (MP)	Scope of Work	Planning Horizon	Estimate of Probable Cost
P1A – Install Raised Median from Butterfield Road to Road 3N and Retime Signal at Road 3N	329.03 – 329.20	Convert TWLTL to 8-foot raised median and construct 5-foot sidewalk on both sides, from Butterfield Road to Road 3N. Mill and overlay existing asphaltic concrete pavement; existing curb and gutter to remain. Retime the existing signal at Road 3N with a 100 second cycle for both peaks, with a protected permitted southbound left-turn, protected only northbound left-turn, and permitted only eastbound and westbound left-turns.	Near-term	\$490,000
P1B – Install Raised Median from Perkinsville Road to Road 3N with Roundabout at Road 3N	329.00 – 329.20	Convert TWLTL to 8-foot raised median and construct 5-foot sidewalk on both sides, from Perkinsville Road to Road 3N. Construct a two-lane roundabout at Road 3N.	Long-term	\$2,010,000
P2 – Widen to Four-Lane Section with Raised Median from Road 3N to Road 4N	329.20 – 330.20	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 3N to Road 4N roundabout. Construct future roundabout at Road 3 1/2N, funded by private development.	Mid-term	\$5,890,000
P3 – Widen to Four-Lane Section with Raised Median from Road 4N to Road 5N and Construct Roundabout at Road 5N	330.20 – 331.28	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 4N roundabout to proposed Road 5N Roundabout. This project could be constructed in phases, with the roundabout at Road 5N as the first phase.	Mid-term	\$8,370,000
P4 – Align Approaches at Road 6N	332.35	Reconstruct the east and westbound approaches at the Road 6N intersection so that they align (offset approximately 70 feet).	Long-term	\$480,000
P5 – Widen to Four-Lane Section with Graded Median from Old Highway 89 to Frontier Road and Construct Roundabouts at Old Highway 89 and Frontier Road	333.41 – 334.50	Widen to a four-lane facility conforming to ADOT's fringe urban typical section, with no curb and a standard width, graded median between Old Highway 89 and Frontier Road. Construct two-lane roundabouts at Old Highway 89 and Frontier Road. This project could be constructed in phases, with either/both roundabouts constructed as the first phase.	Long-term	\$13,190,000

Table E1 – Project Recommendations

Project	Project Limits (MP)	Scope of Work	Planning Horizon	Estimate of Probable Cost
P6 – Construct Left- and Right-Turn Lanes at Little Ranch Road	335.77	Construct left- and right-turn lanes at Little Ranch Road.	Mid-term	\$1,410,000
P7 – Install Lighting at Paulden Post Office	337.05	Install street lighting at the Paulden post office. Cost and CMF assume spot lighting with four poles. Bundling this project with the currently programmed project should be considered.	Near-term	\$90,000
P8 – Construct Roundabout at Big Chino Road	337.70	Construct a two-lane roundabout. This project could be bundled with the roundabout at Bramble Drive or constructed sequentially as needed.	Mid-term	\$4,540,000
P9 – Construct Roundabout at Bramble Drive	338.80	Construct a two-lane roundabout. This project could be bundled with the roundabout at Big Chino Road or constructed sequentially as needed.	Mid-term	\$5,100,000
P10 – Install Wildlife Warning Signage from MP 334 to MP 348	334.00 – 348.00	Install wildlife warning signage from MP 334 to 348.	Near-term	\$3,000

1.0 Introduction

The SR 89 Chino Valley to Forest Boundary Transportation Study (Study) is being conducted by ADOT, in partnership with CYMPO.

1.1. Study Overview

SR 89 is a high-speed, north-south oriented highway located in Yavapai County (County). SR 89 is one of a limited number of regional roadways in the CYMPO area that links the City of Prescott (Prescott) and the Town of Prescott Valley (Prescott Valley) to Interstate 40 (I-40) via the Town of Chino Valley (Chino Valley). This Study is focused on the segment of SR 89 that connects Chino Valley, the community of Paulden, and the Prescott National Forest (PNF).

The population in Chino Valley is anticipated to grow 73% over the next 25 years; employment will increase 100%. Traffic volumes along SR 89 and the Chino Valley area are increasing due to general growth as well as additional commercial and recreational traffic to I-40 and beyond. Many businesses and some residential areas abut SR 89, where there are numerous access points with limited turning-movement accommodations.


Records identified 203 crashes from 2010 to 2015, where there were 62 reported injuries and three fatalities. North of Chino Valley, rugged terrain, steep grades, and other physical features affect traffic flow and limit passing opportunities. Due to area growth, increasing traffic volumes, inadequate turning-movement accommodations, and high traffic speeds, SR 89 is in need of operational and safety improvements.

The purpose of this Study is to develop a strategic plan to improve the safety and operational efficiency of SR 89. The strategic plan will identify a package of improvements to address safety, access, mobility, and capacity issues. The improvements will be prioritized and prepared for implementation in phases as funding becomes available.

1.2. Study Area

The Study Area consists of the segment of SR 89 from milepost (MP) 328.95 to 341.42 that connects Chino Valley, Paulden, and the PNF in Yavapai County. SR 89 is generally a two-lane roadway, except there are four lanes south of Road 3N. SR 89 is a high-speed facility with a varying posted speed of 55 mph to 65 mph north of Road 5 North; to the south, the posted speed varies 45 mph to 55 mph. A map of the Study Area is included as **Figure 1**.

Figure 1 – Study Area



2.0 Relevant Plans and Studies

A review of completed plans and studies encompassing the Study Area was performed and summarized below. Sources and reference information for these documents, along with other data included in this working paper, are cataloged in **Appendix WP1-2**.

2.1. CYMPO Title VI Plan, June 2016

CYMPO recently updated its Title VI Plan, which addresses environmental justice, goals for public involvement, population and demographic profiles of the regions, and provisions for outreach and document translation for limited English proficiency individuals. No protected populations were identified in the Study Area.

2.2. AASHTO U.S. Bicycle Route System, August 2015

The U.S. Bicycle Route (USBR) System is a developing network of bicycle routes aimed at facilitating travel for bicyclists between local streets, communities, and states. Four routes have been recommended in Arizona, including USBR 66, 70, 79, and 90. Alternatives were developed and scored. The recommended route for USBR 79 follows SR 89 from Prescott to I-40.

2.3. CYMPO Regional Transportation Plan Update 2040, April 2015

CYMPO developed the Regional Transportation Plan (RTP) Plan Update 2040 as an update to the 2011 Regional Transportation Plan Update. The communities of Prescott, Prescott Valley, Chino Valley, Dewey-Humboldt, and portions of Yavapai County, and the Yavapai-Prescott Indian Tribe were included. The RTP serves to reprioritize short, medium, and long-term transportation investments through the 2040 planning horizon and adjust performance measures to improve opportunities to obtain federal funding. The RTP indicates widening SR 89 to four lanes south of the Study Area is funded between fiscal year (FY) 2015 and FY2020. Subsequent widening to six lanes from Deep Well Ranch Road to Center Street is included in the FY2025 to FY2040 planning horizon; this segment is also south of the Study Area. The Great Western Extension is included in the FY2025 to FY2040 planning horizon. The Great Western Extension is a new two-lane facility located north of SR 89A and will intersect SR 89 near Road 5 South. Recommended improvements beyond FY2040 include the Chino Valley Extension (see Section 2.8), a new four-lane access controlled road, to serve as an alternate route for SR 89 in the Chino Valley and Paulden areas.

2.4. Statewide Wildlife Crash Analysis and Proposed Action Plan, September 2014

ADOT developed a study assessing wildlife crashes on a statewide basis to address wildlife connectivity and safety. Crash data was obtained from the ADOT crash database and determined the incidence of crashes with wildlife and the proportion of crashes involving wildlife. Highway segments were evaluated in one and five mile increments to identify hotspots. The Plan recommends some type of action for segments with a combined metric of "High" or "Very High." SR 89 scored "high" from MP 340 to 345. Warning signage in both directions is advised.

2.5. Town of Chino Valley General Plan 2014, May 2014

Chino Valley developed its General Plan 2014 to guide long-term planning for the community. The General Plan 2014 identifies existing and future conditions, including land use, transportation, recreation, environment, and planned development. The Chino Valley Vision, established in the General Plan 2014, focuses on expansion and diversification of commercial and residential development while maintaining the town heritage. The General Plan 2014 outlines the goals and strategies of the Chino Valley Vision and serves as a guideline for future decision-making. The General Plan 2014 notes planned improvements along this corridor, including the roundabouts at Road 4N and Perkinsville Road. The General Plan 2014 identifies potential developments, including the Del Rio Springs planned community discussed in Section 3.4.

2.6. 2014 Arizona Strategic Highway Safety Plan, 2014

The Strategic Highway Safety Plan (SHSP), developed by ADOT in coordination with stakeholders, establishes strategies to reduce fatalities and serious injuries on all public roadways. The SHSP serves as the statewide plan, encompassing other state and regional safety plans, to measure the safety performance of public roads based on set goals and objectives. Crash data is analyzed to identify Emphasis Areas that require safety improvements reduce the number of fatalities and serious injuries. The previous Arizona SHSP was adopted in 2007. The SHSP Emphasis Areas should be considered when developing potential improvements to address safety concerns within the Study Area.

2.7. Yavapai County Comprehensive Plan, September 2012


The Yavapai County Comprehensive Plan was developed to guide future development while maintaining the high quality of life and natural environment. Yavapai County includes over 8,000 square miles of land from just north of the Phoenix Metro Area and south of the Grand Canyon. The Comprehensive Plan covers eight elements, including transportation, land use, growth areas, water, energy, open space, environment, and cost of development to guide Yavapai County growth and development. The Comprehensive Plan considers transportation as an essential part of the planning process that guides land use and the compatibility of rural and urban areas. The Comprehensive Plan identifies planned regional roadway projects, including the Great Western/Glassford Extension, which runs adjacent to SR 89 from SR 89A to Road 5S; intersection improvements along SR 89 at Road 4N and Perkinsville Road; and a connection from SR 89 to SR 69.

2.8. Chino Valley Extension Study, February 2009

Chino Valley conducted a corridor feasibility study for the proposed Chino Valley extension, from Chino Valley to north of Paulden. The purpose of the study was to develop alternatives for a corridor east of Chino Valley. Corridor CV8 was the recommended corridor based on the minimal impact to preservation lands and phasing opportunities.

Figure 2 displays the recommended Chino Valley extension as a controlled access highway that serves as an alternative route to SR 89 and SR 89A.

Figure 2 – Recommended Chino Valley Extension



2.9. State Route 89 Access Management Plan, June 1997

This study was unavailable; however, the following excerpt from the *Arizona State Highway Access Policy and Legislation Study*, prepared by Lima and Associates and DMJM Harris in March 2001, summarizes its pertinent recommendations as follows:

The plan was prepared for ADOT, Yavapai County, City of Prescott, and Town of Prescott Valley and was put together by JHK & Associates in June of 1997. The plan covers a corridor of SR 89 from Prescott north to Paulden and the Prescott National Forest Boundary. Because of the corridor's location the access management plan had to address urban, small urban and rural environments in regard to access management. Therefore the plan recommends various strategies for different areas along the corridor, which was divided into six segments. For each of the segments recommendations were made based on the individual segment characteristics. In more detail the following recommendations are made.

Through the Prescott area, south of Granite Dells, the plan identifies four potential locations for future traffic signals. These are spaced approximately 1/2 mile apart. Through Granite Dells, where numerous driveway accesses exist, the plan recommends consolidation of driveways when the land uses change or roadway improvements are performed.

One-half mile spacing between signalized intersections is recommended for the Prescott Airport area, and a list of three potential locations is provided. Between the Airport to Chino Valley, the plan recommends adhering to one-mile spacing of major, signalized intersections and non-major intersections with right-in, right-out, and left-in access at half mile spacing.

Chino Valley is a much more urbanized area with over 200 existing driveways with direct access to SR 89. Therefore, the plan recommends eliminating as many driveways as possible by providing alternate access via town streets and driveway consolidation. The ultimate goal through Chino Valley is major, signalized intersections at one-half mile spacing and non-major intersections with right-in, right-out, and left-in access at one quarter-mile spacing. From Chino Valley to Paulden and the Prescott National Forest boundary, the plan calls for major, signalized intersections to be located at least one-mile apart, and existing access should be consolidated or eliminated when possible.

This study summarizes the recommendations for the SR 89 corridor as shown in **Table 1**.

Table 1 – Summary of SR 89 Access Management Recommendations	
Intersection Spacing	Rural: 1 mile Urban: 1/2 to 1 miles
Alternative Access	Consolidation of driveways; Alternative access;
Method of Access Management	Eliminate driveways if possible

3.0 Current Conditions

3.1. Land Ownership and Jurisdiction

The entire corridor lies within Yavapai County. The southern portion of the corridor is in Chino Valley and the northern portion is part of the Prescott National Forest, as illustrated in **Appendix WP1-1**. Land along the corridor is generally privately owned, although there are pockets of land held by the Arizona State Land Department (ASLD). The Arizona Game and Fish Department (AGFD) has holdings near the corridor, but does not own land immediately adjacent. The corridor passes through both the CYMPO and Northern Arizona Council of Governments (NACOG) planning areas; this boundary follows the PNF boundary, with CYMPO to the south. Land ownership and jurisdiction are shown in **Figure 3**.

3.2. Land Use

Land use within the corridor is rural in nature. Local commercial uses are concentrated south of Road 5N, with predominately undeveloped, rural residential, and the PNF in the northern portion of the corridor, as shown in **Figure 4**. The Drake Cement Plant is roughly five miles north of the Study Area, but is a large commercial facility. Residential development is reviewed in more detail in **Section 3.4**.

Figure 3 – Land Ownership and Jurisdiction





Figure 4 – Land Use



3.3. Zoning

The Study Area includes portions of both Yavapai County and Chino Valley; accordingly, both agencies zoning designations are used within their respective jurisdictions.

The Yavapai County designations shown in **Figure 5** include:

- R1L – Residential; Single Family Limited
- RMM – Residential; Multi-Sectional Manufactured Homes
- R1 – Residential; Single Family
- RCU – Residential; Rural
- RS – Residential and Services
- C1 – Commercial; Neighborhood Sales and Services
- C2 – Commercial; General Sales and Services
- PAD – Planned Area Development

There is a 29 acre PAD near Sweet Valley Road that includes the Depot 89 and a mobile home vendor. There are two small commercial parcels between the BNSF Railway and Big Chino Road (approximately 20 and 5 acres each); otherwise, the entire portion of the corridor within County jurisdiction is zoned for varying density residential uses. The vast majority of the corridor is zoned RCU, or Residential; Rural.

Chino Valley designations shown include:


- OS – Open Space/Resource Conservation
- AR-36 – Agricultural/Residential – 36 Acre Minimum
- AR-5 – Agricultural/Residential – 5 Acre Minimum
- AR-4 – Agricultural/Residential – 4 Acre Minimum
- SR-2.5 – Single Family Residential – 2.5 Acre Minimum
- SR-2 – Single Family Residential – 2 Acre Minimum
- SR-1.6 – Single Family Residential – 1.6 Acre Minimum
- SR-1 – Single Family Residential – 1 Acre Minimum
- SR-0.16 – Single Family Residential – 7,000 Square Foot Minimum lot area
- MR – Multiple Family Residential
- MHP-4 - Mobile/Manufactured home parks (4 Acre Minimum)
- CL – Commercial Light
- CH – Commercial Heavy
- I – Industrial
- PL – Public Land Designation

Zoning along SR 89 within Chino Valley is predominantly for commercial use; however, much of the land north of Road 5N is undeveloped or underdeveloped. Large parcels of land between Road 6N and Bethany Lane are held by the Ranch at Del Rio Springs developers and are zoned CL. Otherwise, varying density residential uses are generally zoned where there is no frontage to SR 89.

3.3.1. Open Zoning Cases

Based upon available County and Chino Valley GIS information, along with input from their staff, there are no major open zoning cases along the corridor.

Figure 5 – Zoning



3.4. Residential Development

The Chino Valley Unified Development Ordinance dictates that preliminary plats expire after three years if the application for the final plat is not submitted; it also states that engineering plans are subject to update if construction has not started one year after approval. Plans are also subject to update if construction is stopped for one year or more. These requirements were not in prior versions of the ordinance, so there are approved plats that are not recorded.

The largest development proposed within the Study Area is the Ranch at Del Rio Springs, a 3,000 acre PAD originally expected to provide 1,226 single-family homes. The development was planned north of Road 5N, headed north toward Old Highway 89 on both the east and west sides of SR 89. The development was initiated in 2000 and zoning reflects commercial and MR1/MHP4 residential. The development is currently inactive; the following summarizes its recent history:


- On September 5, 2000, Council adopted Ordinance Nos. 421 and 432 providing for annexation and rezoning of the subject area.
- On October 26, 2000, Council adopted Ordinance No. 575 approving a Development Agreement with the Ranch at Del Rio Springs.
- On May 26, 2005, Council approved a Final Master Development Plan and adopted Ordinance No. 05-746 approving a First Addendum to the Development Agreement.
- The Citizen Participation protocol resulted in approximately 70 notices being mailed out. The Town received 22 responses in favor, with 20 of those being from Bond Ranch, and one from ADOT stating that: 1) Access points had not been approved and 2) A traffic impact analysis had not been received.
- The Preliminary Plat for Del Rio East – Alpha (Phase I) was approved by the Planning and Zoning Commission with eight stipulations in July 2007. Phase I included 292.2 acres east of SR 89, generally between Road 5 North and Old Highway 89, and provided 163 residential lots (parcels 306-40-038A, 028P and portions of 306-40-038 and 028Q).
- The terms of the Water Resources, Infrastructure, and Management Agreement between Chino Valley and the Ranch at Del Rio Springs ("Agreement") were to expire on February 18, 2008.
- An eighth amendment to the Agreement extended the terms by nine months (December 26, 2008).

No other records were found and a final plat was not submitted.

Approved developments are shown in **Figure 6**. There are no active developments planned along SR 89. Developments near the corridor include:

- **Heritage Pointe** – Parcel 306-13-004H has an approved plat for 75 single family homes (1 acre lots). The development is currently in escrow.
- **Windmill House** (name uncertain) – Parcel 306-05-031N recently approved Planned Area Development (PAD) for 105 apartments.
- **Unnamed Development** – Parcel 306-04-006H was platted for 75 units and has been inactive for over one year.

Figure 6 – Residential Development



3.5. Activity/Employment Centers

There are no major employers within the corridor; it primarily serves as a north-south connection to other areas. The Drake Cement Plant is the nearest notable employer, located roughly five miles north of the Study Area.

3.6. Utilities

Existing utilities in the area include Arizona Public Service (APS), Abra Water Company, Cable One, and UniSource Energy. APS has a 69 kV transmission line that parallels SR 89 and crosses from the east to the west side of the roadway in more than one location, as shown in **Appendix WP1-1**. Other minor utilities are present to serve local needs.

3.7. Transportation Network

3.7.1. Roadway Characteristics

SR 89 is generally a two-lane roadway, except for in the immediate vicinity of the roundabouts at the Road 3 North and Road 4 North intersections. SR 89 is a high-speed facility with a varying posted speed of 55 mph to 65 mph north of Road 5 North; to the south, the posted speed varies 45 mph to 55 mph. SR 89 generally intersects with other public streets at 0.5 mile intervals. Between intersections, there are private access points. Crossing streets of note include Perkinsville Road, Road 3N, Road 4N, and Big Chino Road.

Turn lanes are provided along SR 89 at Rolling Hills Road (northbound left), Midway Drive/Old Highway 89 (northbound left, southbound left), Big Chino Road (northbound left, southbound right), and Bramble Drive/San Francisco Street (northbound left and right, southbound left and right). While no passing lanes are present within the project limits, passing is permitted for at least one direction for approximately 70% of the study area.

The cross section of SR 89 generally consists of a 12-foot lane in each direction and paved shoulders varying between six to ten-feet in width. Curb and gutter replaces the paved shoulders intermittently within the limits of Chino Valley. Beyond the roadway, there are generally recoverable slopes and shallow ditches. There are sections where the road passes through rock cut, including immediately south of the SR 89 intersection with Bethany Lane/Old Highway 89, from the SR 89 intersection with Buffalo Run Road to the SR 89 intersection with Frontier Road, immediately north of the SR 89 intersection with Little Ranch Road, and at approximately MP 340. From MP 340 to the northern end of the Study Area, the roadside grading features a non-recoverable fill slope. From MP 340 to the northern Study Area limits, there are short sections of guardrail in the immediate vicinity of structures or culverts.

The elevation of the roadway through the project limits varies between approximately 4,350 feet and 4,650 feet. The low point is near MP 336. Roadway profile grades are generally less than 3%. Along the corridor, there are spot locations where the profile grade exceeds 3%, but is still less than or equal to 6%. As SR 89 enters the PNF, the profile grade increases to approximately 8%.

There are several structures, both bridges and culverts, along SR 89 within the Study Area. The most notable structure is the grade-separated BNSF Railway crossing approximately 0.3 miles south of the Big Chino Road intersection (MP 337.38) shown in **Figure 7**. The single-span structure has abutment type walls and creates a pinch point along SR 89; the opening width is approximately 40 feet. This structure complicates roadway widening at this location. According to the ADOT Railroad Liaison, a single track crosses SR 89 and carries roughly nine trains a day. It is not known if there are plans for future expansion or if there are any cargo size limitations.



Figure 7 – BNSF Railway Overpass

SR 89 passes over two structures and three culverts. The structures are at MP 333.09 (Del Rio Ranch Bridge) and 335.95 (Big Chino Wash Bridge). The culverts are at MP 334.1, 335.12, and 337.6.

3.7.1.1. Roadway and Structure Condition

Roadway

The roadway pavement condition along SR 89 has been evaluated by ADOT in multiple categories including cracking, patching, flushing, friction, ride, and rutting. Reporting is provided in mile segments.

Cracking ratings are represented as a percentage with 0% corresponding to no discernable cracking and 100% as pervasive cracking. The average 2013, 2014 and 2015 scores within the project area are 4.7%, 5.6%, and 6.9%, respectively. MP 331 and 338 have had the most cracking, with MP 331 having the worst rating over the three-year period in 2015 with a rating of 20%.

Patching ratings are represented as a percentage with 0% corresponding to no discernable patching and 100% as pervasive patching. The only locations with non-zero patching ratings are MP 333 and 336; MP 333 had a rating of 65% in 2014 and 2015 while MP 336 had a rating of 99% in 2014 and 2015.

Flushed pavement has a shiny surface caused by the liquid asphalt separating from the aggregate and moving upward to the surface of the road. The presence of flushing can be indicative of a pavement which has a wearing surface with reduced surface texture. Flushing ratings are one to five, with a rating of five representing the ideal of no discernable flushing. The average flushing rating in 2015 was four. The lowest rated locations were MP 333 and MP 335, both with ratings of 3.5.

Friction ratings are calculated by multiplying the friction coefficient by 100. Friction ratings above 35 are ideal. Every milepost scored above 35 in 2014 (the last year data was available).

Ride ratings are in inches per mile, with lower values indicating a smoother ride. The average ride rating in 2015 was 60.5 with a minimum value of 48 and a maximum value of 77. The worst rated location is MP 341.


Rutting ratings are provided in inches with lower values indicating less rutting. The average rutting rating in 2015 was 0.06 with a minimum value of 0.02 and a maximum value of 0.11. The worst rated location is MP 336.

MP 336 frequently rates worse than the corridor average and has the corridor-worst ratings in patching and rutting.

Structures

Bridges are given a Sufficiency Rating after being evaluated on the condition of the deck, superstructure, substructure, channel, and culvert. The formula to calculate the Sufficiency Rating is determined by the Federal Highway Administration (FHWA) to assess the following attributes of the bridge: Structural Adequacy and Safety, Serviceability and Functional Obsolescence, and Essentiality for Public Use. **Figure 8** depicts a summary of the Sufficiency Rating factors and their relative weights.

Figure 8 – Summary of Sufficiency Rating Factors



ADOT has determined that a Sufficiency Rating of 82 or less triggers the generation of an estimate to determine the costs for needed improvements.

The Del Rio Ranch Bridge (Structure Number 04 20046) was constructed in 2013 and has had no major reconstruction. On its most recent ADOT inspection in 2015, the Del Rio Ranch Bridge scored a Sufficiency Rating of 100.00.

The Big Chino Wash Bridge (Structure Number 04 0979) was constructed 1967 and was partially reconstructed in 2014. On its most recent ADOT inspection in 2015, the Big Chino Wash Bridge scored a Sufficiency Rating of 82.20.

The BNSF Railway overpass (Structure Number 04 1577; MP 337.38), which was constructed in 1961, was inspected in 2015. The ADOT inspection report did not provide a Sufficiency Rating.

The three culverts at MPs 334.1 (Structure Number 4804), 335.12 (Structure Number 4805) and 337.6 (Structure Number 4806) were all inspected by ADOT in 2013 and received identical Sufficiency Ratings of 82.15.

3.7.1.2. Functional Classification of Roads

SR 89 is classified by ADOT as a principal arterial between Prescott and the PNF. Within the limits of Chino Valley, the classification is modified to a Rural Minor Arterial north of Road 4N and an Urban Minor Arterial south of Road 4N.

Crossing streets of note include urban collectors Perkinsville Road, Road 3N, and Road 4N, and minor collector Big Chino Road. Detailed functional classification mapping is shown in **Figure 9 and Figure 10**.

Figure 9 – Yavapai County Functionally Classified Roads





Figure 10 – Chino Valley Functionally Classified Roads



3.7.1.3. Access Management Policies and Guidelines

Access management is the careful control of the location, spacing, design, and operation of public intersections, private driveways, medians and median openings to a roadway. It involves roadway design applications such as median treatments, auxiliary turn lanes and the appropriate spacing of traffic signals. The contemporary practice of access management extends the concept of access design and location control to all roadways – not just limited access highways or freeways. Access management is particularly important along major arterial streets and other principal roads whose primary function is the safe and efficient movement of traffic. The overall benefits of access management include improved roadway operation and safety, preserves market area for businesses, and maintains more efficient freight movement.

Table 2 and **Table 3** summarize pertinent draft ADOT Access Management Guidelines used to assess corridor access spacing. ADOT recommendations in **Table 2** were applied to note locations where access points are not adequately spaced on the same side of the roadway in **Appendix WP1-1**.

Table 2 – ADOT Access Management Guidelines Table 4.1 Connection Spacing Requirements

Connection Type	Minimum Required Spacing without Median			Minimum Required Spacing with Median	
	≤ 45 mph		> 45 mph	≤ 45 mph	> 45 mph
	2-lane rural *	All other			
Driveways	250 ft	440 ft	660 ft	440 ft	660 ft
Intersections (unsignalized)	250 ft	660 ft	1,320 ft	1,320 ft	1,320 ft
Intersections (signalized)	1,320 ft	1,320 ft	2,640 ft	1,320 ft	2,640 ft

* Minimum spacing criteria only applies to two-lane rural roads exhibiting ALL of the following characteristics:

1. Outside of Metropolitan Planning Organization (MPO) boundaries*
2. Current ADT levels < 2,000
3. Peak hour trip generation potential of the proposed development < 50 total peak hour trips

Though permissible by the guidelines in **Table 2**, ADOT District staff have indicated ¼ mile signal spacing in this corridor would create traffic signal coordination challenges and should not be allowed.

Table 3 – ADOT recommended Corner Clearance –without Median

Connection Type	Minimum Required Corner Clearance WITHOUT MEDIAN		
	≤ 45 mph		> 45 mph
	2-lane rural *	All other	
Right-In (upstream only)	125 ft	250 ft	440 ft
Right-Out (downstream only)	125 ft	250 ft	660 ft
Right-In/Right-Out	250 ft	275 ft	660 ft
Full Access (unsignalized)	250 ft	660 ft	1,320 ft
Full Access (signalized)	1,320 ft	1,320 ft	2,640 ft

* Minimum spacing criteria only applies to **2-LANE RURAL** roads exhibiting ALL of the following characteristics:

1. Current ADT levels < 2,000
2. Peak hour trip generation potential of the proposed development < 50 total peak hour trips

Note: It is desirable to maximize the distance between the corner parcel connection and the adjacent intersection. Minimum connection spacing criteria for corner clearance should only be considered when greater spacing cannot be achieved.

The draft ADOT Access Management Guidelines also include recommended spacing for corner clearance where a median is present. This guidance was not needed at this time for the corridor, but is included for reference in **Table 4**.

Table 4 – ADOT recommended Corner Clearance – with Median

Connection Type	Minimum* Required Corner Clearance WITH MEDIAN		
	≤ 45 mph		> 45 mph
	Urban	All other	
Right-In (upstream only)	125 ft	250 ft	440 ft
Right-Out (downstream only)	125 ft	250 ft	660 ft
Right-In/Right-Out	250 ft	275 ft	660 ft
Full Access (unsignalized)	660 ft	1,320 ft	1,320 ft
Full Access (signalized)	1,320 ft	2,640 ft	2,640 ft

1. Minimum connection spacing criteria for corner clearance should only be considered when greater spacing cannot be achieved.
2. Minimum spacing criteria only applies to roads in MPO areas (see Appendix) with high density traffic conditions.
3. It is desirable to maximize the distance between the corner parcel connection and adjacent intersections

The Transportation Research Board's (TRB) *Access Management Manual* (2014) generally recommends that driveway spacing requirements be included as part of "connection spacing" criteria, so that all connections are reviewed concurrently. TRB guidance recommends review of access spacing on opposite sides of a roadway, with different criteria for situations with and without a median.

The National Cooperative Highway Research Program (NCHRP) Report 672, Roundabouts: An Informational Guide (2nd Edition), provides recommendations for access management and roundabouts. It generally directs that driveways not be given direct access to a roundabout, and describes criteria that should be met if direct access is given. It includes general guidance for left-turn lanes downstream from the roundabout. ADOT or TRB guidance for corner clearance at traffic signals should be applied to roundabouts to promote safety and preclude driveways from interfering with intersection operation.

3.7.1.4. Existing Access Control

Appendix WP1-1 provides a comprehensive assessment of the existing access management conditions in the Study Area. Each access point along the corridor was identified through reviewing available aerial mapping and performing site visits in early 2016. Each access point was then categorized into one of the following three access types:

1. RIRO – Only two traffic movements, right-in and right-out, are permitted with a side street or driveway. Intersections are typically controlled by either STOP or YIELD signs on the side street; driveways typically are not signed.
2. Three-Quarter Intersections – Three-quarter intersections provide RIRO and left-in access only and are generally controlled by either STOP or YIELD signs.
3. Full Access Intersection – Full access intersections generally allow all traffic movements on all approaches. These intersections are either STOP controlled on both side street approaches or traffic signal controlled.

Each access point is identified in **Appendix WP1-1** and detailed in tabular form in **Table 5 and Table 6**. Privately owned roads intersecting SR 89 are denoted in **Table 5**; all of the driveways in **Table 6** are privately owned and are presented in the order in which they appear heading north in the corridor to facilitate review with **Appendix WP1-1**. Access spacing was compared to the draft ADOT Access Management Guidelines (November 2014) shown in **Table 2. Appendix WP1-1** illustrates those access points that are more closely spaced than recommended on the same side of the roadway.

Table 5 – Summary of Existing Intersections*			
Cross Street Name	Intersection ID No.	Access Type	Ownership
W Butterfield Road	1	Full Access	Public
Adams Road	2	Full Access	Public
W Palomino Road	3	Full Access	Public
Unnamed Alley	4	Full Access	Private
Road 3 1/2N	5	Full Access	Public
Road 3 1/2N	6	Full Access	Public
Commercial Way	7	Full Access	Public
Industrial Drive	8	Full Access	Public
Jack Dale Drive	9	Full Access	Private
Choctaw Lane	10	Full Access	Public
Staley Lane	11	Full Access	Public
Road 5N	12	Full Access	Public

Table 5 – Summary of Existing Intersections*			
Cross Street Name	Intersection ID No.	Access Type	Ownership
Road 5N	13	Full Access	Public
Road 5 1/2N	14	Full Access	Public
Road 6 N	15	Full Access	Public
Road 6 N	16	Full Access	Public
Del Rio Ranch Road	17	Full Access	Public
Bethany Lane	18	Full Access	Public
Old Highway 89	19	Full Access	Public
<i>Buffalo Run Road</i>	<i>20</i>	<i>Full Access</i>	<i>Private</i>
<i>Livernois Way</i>	<i>21</i>	<i>Full Access</i>	<i>Private</i>
<i>Frontier Road</i>	<i>22</i>	<i>Full Access</i>	<i>Private</i>
<i>El Rocko Lane</i>	<i>23</i>	<i>Full Access</i>	<i>Private</i>
<i>Bald Eagle Trail</i>	<i>24</i>	<i>Full Access</i>	<i>Private</i>
Rolling Hills Road	25	Full Access	Public
<i>Little Ranch Road</i>	<i>26</i>	<i>Full Access</i>	<i>Private</i>
<i>Sweet Valley Road</i>	<i>27</i>	<i>Full Access</i>	<i>Private</i>
Old Highway 89	28	Full Access	Public
Big Chino Road	29	Full Access	Public
Laguna Trail	30	Full Access	Public
Pittsburgh Road	31	Full Access	Public
<i>Verde Ranch Road</i>	<i>32</i>	<i>Full Access</i>	<i>Private</i>
Verde Ranch Road	33	Full Access	Public
Bramble Drive	34	Full Access	Public
<i>Clayton Road</i>	<i>35</i>	<i>Full Access</i>	<i>Private</i>
<i>Old Highway 89</i>	<i>36</i>	<i>Full Access</i>	<i>Private</i>

*Italics denotes private access

Table 6 – Summary of Existing Driveways

Driveway ID No.	Access Type		Driveway ID No.	Access Type		Driveway ID No.	Access Type
W1	RIRO		W10	Full Access		W23	Full Access
W2	Full Access		E21	Full Access		E37	Full Access
E1	RIRO		W11	Full Access		E42	Full Access
E2	Full Access		W12	Full Access		E43	Full Access
E3	Full Access		E22	Full Access		W25	Full Access
W4	Full Access		E23	Full Access		E44	Full Access
E4	Full Access		E24	Full Access		E45	Full Access
W3	Full Access		W13	Full Access		W26	Full Access
W1	RIRO		W14	Full Access		E46	Full Access
E5	Full Access		E25	Full Access		E47	Full Access
W5	Full Access		E26	Full Access		E48	Full Access
E6	Full Access		E27	Full Access		E49	Full Access
E7	Full Access		E28	Full Access		E50	Full Access
E8	Full Access		E29	Full Access		E51	Full Access
E9	Full Access		W15	Full Access		W27	Full Access
W6	Full Access		E30	Full Access		E52	Full Access
E10	Full Access		W16	Full Access		W28	Full Access
W7	Full Access		W17	Full Access		E53	Full Access
E11	Full Access		E31	Full Access		E54	Full Access
E12	Full Access		W18	Full Access		W29	Full Access
E13	Full Access		E32	Full Access		E55	Full Access
E14	Full Access		W19	Full Access		E56	Full Access
E15	RIRO		W20	Full Access		E57	Full Access
E16	RIRO		E33	Full Access		E58	Full Access
E17	Full Access		W21	Full Access		E59	Full Access
W8	Full Access		W22	Full Access		W30	Full Access
E18	Full Access		E34	Full Access		W31	Full Access
W9	Full Access		E35	Full Access		W32	Full Access
E19	Full Access		E36	Full Access		W33	Full Access
E20	Full Access					E60	Full Access

Table 7 identifies driveways that did not meet minimum recommended spacing in the ADOT draft Access Management Guidelines for corner clearance on one side of the road, as summarized in **Table 3**.

Table 7 – Corner Clearance Spacing Less than Recommended			
Northbound		Southbound	
Driveway No.	Cross Street Name	Driveway No.	Cross Street Name
E1	Adams Road	W1	W Butterfield Road
E1, E2, E3, E4, E5	Road 3N	W2	W Palomino Road
E5	Unnamed Alley	W3, W4, W5	Road 3N
E6, E7, E8, E9, E10	Road 3 1/2N	W6	Road 3 1/2N
E14, E15, E16	Road 4N	W6	Commercial Way
E17, E18, E19, E20, E21, E22	Jack Dale Drive	W7	Industrial Drive
E29, E30, E31	Staley Lane	W9, W10, W11, W12, W13, W14	Choctaw Lane
E30, E31	Road 5N	W16, W17	Road 5N
E37, E38, E39, E40, E41, E42, E43	Livernois Way	W23, W24	Buffalo Run Road
E44	Bald Eagle Trail	W24, W25	Frontier Road
E58, E59	Pittsburgh Road	W26	Little Ranch Road
		W30, W31, W32	Verde Ranch Road
		W32, W33	Bramble Drive

3.7.2. Truck and Freight Movement

Both trucks and trains move through the Study Area. The percentage of vehicles that are trucks traveling along SR 89 through the Study Area range from 5% in the south to as high as 14% north of Bramble Drive (MP 338.8).

Trucks which exceed 14 feet in width, 16 feet in height, 120 feet in length, or exceed 250,000 pounds require a Class C permits. In the 13 month period from January 2015 and February 2016, 77 Class C permits were issued for travel through the Study Area.

Trains traverse the Study Area via the BNSF Railway (MP 337.38). The single-span structure supports a single track and carries roughly nine trains a day. It is not known if there are plans for future expansion or if there are any cargo size limitations.

3.7.2.1. Class C Permits

Class C permits are required for loads that exceed 14 feet in width, 16 feet in height, 120 feet in length, and exceed 250,000 pounds. **Table 8** lists the number and type of permits issued between January 2015 and February 2016. Permit data is not available prior to January 2015 due to a change in how ADOT stored permit data in January 2015.

Table 8 – Permits Issued between January 2015 and February 2016	
Permit Type	Number Issued
Single Trip Class C Oversize	59
Single Trip Easy Class C	11
Single Trip Mobile Home OS	7
Single Trip Class C Oversize/Overweight	0

3.7.2.2. Routing Constraints

Several infrastructure limitations both within and external to the study limits may be reducing the number of permit requests. These factors include weight limit restriction at the Hell Canyon Bridge (MP 345.70; restricted to 80,000 pounds). Additional restrictions include the difficulty of loads exceeding 120 feet navigating the roundabouts within and south of the Study Area along SR 89.

3.7.2.3. Critical Length of Grade

Critical length of grade calculations are performed to determine the distance on an effective grade where the speed of heavy vehicles is reduced by 10 mph or greater. The figures provided by AASHTO in the 2011 *A Policy on Geometric Design of Highways and Streets* (Green Book) which are used when calculating the critical length of grade assume an initial speed of 70 mph. A critical length of grade is achieved between MP 339.98 and MP 340.49. The speed data collected for northbound (upgrade) traffic near MP 341 indicate that 63% of vehicles were traveling 65 mph or faster.

3.7.3. Bicycle and Pedestrian Network

Within the limits of Chino Valley, there are intermittent sections of sidewalk immediately adjacent to various roadway intersections. There are no other dedicated pedestrian facilities along SR 89.

While there are no unattached bicycle facilities within the project limits, the 2012 AASHTO Guide for the Development of Bicycle Facilities states that five-foot wide paved shoulders provide cyclists adequate area to maneuver on facilities with vehicular speeds less than 50 mph. Additional shoulder width should be provided along facilities with speeds 50 mph or faster or facilities with heavy truck use. The paved shoulder width along SR 89 is eight-feet or wider from MP 329.3 to MP 340.4 and six-feet wide from MP 340.4 to the northern limit of the Study Area.

3.7.4. Transit Network

Yavapai Regional Transit, Inc. (YRT) provides regular transit service between Prescott, Prescott Valley, and Chino Valley. YRT was originally started in 2009 as Chino Valley Transit and officially became YRT in 2013. The Gold Route extends farther north than any other year-round route; its northern limit is Road 3N, with an allowable one mile route deviation zone in Chino Valley to accommodate individuals with mobility limitations. The Gold Route provides a connection to the Blue and Red Routes, and ultimately Prescott and Prescott Valley. The Blue and Red Routes only operate on Friday.

YRT is providing seasonal service in the summer of 2016 to provide a connection between Paulden and the Chino Valley Pool. The northern limit of the seasonal service is the Paulden Christian Fellowship Church.


3.8. Traffic Analysis

3.8.1. Existing Traffic Volumes

Traffic counts were collected on March 23, 2016. Daily 24-hour counts and turning movement counts for the morning and evening peak hours were collected in the Study Area as shown on **Figure 11**. More detailed traffic count data, including vehicle classification counts, is included in **Appendix WP1-3**.

Daily traffic volumes for the Study Area can be generally characterized as medium in the southern portion of the corridor and low in the north. Daily traffic volumes on SR 89 were approximately 12,900 vehicles north of Road 3N, 9,200 vehicles south of Rolling Hills Road, and 3,800 north of MP 341. Along the corridor, truck percentages range from 5% in the south to as high as 14% north of Bramble Drive.

Figure 11 – Existing Traffic Volumes



3.8.2. Traffic Operational Analysis

Existing capacity analysis was conducted for the existing (2016) conditions at the five intersections identified in **Figure 11**. *HCS* software which uses the *Highway Capacity Manual* methodology was used for all intersections, except the intersection of SR 89 with Road 4N. This intersection is a roundabout; therefore, *SIDRA* software was used to analyze the intersection with *Highway Capacity Manual* methodologies. *HCS* and *SIDRA* results are included in **Appendix WP1-4**.

Table 9 summarizes the 2016 AM and PM peak hour capacity analysis results, which are presented in terms of Level of Service (LOS) and delay. LOS is a qualitative value of how well a roadway or intersection operates. A grading system of A through F is assigned. LOS A represents free-flow traffic operations with little vehicle delay; LOS F represents substantial congestion and vehicle delay. Operations of LOS C and better are typically considered good and acceptable. Operations of LOS D, E or F typically need attention.

Table 9 – 2016 AM & PM Peak Hour Capacity Analysis					
Intersection*	Approach	2016 AM Peak		2016 PM Peak	
		LOS	Delay (sec/veh)	LOS	Delay (sec/veh)
Intersection 1 SR 89 & Road 3N	Eastbound	D	39.1	D	42.8
	Westbound	D	38.6	D	41.9
	Northbound	A	8.9	A	7.7
	Southbound	B	11.7	A	9.4
	Overall	B	19.0	B	14.6
Intersection 2 SR 89 & Road 4N	Eastbound	A	5.7	A	5.0
	Westbound	A	4.8	A	6.0
	Northbound	A	5.0	A	6.8
	Southbound	A	6.4	A	5.7
	Overall	A	5.8	A	6.3
Intersection 3 SR 89 & Rolling Hills Road	Eastbound	B	11.9	B	12.0
	Northbound	A	1.0	A	0.4
	Southbound	A	0.0	A	0.0
	Overall	A	1.2	A	0.8
Intersection 4 SR 89 & Big Chino Road	Eastbound	B	11.6	B	13.3
	Northbound	A	2.1	A	3.7
	Southbound	A	0.0	A	0.0
	Overall	A	4.4	A	3.7
Intersection 5 SR 89 & Bramble Drive	Eastbound	A	9.1	B	10.6
	Westbound	B	11.2	C	15.0
	Northbound	A	1.0	A	3.6
	Southbound	A	0.0	A	0.2
	Overall	A	3.7	A	3.0

*Refer to **Figure 11** for intersection number.

The analysis indicates that the intersections operate very well with an overall LOS A or B. All approaches operate at LOS C or better except the intersection of SR 89 and Road 3N. However, at this location, the side street approaches still operate at an acceptable LOS D which is typical for a signalized intersection with significantly lower volumes on the minor approaches compared to the mainline.

3.8.3. Crash Analysis

Crash data for the five-year period from November 30, 2010 to November 30, 2015 was obtained from the Accident Location Identification Surveillance System (ALISS) database. Within this period, 203 crashes occurred within the Study Area. There were 41 crashes in 2011, 36 crashes in 2012, 48 crashes in 2013, and 40 crashes in 2014. There were 5 crashes and 33 crashes in the partial years 2010 and 2015, respectively. 65 of the 203 crashes (32%) resulted in death or injury, which is consistent with the statewide average injury crash percentage for 2010 to 2014 (32.4%). There were three fatalities reported during the 5-year study period. A summary of total crashes is provided in **Table 10**.

Recently, a fatal crash occurred at MP 335 on February 25, 2016; due to its severity, it will be included in the crash review, but excluded from statistical analysis. It is shown in **Appendix WP1-1**. It was a rear end crash during daylight hours.

A roundabout was constructed at Road 4N and completed in September 2015. A roundabout was constructed at Perkinsville Road and recently completed. The effects of these improvements are not reflected in the crash data, as the analysis period narrowly overlaps the completion of the roundabout at Road 4N.

Crash mapping, including the crash type, severity, and location, is shown in the map book in **Appendix WP1-1**. A crash heat map indicating crash density within the corridor is shown in **Figure 12**. There is a higher crash density in the southern portion of the corridor.

Table 10 – Crash Severity			
Crash Severity	Number	SR 89%	Statewide Average %*
Fatal	3	1.5%	0.69%
Injury	62	30.5%	31.74%
Property Damage Only	138	68.0%	67.57%
Total	203	100.0%	100.0%

*Average of all crashes from 2010-2014

Figure 12 – Crash Heat Map




Table 11 compares the manner of collision in multi-vehicle crashes in the Study Area with the 2014 statewide averages. Within the corridor, rear end, left turn, and sideswipe (same direction) crashes are the most prevalent. Left turn and sideswipe (opposite direction) crashes exceed the 2014 statewide average crash rate for these crash types.

Table 11 – Multiple Vehicle Crashes			
Type of Crash	Number	SR 89%	2014 Statewide Average %
Rear End	49	24.1%	46.0%
Left Turn	32	15.8%	14.9%
Sideswipe (Same Direction)	17	8.4%	13.2%
Angle	11	5.4%	16.2%
Sideswipe (Opposite Direction)	7	3.4%	1.4%
Head On	3	1.5%	1.8%
Other	3	1.5%	
Unknown	1	0.5%	
Total	123	60.6%	

Table 12 compares the remaining first harmful event with the statewide average for rural areas. Some of these crashes included more than one vehicle. Fixed object, animal, and other non-fixed object crashes were the most prevalent, with both fixed object and animal crashes exceeding the statewide rural average. Other non-collision crashes also exceeded the statewide rural average.

Table 12 – Other Vehicle Crashes			
Type of Crash	Number	SR 89%	2014 Statewide Rural Ave. %
Fixed Object	39	19.2%	18.3%
Animal	15	7.4%	7.2%
Other Non-fixed Object*	10	4.9%	5.5%
Overturning	9	4.4%	8.1%
Other Non-collision**	5	2.5%	2.0%
Pedestrian	1	0.5%	0.7%
Other	1	0.5%	
Total	80	39.4%	

*Includes Collision with Parked Vehicles, Trains, Railway Vehicles, and Work Zone Equipment

**Includes Vehicle Immersion, Jackknife, and Cargo Loss or Shift

As indicated in **Table 13**, the majority of crashes in the corridor occur on Friday, which is closely followed by Saturday and Wednesday. Statewide, there are fewer crashes on Saturday and Sunday than any other day of the week. DUIs were issued in 4.4% of crashes in the corridor (9 crashes) which is on par with the statewide average of crashes involving alcohol (4.42%). Of these DUI-related crashes, 5 occurred on Friday. In 24 of the 203 total crashes, the driver was cited for distracted driving; 8 (33.3%) of these occurred on Wednesday.

Table 13 – Crash Distribution by Day		
Day of Week	Number	%
Friday	41	20.2%
Saturday	36	17.7%
Wednesday	35	17.2%
Monday	25	12.3%
Tuesday	25	12.3%
Thursday	24	11.8%
Sunday	17	8.4%
Total	203	100.0%

3.8.3.1. Segmented Crash Analysis

As described in Section 3.0, the character of the corridor changes substantially north of Road 5N. The crash characteristics were evaluated from Road 5N south, including crashes at the intersection of Road 5N. Crashes were also evaluated from Road 5N north, excluding crashes at the intersection of Road 5N.

3.8.3.1.1. Crash Analysis for Study Area South of Road 5N

As shown in **Table 14**, rear end, left turn, and sideswipe (same direction) are the most prevalent crash types south of Road 5N. Left turn crashes are 1.5 times the 2014 statewide average. Sideswipe (same direction) crashes slightly exceed the statewide average. While there are fewer total sideswipe (opposite direction) crashes, 5.2%, the occurrence is over three times the statewide average. 12.4% of crashes within this extent are single vehicle crashes.

Table 14 – Crash Characteristics South of Road 5N			
Type Of Crash	Number	S of Road 5N SR 89%	2014 Statewide/ Statewide Rural Ave.%
Rear End	31	32.0%	46.0%
Left Turn	22	22.7%	14.9%
Sideswipe (Same Direction)	13	13.4%	13.2%
Fixed Object	10	10.3%	18.3%
Angle	8	8.2%	16.2%
Sideswipe (Opposite Direction)	5	5.2%	1.4%
Overturning	2	2.1%	8.1%
Other Non-Collision**	1	1.0%	2.0%
Animal	1	1.0%	7.2%
Other	3	3.1%	
Unknown	1	1.0%	
Total	97	100.0%	

*Includes Collision with Parked Vehicles, Trains, Railway Vehicles, and Work Zone Equipment

**Includes Vehicle Immersion, Jackknife, and Cargo Loss or Shift

Crashes were fairly evenly distributed in the northbound and southbound directions, with 29.9% of crashes southbound and 38.1% traveling northbound; crashes reported as east, west, southwest, northwest, northeast, and unknown accounted for 32.0% of crashes.

As shown in **Table 15**, most crashes occurred at intersections (not the segment in between) within this portion of the corridor. Crash data was collected from 2010 to 2015; since that time, roundabouts were constructed at Road 4N and Perkinsville Road. Crash data indicated conditions before these facilities were built. Characteristics of the other intersections have not changed. Road 3N is signalized. There is a two way left turn lane at Palomino Road. There is a horizontal curve at Road 5N and the east and westbound approaches are offset; no turn lane is provided.

Table 15 – Top Five Crash Locations South of Road 5N		
Location	Number	% of Total
Road 3 North	22	22.7%
Road 4 North	20	20.6%
Perkinsville Road	15	15.5%
Palomino Road	13	13.4%
Road 5 North	8	8.3%
Total	78	80.4%

Table 16 reflects crash characteristics south of Road 5N, with crashes at Perkinsville Road and Road 4N removed from the analysis to allow review of the corridor, excluding the recently improved intersections. Rear end, left turn, and fixed object crashes are the most prevalent. The percentage of left turn and sideswipe (opposite direction) exceed the statewide averages (1.7 and 5.6 times the statewide average, respectively).

Table 16 – Crash Characteristics South of Road 5N Excluding Perkinsville Road and Road 4N			
Type Of Crash	Number	S of Road 5N SR 89%	2014 Statewide/ Statewide Rural Ave.%
Rear End	22	35.5%	46.0%
Left Turn	16	25.8%	14.9%
Fixed Object	6	9.7%	18.3%
Sideswipe (Opposite Direction)	5	8.1%	1.4%
Sideswipe (Same Direction)	5	8.1%	13.2%
Angle	3	4.8%	16.2%
Overturning	1	1.6%	8.1%
Other Non-Collision**	1	1.6%	2.0%
Animal	1	1.6%	7.2%
Other	2	1.6%	
Total	62	100.0%	

*Includes Collision with Parked Vehicles, Trains, Railway Vehicles, and Work Zone Equipment


**Includes Vehicle Immersion, Jackknife, and Cargo Loss or Shift

The distribution of crashes for light conditions is comparable to the 2014 statewide averages, as shown in **Table 17**.

Table 17 – Crash Lighting South of Road 5N			
Light Conditions	Number	S of Road 5N SR 89%	2014 Statewide Average %
Daylight	81	83.5%	72%
Dark – Not Lighted	9	9.3%	6%
Dusk	4	4.1%	3%
Dark – Lighted	2	2.0%	17%
Dark – Unknown Lighting	1	1.0%	1%
Total	97	100.0%	

The hourly crash distribution south of Road 5N is shown in **Figure 13**. No crashes were observed between 8pm and 6am; 2pm is the observed peak hour for crashes. Traffic counts at Road 3N indicate volumes are very low between 8pm and 6am (roughly 8% of total daily trips); AM and PM peak hours are 6:30am and 4pm.

Figure 13 – Hourly Distribution of Crashes South of Road 5N



In general, crashes south of Road 5N are clustered around existing intersections. Access spacing often exceeds the density recommended in the draft ADOT Access Management Guidelines. Left turn lanes are provided in some locations; there are no medians other than at the roundabout approaches. The speed limit was recently reduced in this area, but speed may still be a contributing factor.

3.8.3.1.2. Crash Analysis for Study Area North of Road 5N

As shown in **Table 18**, fixed object, rear end, and animal collisions are the most prevalent crash types north of the intersection at Road 5N; 54.7% of crashes are single vehicle crashes. Fixed object and animal crashes are 1.5 and 1.75 times the statewide average, respectively. Drivers in

12 of the 29 fixed object crashes (41.3%) were either cited for exceeding the lawful speed or driving at speed too fast for conditions.

Table 18 – Crash Characteristics North of Road 5N			
Type of Crash	Number	N of Road 5N SR 89%	Statewide/ Statewide Rural Ave.%
Fixed Object	29	27.4%	18.3%
Rear End	18	17.0%	46%
Animal	14	13.2%	7.2%
Left Turn	10	9.4%	14.9%
Other Non-fixed Object*	10	9.4%	5.5%
Overtaking	7	6.6%	8.1%
Sideswipe (Same Direction)	4	3.8%	13.2%
Head On	3	2.8%	1.8%
Angle	3	2.8%	16.2%
Sideswipe (Opposite Direction)	2	1.9%	1.4%
Other Non-collision**	3	2.8%	2.0%
Pedestrian	1	0.9%	1.0%
Other	2	1.9%	
Total	106	100.0%	

*Includes Collision with Parked Vehicles, Trains, Railway Vehicles, and Work Zone Equipment

**Includes Vehicle Immersion, Jackknife, and Cargo Loss or Shift

Crashes were fairly evenly distributed in the northbound and southbound directions, with 42.5% of crashes southbound and 49.1% traveling northbound; crashes reported as eastbound and westbound accounted for 8.4% of crashes.


There was a higher occurrence of nighttime crashes than the statewide average (32% compared to 23%), as shown in **Table 19**.

Table 19 – Crash Lighting North of Road 5N			
Light Conditions	Number	N of Road 5N SR 89%	Statewide Average %
Daylight	67	63.2%	72%
Dark – Not Lighted	33	31.1%	6%
Dawn	3	2.8%	2%
Dusk	2	1.9%	3%
Dark – Lighted	1	1.0%	17%
Dark – Unknown			1%
Total	106	100.0%	100%

The hourly crash distribution north of Road 5N is shown in **Figure 14**. More crashes occurred at 3pm than any other time of day. Traffic counts indicate the PM peak hour occurs at 4pm. Speed data was also gathered and indicates that nearly 90% of southbound vehicles (all times of day)

are speeding north of MP 341, with 16% exceeding 10 mph over the posted speed. Over 60% of northbound vehicles at the same location are speeding, with nearly 5% exceeding 10mph over the posted speed.

Figure 14 – Hourly Distribution of Crashes North of Road 5N



In general, the crashes north of Road 5N are either clustered around existing intersections or are single vehicle crashes involving an animal or run off the road (fixed object). A disproportionate number of crashes occur at night compared to the statewide average. This area includes a portion of the PNF and is in close proximity to the Big Chino Wash and other 404 designated washes. The presence of these natural resources likely attracts wildlife.

4.0 Environmental Considerations

4.1. Natural Resources

Based on an aerial review of the Study Area, the majority of the corridor lies within the Plains and Great Basin Grassland Biotic Community (Brown 1994) with the northern-most portion extending into Great Basin Conifer Woodland (Brown 1994). Geological formations vary and include early Pleistocene to latest Pliocene surficial deposits; Pliocene to late Miocene basaltic rocks; undivided Quaternary surficial deposits; and Mississippian, Devonian, and Cambrian sedimentary rocks (Ludington et. al 2005). Soils within the Study Area include Mesic Semiarid soils of the Pasura-Abra-Lynx, Cabezon-Thunderbird-Springerville, Tortugas-Purner-Jacks, and Pastura-Poley-Partri Associations (Hendricks 1985).

The landscape throughout the Study Area is primarily open grassland with sparsely scattered junipers (*Juniperus spp.*). Understory vegetation includes scattered shrubs and succulents such as saltbush (*Atriplex spp.*), yucca (*Yucca spp.*), and cholla (*Cylindropuntia spp.*). The northern portion of the Study Area, as it enters Great Basin Conifer Woodland, consists of more dense and uniformly distributed stands of juniper and includes an understory of shrubs such as cliffrose (*Purshia spp.*) and wolfberry (*Lycium spp.*).

4.2. Water

Several ephemeral drainages bisect SR 89 throughout the Study Area, including an ephemeral/intermittent portion of the Big Chino Wash that crosses SR 89 near MP 336.00. However, the stretch of the Big Chino Wash that bisects the Study Area does not contain riparian or wetland vegetation, as the banks of the river are vegetated with only grasses and forbs. Therefore, there are no riparian corridors, wetlands, or perennial or semi-perennial sources of water within the Study Area.

All surface waters within the Study Area are ephemeral and no perennial drainages or permanent open waters are present. The primary drainage features in the Study Area are the Big Chino Wash, which flows in an easterly direction, and Little Chino Wash, which generally flows north and is a tributary to the Verde River. Several additional unnamed drainage features that would likely be considered waters of the U.S. and would be under the U.S. Army Corps of Engineers (USACE) jurisdiction are also present within the Study Area. All drainage features within the area flow toward the Big Chino Wash, which crosses SR 89 at approximately MP 335.96. Terrain throughout the Study Area is fairly flat, causing storm water runoff to collect in surface depressions rather than directionally flowing through the area. Several of these surface depressions are located within the Study Area and are documented as wetland and ephemeral pond features by the US Fish and Wildlife Service National Wetland Inventory database. Field investigation of these features would be necessary to determine if they have the soil, vegetative, and hydraulic attributes that would classify them as wetlands under the jurisdiction of the USACE.

4.3. Fish, Wildlife, and Plants

Species lists from the AGFD, U.S. Fish and Wildlife Service (USFWS), and PNF were obtained to determine special status species potentially occurring in the vicinity of the Study Area.

4.3.1. Fish

Several native fish species are known to occur in the vicinity of the Study Area along the Big Chino Wash. The Gila longfin dace (*Agosia chrysogaster chrysogaster*), spikedace (*Meda fulgida*), desert sucker (*Catostomus clarkii*), Sonora sucker (*Catostomus insignis*), razorback sucker (*Xyrauchen texanus*), headwater chub (*Gila nigra*), and roundtail chub (*Gila robusta*) were identified as potentially occurring in the vicinity of the Study Area. However, there are no adequate water sources present within the Study Area; thus, native fish species are not anticipated to be impacted.

4.3.2. Wildlife

The black-footed ferret (*Mustela nigripes*), northern Mexican gartersnake (*Thamnophis eques megalops*), western yellow-billed cuckoo (*Coccyzus americanus*), bald eagle (*Haliaeetus leucocephalus*), golden eagle (*Aquila chrysaetos*), and western burrowing owl (*Athene cunicularia hypugaea*) have potential to occur within the vicinity of the Study Area. Suitable habitat for the black-footed ferret includes grassland plains in association with prairie dog colonies. However, the Study Area is located outside of the current distribution of the black-footed ferret. The nearest occupied habitat for black-footed ferret is located over 40 miles northwest in the 10(j) experimental non-essential population within Aubrey Valley. Furthermore, based on an aerial review of the Study Area, it does not appear that any prairie dog colonies are present along the corridor. Suitable habitat for the yellow-billed cuckoo and northern Mexican gartersnake includes large blocks of riparian woodlands and streamside gallery forests. However, no adequate water sources or riparian woodlands are located within the Study Area. The nearest riparian corridor is located approximately two miles east of the Study Area at the confluence of Granite Creek and the Verde River. Potential improvements are not anticipated to effect to yellow-billed cuckoo and the northern Mexican gartersnake. The open landscape of the Study Area does not contain large cliffs suitable for nesting eagles; however, few tall trees are present near Sullivan Lake and on private property that may provide suitable nesting habitat for eagles. Eagles are known to occur within the vicinity of the Study Area and a bald eagle nest site has been documented near Sullivan Lake. Potential future improvements to SR 89 would not result in a decline in prey populations, or hinder bald or golden eagle foraging habits or movement through the study corridor. If an eagle nest is located adjacent to the Study Area, noise impacts may occur from potential future projects if conducted during the breeding season.

Suitable habitat for the western burrowing owl consists of variable, open well-drained grasslands, steppes, deserts, prairies, and agricultural lands, often associated with burrowing mammals. The open grasslands throughout much of the Study Area provide suitable habitat for the western burrowing owl. Therefore, pre-construction surveys for burrowing owls would be needed prior to any ground disturbing activities. Western burrowing owls are protected by the federal Migratory Bird Treaty Act, and possible future improvements within the study corridor resulting in ground disturbance have the potential to result in injury or death to eggs, young, or adult burrowing owls. Therefore, the project has the potential to result in "take" of birds protected by the Migratory Bird Treaty Act.

Possible future improvements to SR 89 have the potential to result in "take" of roosting bats and nesting migratory birds. Suitable habitat for roosting bats and nesting swallows is present along bridge structures throughout the study corridor. In order to avoid impacts to bats and migratory

birds, bridge structures within the study corridor should be inspected for nesting birds and roosting bats prior to conducting bridge work. Additionally, vegetation clearing activities conducted within the migratory bird breeding season (March 15 – August 31) have the potential to result in “take” of nesting migratory birds. Therefore, vegetation removal, involving the removal of trees, should be conducted outside of breeding bird season in order avoid any restrictions. If vegetation removal must occur within breeding bird season, mitigation measures should be implemented in order to reduce impacts to nesting birds.

4.3.3. Plants

Two PNF sensitive species, Rusby’s milkwort (*Rhinotropis rusbyi*) and Verde Valley Sage (*Salvia dorrii mearnsi*), were documented as occurring within three miles of the Study Area. Suitable substrate for Rusby’s milkwort includes sandy flats and limestone bedrock, rock, gravel and silt within pinyon – juniper woodland. Pockets of suitable habitat are present throughout the Study Area. Suitable habitat for Verde Valley sage includes red-brown clay and sandy soil of Supai/Hermit Formation and Redwall Limestone within Pinyon – Juniper Woodland. Suitable habitat is present along the northern portion of the Study Area. Potential future improvements to the study corridor resulting in vegetation removal may impact individuals if present.

Plants protected by the Arizona Native Plant Law may be impacted by potential future improvements within the corridor. Therefore, to ensure protected native plants are not impacted, mitigation measures should be implemented during future projects.

4.4. Critical Habitat

Critical habitat for five federally listed species was identified as occurring within three miles of the Study Area. Designated critical habitat for the spikedace and loach minnow (*Tiaroga cobitis*); and proposed critical habitat for the narrow-headed gartersnake (*Thamnophis rufipunctatus*), northern Mexican gartersnake, and yellow-billed cuckoo are found 0.35 miles east of the Study Area along the Verde River. However, critical habitats are located outside of the Study Area and therefore are not anticipated to be impacted by potential future improvements to SR 89.

4.5. Wildlife Connectivity

The AGFD On-line Environmental Review Tool receipt included a standard response regarding local or regional needs of wildlife movement, connectivity, access to habitat needs and design of various roadway features such as culverts and bridges. ADOT, AGFD, the Federal Highway Administration and representatives from other agencies have completed a Wildlife Linkages Assessment to address important wildlife movement corridors in Arizona. The study corridor lies within two potential linkage zones (PLZ) and one linkage design. The East – West PNF PLZ #35 occurs along SR 89 between MP 328.95 and MP 339.80 and the Big Black Mesa – Hell Canyon PLZ #22 occurs from MP 339.80 to MP 341.42. Additionally, the study corridor occurs within the Granite Mountain – Black Hills Linkage Design between MP 335.25 and MP 337.15 as well as MP 338.92 and MP 339.95.

4.6. Cultural Resources

The SR 89 right-of-way (R/W) corridor within the Study Area, between MP 328.95 and MP 341.42, has been previously surveyed for cultural resources as summarized in **Table 20**. In

addition, a ½-mile buffer on each end of the project limits (between MP 328.45 to MP 341.92) and a ½-mile buffer east and west of the SR 89 corridor was researched.

The SR 89 corridor (including the buffer zone) between MP 328.45 and MP 331.30 is developed with numerous residences and businesses located along both sides of the roadway. Between MP 331.30 and MP 337.70, the corridor is primarily undeveloped agricultural fields with small, scattered pockets of developed residential areas. The area between MP 337.70 and MP 338.75 is again developed (residences), but to a lesser degree than between MP 328.95 and MP 331.30. The final stretch of the SR 89 study corridor, between MP 338.75 and MP 341.42 (including the buffer zone) is almost entirely undeveloped.

Two prehistoric artifact scatters are located within the SR 89 R/W. One scatter is eligible for inclusion in the National Register of Historic Places (NRHP) under Criterion D; the NRHP eligibility of the other scatter is undetermined. One additional prehistoric artifact scatter (NRHP eligible - Criterion D) is located within the ½-mile buffer research area. All three sites would require testing and/or data recovery if they cannot be avoided by any potential project.

Five abandoned segments of historic SR 89 are located within and outside the R/W corridor. Historic SR 89 is overall eligible for inclusion in the NRHP under Criterion D, and is part of the Historic State Highway System (HSHS). The majority of SR 89, within the Study Area, has been widened and modernized. Four of the five abandoned segments are non-contributing components to the overall eligibility of the site. The fifth segment is a contributing component. HSHS documentation of the portion of SR 89 that has not been widened and modernized, and contributing segments that would be affected by any potential project, is recommended.

According to the AZSITE database, the historic Santa Fe, Prescott & Phoenix Railway line is located approximately 350 feet east of SR 89, between MP 336.65 and MP 336.90. The site is overall eligible for inclusion in the NRHP under Criteria A and D. If the historic railway line cannot be avoided, research would need to be conducted to determine if the affected segment is a contributing or non-contributing component.

Historic buildings and structures are located along SR 89 throughout the Study Area. The most notable are Del Rio Springs (ca. 1900), Verde River Bridge (1923), and Sullivan Lake Dam (1938), which are all located approximately ½ mile east of the SR 89 corridor between Chino Valley and Paulden. A comprehensive historic building survey of the area completed in 1995 identified 21 properties that were potentially eligible for the NRHP, but a brief survey of Yavapai County Assessor records indicated that most of these buildings no longer exist. As the study is now more than 20 years old, a re-evaluation of these properties is recommended to determine NRHP eligibility and the impact of any project on these historic buildings/structures.

As there are many undeveloped/undisturbed parcels along both sides of SR 89 within the Study Area, it is recommended that those parcels be resurveyed for cultural resources since the SR 89 R/W was surveyed 17 to 21 years ago. New R/W and Temporary Construction Easement (TCE) parcels would also require a new cultural resource survey.

**Table 20 – Summary of Cultural Resource Surveys Previously Conducted within 0.5 Miles of the SR 89 R/W
Between MP 328.45 and MP 341.92**

Project Name	Location	Number of Sites	Reference
US 89 Right-of-Way	MP 328.45 – MP 338.65	2	Spalding et al. (PMDR) 1994
SR 89, Road 3 North and Perkinsville Road	MP 328.95 – MP 329.19	0	Berg (ACS) 1999
Intersection Improvements, SR 89/Perkinsville Rd	MP 329.27 – MP 329.46	1	Fenicle (EcoPlan) 2012
Intersection Improvements, SR 89/Road 4 North	MP 330.46 – MP 330.83	1	Fenicle (EcoPlan) 2012
Addendum Class III Survey for Geotechnical Access	MP 333.00 – MP 333.27	1	Lundin (HDR) 2012
Private Land Adjacent to SR 89	MP 335.19 – MP 335.29	0	Walsh (Entranco) 2001
TCE at Rolling Hills Road and SR89	MP 335.25 – MP 335.30	0	LaFond and Folb (EcoPlan) 2001
SR89 Right-of-Way and Scenic Setback	MP 338.00 – MP 341.92	4	Spalding (PMDR) 1998
Proposed Widening of SR 89 in Paulden	MP 337.00 – MP 338.80	2	Strohmayr (EcoPlan) 2004
Historic Resource Survey of Chino Valley	MP 328.45 – MP 341.92	21	Stein (SWCA) 1995

4.7. Hazardous Materials

Databases maintained by the Arizona Department of Environmental Quality (ADEQ) and US Environmental Protection Agency (EPA) were reviewed to determine the presence of any known hazardous materials sites or areas of concern. One large quantity generator, Performance Automotive Group at 3651 N SR 89, Chino Valley, AZ 86323 was identified in the database search. This site is involved in plating, coating, or anodizing activities, which generate 1,000 kilograms per month or more of hazardous waste or more than one kilogram per month of acutely hazardous waste. This site listing does not indicate any violation, leak, or spill has occurred at this location. Two underground storage tanks (UST) are located at Paulden Park Place at 23310 N SR 89, Paulden, AZ 86334. Two other tanks were removed from this location in 1993. No records of any spills or incidents were identified in the Study Area.

The ADOT Bridge Record indicates that there are six major structures located in the Study Area including the Del Rio Ranch Bridge (MP 333.09), the Big Chino Wash Bridge (MP 335.95), and the Paulden ATSF RR UP bridge (MP 337.38) as well as three major reinforced concrete box (RCB) structures. If any improvements or modification of these structures would occur in future projects, they would require testing to determine if any asbestos-containing materials (ACM) are present. Any modification or demolition of these structures would require the completion and submittal of a National Emission Standards for Hazardous Air Pollutants (NESHAP) notification to ADEQ. If ACM is detected in the structures to be affected, an Asbestos Removal and Disposal Plan for the removal of the material must be completed, approved, and implemented.

Any painted surfaces, including structures and roadway striping, that would be affected by any future projects would require testing to determine if the paint includes lead above regulatory thresholds. If lead is detected in amounts above regulatory limits, appropriate treatment or mitigation would apply.

4.8. Air and Noise

The Study Area is not located within any areas designated by ADEQ as a non-attainment or maintenance area for any criteria pollutant.

The ADOT Noise Abatement Policy and FHWA Noise Abatement Criteria identify the level of allowable traffic noise level for different categories of land use and activities. For homes, churches, schools, and parks, ADOT will consider mitigation for receivers when predicted traffic noise levels are 64 dBA or higher. ADOT will consider mitigation if noise levels are predicted to increase substantially. A substantial noise level increase is equal to or greater than 15 dBA. Within the Study Area, there are numerous residences and several churches. A noise analysis would be required for any future projects which changes the horizontal or vertical alignment of the roadway or adds capacity.

4.9. Socioeconomic Profile

The demographic composition of the Study Area was calculated using the *US Department of Commerce, Bureau of the Census 2010-2014 American Community Survey 5-year estimates*. Population and demographic information is summarized in **Table 21**. Population data were gathered at the Census Tract level as well as populated places within the Study Area, and

Yavapai County. Census tracts are small, relatively permanent statistical subdivisions of a county for tallying census information and do not cross county boundaries. They are delineated with the intention of being maintained over a long period to allow statistical comparisons from census to census. The size of census tracts varies depending on the population density of the area. The Study Area traverses Census Tracts 2.02, 2.04, and 21, which extend over a much larger area than the Study Area.

According to the US Bureau of Census data the Paulden census-designated place (CDP) has a Hispanic percentage of 29.4%, compared with the overall Study Area percentage of 16.8% and Yavapai County at 13.9%. Census Tract 21 has a higher percentage of people below the poverty level (45.80%) than Yavapai County (16.06%). No substantial protected populations, meaning those populations greater than 50 percent of a population, are located within the Study Area, as summarized in **Table 22**.

The recently adopted CYMPO Title VI Plan provides provisions for outreach and document translation to limited English proficiency populations, as well as Title VI measures for transportation planning projects.

Table 21 – 2014 Population and Racial Demographics

Area	Total Population	White alone		Black or African American alone		American Indian and Alaska Native alone		Asian alone		Native Hawaiian and Other Pacific Islander alone		Some other race alone		Two or more races		Hispanic or Latino	
		#	%	#	%	#	%	#	%	#	%	#	%	#	%	#	%
202	8,012	7,536	94.1	11	0.1	189	2.4	34	0.4	0	0.0	111	1.4	131	1.6	688	8.6
204	7,083	6,749	95.3	78	1.1	83	1.2	59	0.8	0	0.0	114	1.6	0	0.0	1,536	21.7
21	2,385	2,063	86.5	12	0.5	8	0.3	0	0.0	0	0.0	173	7.3	129	5.4	717	30.1
All Block Groups	17,480	16,348	93.5	101	0.6	280	1.6	93	0.5	0	0.0	398	2.3	260	1.5	2,941	16.8
Yavapai County	213,689	196,410	91.9	1,188	0.6	4,094	1.9	1,783	0.8	15	0.0	5,529	2.6	4,670	2.2	29,702	13.9
Chino Valley	10,879	10,248	94.2	21	0.2	198	1.8	34	0.3	0	0.0	246	2.3	132	1.2	953	8.8
Paulden	4,909	4,576	93.2	35	0.7	83	1.7	59	1.2	0	0.0	145	3.0	11	0.2	1,442	29.4

Table 22 – Age 60 Years and Over, Below Poverty Level, Disabled, and Female Head of Household Populations

Area	Total Population	Age 60 Years and Over		Below Poverty Level		Disabled		Female head of Household	
		#	%	#	%	#	%	#	%
202	8,012	2,677	33.4	1196	14.99	1906	23.8	360	10.8
204	7,083	1,841	26.0	1796	25.36	1582	22.3	173	6.3
21	2,385	677	28.4	1086	45.80	393	16.5	69	7.3
All Block Groups	17,480	5,195	29.7	4,078	23.40	3,881	22.2	602	8.6
Yavapai County	213,689	91,531	42.8	33,813	16.06	38,596	18.2	8,524	9.3
Chino Valley	10,879	3,666	33.7	1,890	17.45	2,602	23.9	473	10.7
Paulden	4,909	1,028	20.9	1,305	26.58	1,096	22	175	9.2

4.10. Section 4(f) properties

One Section 4(f) property has been identified near the Study Area. The Chino Valley Community Center Park and Aquatic Center at 1615 North Road 1 East (southeast corner of Perkinsville Road and Road 1 East) is located about 0.35 mile east of SR 89. These public facilities are operated by the Town of Chino Valley Parks and Recreation Department. Potential Section 4(f) properties include the historic properties listed in the Cultural Resources section above.

4.11. Topography and Drainage Features

Study Area topography is shown in **Figure 15**. The surrounding topography is fairly mountainous, with SR 89 passing between ranges. In general, there is a low point in the terrain following the Big Chino Wash.

The roadway has a rolling downhill slope, generally less than 1%, from approximately the southern limit of the Study Area to the Big Chino Wash crossing near Little Ranch Road. There are intermittent locations where the grade exceeds 3% throughout the corridor; however, the roadway grade is generally in excess of 3% from the PNF boundary north to MP 341.42. There is a limited segment north of MP 340 that exceeds 6%. Approximate roadway grades are shown in the Map Book in **Appendix WP1-1**.

Key drainage features are shown in **Figure 16**. The National Flood Insurance Program develops Flood Insurance Rate Maps (FIRMs) to indicate the risk of flooding. Map numbers 04025C1315G, Panel 1315 of 3900, effective September 3, 2010; map number 04025C1305G, Panel 1305 of 3900, effective September 3, 2010; and 04025C0990G, Panel 990 of 3900, effective September 3, 2010, cover the Study Area. Based on these maps, the majority of the corridor is located within flood Zone X (unshaded), or areas determined to be outside the 0.2% annual chance floodplain. The areas around the Big Chino Wash are denoted Zone AE, with base flooding elevations determined. FEMA describes these zones as “the floodway is the channel of a stream plus any adjacent floodplain areas that must be kept free of encroachment so that the 1% annual chance flood can be carried without substantial increases in flood heights.” The area adjacent to the Big Chino Wash by SR 89 is Zone X (shaded) and is subject to flooding effects from the Big Chino Wash. Zone X (shaded) denotes, “areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depths of less than 1 foot or with drainage areas less than 1 square mile, and areas protected by levees from 1% annual chance flood.” There are tributary washes and associated floodways through the valley. There is another floodway crossing north of Road 6N. The PNF is designated Zone D, or “areas in which flood hazards are undetermined, but possible.”

Figure 15 – Topography





Figure 16 – Drainage Features



5.0 Future Conditions

5.1. Utilities

Based upon available information, there are no planned major utility improvements within the Study Area.

5.2. Transportation Network

5.2.1. Roadway Network

The ADOT State Transportation Improvement Program (STIP) prepared for fiscal years 2016-2020 identifies two future projects within the Study Area. The first project begins near milepost 337 and is programmed for FY 2018. Based upon coordination with ADOT, the project will likely include the construction of two new auxiliary lanes that will serve as right-turn lanes and a continuous left-turn lane from Sweet Valley Road north to the BNSF Railway Bridge (Structure Number 04 1577; MP 337.38). The second project, at MP 338, is programmed for FY 2016; it will construct a northbound right-turn lane at Verde Ranch Road.

5.2.1.1. Climbing Lane

A critical length of grade is achieved between MP 339.98 and MP 340.49. The Green Book identifies three criteria reflecting economic considerations which should be satisfied to justify a climbing lane:

1. Upgrade traffic flow rate in excess of 200 vehicles per hour (vph) and
2. Upgrade truck flow rate in excess of 20 vph and
3. One of the following:
 - a. At least a 10 mph speed reduction for heavy trucks or
 - b. LOS of E or F on the grade or
 - c. A reduction of at least two LOS when moving from the approach segment to the grade

Based on the traffic counts taken near MP 341, the existing upgrade traffic flow rate and truck flow rate are 248 vph and 37 vph, respectively.

The economic justification criteria set forth in the Green Book for a climbing lane is achieved.

5.2.2. Bicycle and Pedestrian Network

There are no known pedestrian specific projects planned along SR 89 within the project area.

The 2015 AASHTO *U.S. Bicycle Route System* evaluated alternatives for the future USBR 79. The recommended route for USBR 79 follows SR 89 from Prescott to I-40.

5.2.3. Transit Network

While the YRT has slowly expanded service since its inception as Chino Valley Transit in 2009, there are currently no published plans for new routes.

5.2.4. Freight Movement

Currently, there are restrictions external to the project limits that likely impact freight traffic along the SR 89 corridor. One such restricting feature is the structurally deficient Hell Canyon Bridge (MP 345.70) which currently has an 80,000 pound limit. A new structure is scheduled to be completed in late 2016 which will eliminate this weight restriction, potentially increasing the freight traffic which passes through the project limits.

5.3. Traffic Analysis

5.3.1. Travel Demand Model Land Use

The 2025 and 2040 model results for the CYMPO focused version of ADOT Statewide Travel Demand Model (AZTDM2) were obtained for use in this study. Socioeconomic data from the models was not reviewed for this study. It was understood that an extensive review and update to the socioeconomic data had just been conducted as part of the 2014 CYMPO Regional Transportation Plan Update reviewed in Section 2.3.

5.3.2. Traffic Forecast and Annual Growth Factor Development

Using the 2025 and 2040 model results, annual growth rates were developed for the SR 89 corridor as well as various cross streets. The following growth rates were used for this Study:

State Route 89

Perkinsville Road to Road 6N – 1.25% per year
Road 6N to Rolling Hills Road – 1.00% per year
Rolling Hills Road to Bramble Drive – 0.85% per year
North of Bramble Drive – 1.40% per year

Road 3N – 1.05% per year
Road 4N – 1.03% per year
Rolling Hills Road – 0.67% per year
Big Chino Road – 0.88% per year
Bramble Drive – 0.43% per year

Existing 2016 traffic count data was increased by the annual growth rate to determine 5-year, 10-year and 20-year forecasts.

5.3.3. Design Hour Volume Factor

Design hour forecasts typically represent the 30th highest hourly volume of the year. Since the 2016 traffic count data were assumed to be taken on an “average” day, a design hour volume factor was developed to convert the counted volume to design hour. From the ADOT 2014 AADT Report, the 30th highest hour on SR 89 in the Study Area represents 9% of the AADT. From the 24-hour counts conducted on the corridor, the PM peak is the highest hour of the day and is between 8.2% and 8.5% of the 24-hour volume. The design hour volume factor is calculated by dividing the average daily peak percentage by the 30th highest hour percentage. For the SR 89 corridor, the design hour volume factor is approximately 1.10. To be a little more conservative, this factor was increased to 1.15. The 2016 AM and PM turning movement counts were

multiplied by 1.15 to convert them to the 30th highest hour design volumes for the traffic operational analysis.

5.3.4. Traffic Operational Analysis

Capacity analyses were conducted for the 5-year, 10-year, and 20-year horizon build conditions at the five intersections identified in **Figure 11**. *HCS* software which uses the *Highway Capacity Manual* methodology was used for all intersections, except the intersection SR 89 with Road 4N. This intersection is roundabout; therefore, *SIDRA* software was used to analyze the intersection with *Highway Capacity Manual* methodologies. *HCS* and *SIDRA* results are included in **Appendices WP1-5 through WP1-7. Table 23, Table 24, and Table 25** summarize the 2021, 2026 and 2036 AM and PM peak hour capacity analysis results, respectively.

Table 23 – 2021 AM and PM Peak Hour Capacity Analysis					
Intersection*	Approach	2021 AM Peak		2021 PM Peak	
		LOS	Delay (sec/veh)	LOS	Delay (sec/veh)
Intersection 1 SR 89 & Road 3N	Eastbound	D	37.6	D	41.1
	Westbound	D	36.6	D	41.2
	Northbound	B	10.9	A	9.2
	Southbound	B	14.7	B	11.8
	Overall	C	20.2	B	15.6
Intersection 2 SR 89 & Road 4N	Eastbound	A	6.4	A	5.5
	Westbound	A	5.2	A	7.2
	Northbound	A	5.3	A	7.9
	Southbound	A	7.2	A	6.4
	Overall	A	6.4	A	7.2
Intersection 3 SR 89 & Rolling Hills Road	Eastbound	B	13.4	B	13.1
	Northbound	A	1.1	A	0.5
	Southbound	A	0.0	A	0.0
	Overall	A	1.4	A	0.8
Intersection 4 SR 89 & Big Chino Road	Eastbound	B	13.4	C	17.4
	Northbound	A	2.2	A	3.9
	Southbound	A	0.0	A	0.0
	Overall	A	5.2	A	4.4
Intersection 5 SR 89 & Bramble Drive	Eastbound	A	9.4	B	12.0
	Westbound	B	11.6	C	18.6
	Northbound	A	0.9	A	3.6
	Southbound	A	0.0	A	0.3
	Overall	A	3.8	A	3.4

*Refer to **Figure 11** for intersection number.

Table 24 – 2026 AM and PM Peak Hour Capacity Analysis					
Intersection*	Approach	2026 AM Peak		2026 PM Peak	
		LOS	Delay (sec/veh)	LOS	Delay (sec/veh)
Intersection 1 SR 89 & Road 3N	Eastbound	D	36.6	D	40.4
	Westbound	D	36.4	D	40.6
	Northbound	B	11.5	B	10.2
	Southbound	B	15.7	B	13.1
	Overall	C	20.6	B	16.5
Intersection 2 SR 89 & Road 4N	Eastbound	A	6.6	A	5.7
	Westbound	A	5.3	A	7.4
	Northbound	A	5.4	A	8.2
	Southbound	A	7.5	A	7.4
	Overall	A	6.7	A	7.5
Intersection 3 SR 89 & Rolling Hills Road	Eastbound	B	13.7	B	13.5
	Northbound	A	1.0	A	0.4
	Southbound	A	0.0	A	0.0
	Overall	A	1.4	A	0.8
Intersection 4 SR 89 & Big Chino Road	Eastbound	B	13.7	C	18.4
	Northbound	A	2.1	A	3.9
	Southbound	A	0.0	A	0.0
	Overall	A	5.1	A	4.4
Intersection 5 SR 89 & Bramble Drive	Eastbound	A	9.5	B	12.1
	Westbound	B	12.1	C	18.9
	Northbound	A	1.2	A	3.6
	Southbound	A	0.0	A	0.2
	Overall	A	3.8	A	3.4

*Refer to **Figure 11** for intersection number.

Table 25 – 2036 AM and PM Peak Hour Capacity Analysis					
Intersection*	Approach	2036 AM Peak		2036 PM Peak	
		LOS	Delay (sec/veh)	LOS	Delay (sec/veh)
Intersection 1 SR 89 & Road 3N	Eastbound	D	36.5	D	40.9
	Westbound	D	35.5	D	39.4
	Northbound	B	12.7	B	11.2
	Southbound	B	17.9	B	14.9
	Overall	C	21.7	B	17.6
Intersection 2 SR 89 & Road 4N	Eastbound	A	7.2	A	6.0
	Westbound	A	5.8	A	8.1
	Northbound	A	5.7	A	9.2
	Southbound	A	8.6	A	7.2
	Overall	A	7.4	A	8.3
Intersection 3 SR 89 & Rolling Hills Road	Eastbound	B	14.3	B	14.2
	Northbound	A	1.0	A	0.5
	Southbound	A	0.0	A	0.0
	Overall	A	1.5	A	0.8
Intersection 4 SR 89 & Big Chino Road	Eastbound	B	14.7	C	21.0
	Northbound	A	2.3	A	4.1
	Southbound	A	0.0	A	0.0
	Overall	A	5.6	A	4.8
Intersection 5 SR 89 & Bramble Drive	Eastbound	A	9.5	B	12.7
	Westbound	B	12.3	C	20.7
	Northbound	A	1.1	A	3.6
	Southbound	A	0.0	A	0.2
	Overall	A	3.8	A	3.2

*Refer to **Figure 11** for intersection number.

The analysis indicates the operations for 5-year, 10-year, and 20-year horizon build conditions at the five intersections are very good at overall LOS A or LOS B, except for the SR 89 and Road 3N intersection that will operate at LOS C during the AM peak hour under all build conditions. The minor road approaches at this intersection operate at an acceptable LOS D, which is typical of minor approaches at signalized intersections with substantially lower volumes than the mainline (SR 89). Even with the projected growth in the area, the five Study Area intersections are expected to have acceptable intersection operations through at least 2036 without any geometric or capacity improvements.

6.0 Identified Needs Summary

Working Paper 1 reviewed pertinent current and projected future information for the Study Area. Transportation issues, opportunities, and constraints were outlined; recommendations from previous studies were documented. Based on a review of this information, the following transportation needs and deficiencies were identified.

6.1. Safety

Working Paper 1 identified a need to address safety within the Study Area. Within the five year period from November 30, 2010 to November 30, 2015, there have been over 200 crashes reported with three fatalities within the analysis period; one fatality occurred after the analysis period. The corridor has two distinct character areas where the crash patterns differ.

- South of Road 5N (developed), the top three types of crashes include rear end, left turn, and sideswipe (same direction). Crashes were generally clustered around intersections. The top five locations, from south to north, include the intersections at Perkinsville Road, Palomino Road, Road 3N, Road 4N, and Road 5N. The Perkinsville Road and Road 4N intersections were recently reconstructed as roundabouts, which is anticipated to address safety concerns at these locations. The intersections at Palomino Road, Road 3N, and Road 5N, along with other locations, should be considered for safety related improvements.
- North of Road 5N (less developed), the top three types of crashes include fixed object, rear end, and animal. Crashes were generally clustered around intersections, with various intermittent crash locations throughout. The four fatalities reported in the Study Area occurred in this segment, where three of the four occurred at intersections. In addition to the intersections, clusters of crashes occur just south of the Del Rio Ranch Bridge (near MP 333), between Little Ranch Road and the Big Chino Wash Bridge (MP 335.7 to 336.2), and near the development just south of the BNSF Railway bridge (MP 337.0). In general, there is a need to reduce the number of single vehicle and nighttime collisions.

6.2. Access Management

There is a need to address connection (access point) density, location, and type within the Study Area. An access management plan needs to be developed to guide corridor development now and in the future. Provisions for access management for future development should also be considered.

6.3. General Considerations

Additional general considerations should include accommodating the presence of truck traffic and environmental concerns with potential corresponding mitigation measures for potential improvements.

7.0 Corridor Vision and Access Management

A long-term corridor vision, extending beyond the 20-year planning horizon of this study, was developed to accommodate buildout growth and to integrate access management. Components of this vision should generally be completed as needed, to accommodate future development as it occurs. The corridor vision can be divided in four segments:

- Perkinsville Road to Road 5N;
- Road 5N to Sweet Valley Road;
- Sweet Valley Road to Bramble Drive; and
- Bramble Drive north to study limit.

Access management will protect the investment in the corridor by reducing travel times, improving corridor aesthetics, and enhancing future facility performance. Access management typically reduces the number of conflict points, and in turn, the number of crashes. In general, medians are proposed through much of the corridor to promote right-in right-out access; roundabouts are proposed at key locations to provide left- and U-turn movements. The roadway typical sections, locations for major intersections, and other features were developed in consideration of existing and anticipated development patterns.

The following corridor vision should guide development along the corridor; however, there could be another approach if parallel roads develop, requiring fewer full access intersections.


7.1. Perkinsville Road to Road 5N (MP 329.20 to 331.28)

Perkinsville Road to Road 5N is entirely within Chino Valley and is more densely developed than the rest of the corridor. Based upon existing development, a four-lane facility with an eight-foot wide raised median, curb, gutter, and sidewalk is recommended, as shown in **Figure 17**. The typical section should utilize the existing curb and gutter south of Road 3N (approximate 71-foot width); the typical section north of 3N could either match the section south of Road 3N or narrow the median as shown in **Figure 17**. The best approach should be determined during final design. This generally conforms to the Urban Highway Typical Section UA as shown in Figure 306.4A of the ADOT Roadway Design Guidelines (RDG), modified with a narrower median and sidewalks.

Roundabouts are recommended at major intersections in this segment to accommodate left- and U-turn movements. Major intersections include the existing roundabouts at Perkinsville Road and Road 4N and a proposed roundabout at Road 5N. Current site constraints provide challenges to constructing a roundabout at Road 3N. Partial access (e.g. $\frac{3}{4}$ access) at Road 3N may be considered; however, the Town Fire District is located just west of the intersection and there are concerns regarding emergency response for the eastbound to northbound left-turn movement. Access at Road $3\frac{1}{2}$ N may be full or partial access, based upon future development and ADOT discretion. There is an opportunity to balance future improvements at Road 3N and Road $3\frac{1}{2}$ N, where one could potentially accommodate turning movements that would typically occur at the other location. The ultimate build out of the Road 3N and Road $3\frac{1}{2}$ N intersections

should be determined by corridor needs, development patterns, and engineering and construction considerations.


Figure 17 – Recommended Typical Section between Perkinsville Road and Road 5N



7.2. Road 5N to Sweet Valley Road (MP 331.28 to 336.69)

Road 5N to Sweet Valley Road includes the northern limit of Chino Valley and ends south of the Paulden Post Office. Based upon existing and planned development density, a four-lane facility conforming to the Fringe-Urban Highway Typical Section IS3 as shown in Figure 306.3 of the ADOT RDG is recommended in this segment as shown in **Figure 18**. It is a four-lane divided highway (bifurcated highway) with rural characteristics. Roundabouts that accommodate left- and U-turn movements are recommended at major intersections within this segment, including Old Highway 89, Frontier Road, Rolling Hills Road, Little Ranch Road, and Sweet Valley Road.


Figure 18 – Recommended Typical Section between Road 5N and Sweet Valley Road



7.3. Sweet Valley Road to Bramble Drive (MP 336.69 to MP 338.80)

Sweet Valley Road to Bramble Drive includes downtown Paulden; Bramble Drive is the northern-most intersection before the PNF. Based upon existing and planned development density, a 4-lane facility with a 16-foot wide concrete raised median conforming to the Fringe-Urban Highway Typical Section IS1 as shown in Figure 306.3 of the ADOT RDG is recommended as shown in **Figure 19**. Roundabouts are recommended at major intersections within this segment, including Big Chino Road and Bramble Drive. In order to accommodate a four-lane section, the BNSF Railway bridge would need to be widened.

Figure 19 – Recommended Typical Section between Sweet Valley Road and Bramble Drive



7.4. Bramble Drive North (MP 338.80 to 341.42)

The PNF boundary is less than one mile north of Bramble Drive. Little through traffic is anticipated in this section, therefore the existing two-lane road should be sufficient to accommodate traffic demand. No median is necessary as there are very limited access points.

7.5. Access Management Guidelines

ADOT is currently developing Access Management Guidelines. The draft ADOT guidelines and/or guidelines from the Transportation Research Board (TRB) *Access Management Manual* (2014) should be considered when permitting new access points.

Reducing the number of new/existing access points is an effective tool to reduce the number of conflict points. A disposition of access for each access point was not conducted. All parcels require an access point; however, when possible, the following criteria should be met for new access points on SR 89:

- Side street/cross street access is used in lieu of SR 89 if available.
- Meets access spacing requirements (see Section 3.7.1.3).
- Is not located within a turn lane to another public street or a private driveway.

When practicable, unused or redundant access points could be removed as parcels develop/redevelop. This includes limiting new development to one connection per parcel to SR 89 whenever possible.

8.0 Potential Improvement Strategies

After the Draft Working Paper 1 was prepared, the second Study Team meeting was held. The group developed potential improvement strategies that would blend with the long-term vision, minimize “throw away” infrastructure considering the corridor vision, and address the identified needs.

Safety countermeasures were identified that may improve safety performance by focusing on the crash types having the greatest potential for mitigation. Improvements were investigated to accommodate access management and growth needs. Intersection improvements were only investigated for intersections with public roads.

8.1. Safety Analyst Analysis

The ADOT Traffic Safety Section utilized Safety Analyst to analyze the corridor. The following recommendations stemmed from this analysis:

- Strong need for access management due to high rear-end crashes in urban areas.
- Reduce the high number of run-off road / fixed object crashes in rural areas.
- There is a need for appropriate wildlife fencing.
- Implement wildlife crossing signage (especially between MP 334 – 342).

These recommendations were considered when developing the potential improvements summarized below. Potential improvements were combined into logical projects and are illustrated in the Recommendations Map Book in **Appendix WP2-1**.

The ADOT Traffic Safety Section suggested non-engineering safety improvements. Four behavioral traits from the Strategic Highway Safety Plan (SHSP) to include in a safety campaign targeting this corridor may include Slow Down, Buckle Up, Pay Attention, and Drive Sober.

8.2. Perkinsville Road to Road 5N (MP 329.20 to 331.28)

This segment is more urbanized than the northern portion of the corridor. Potential treatments were developed to address existing access management and safety concerns; specifically, to reduce the number of conflict points at driveways and intersections. The potential treatment from Perkinsville Road to Road 5N includes constructing Urban Highway Typical Section UA as shown in Figure 306.4A of the ADOT Roadway Design Guidelines (RDG), modified with an eight-foot wide median and includes sidewalks. If funding is available, a 16-foot wide median could be considered. Where left-turn lanes are provided, they should be sized to accommodate the gap, braking distance, and queue within the median. There is a development platted between Road 3N and Road 3½N; a widened roadway section with a divided median will accommodate anticipated future demand and promote access management. It is anticipated that some type of access will be necessary at Road 3½N; the type of access (e.g. ¾ access or full access) will be determined based upon future development and ADOT discretion. There are underdeveloped parcels between Road 4N and Road 5N; should their use intensify, a widened roadway section with a divided median will accommodate future development and promote access management.

A raised median is inconsistent with the adjoining section of SR 89 from Road 1S to Perkinsville Road, where there is four-lane section with a two-way left-turn lane (TWLTL). However, a two-way left-turn lane is not recommended in this segment due to the high number of access points.

Roundabouts are generally recommended at primary intersections within the Study Area; Road 3N is an exception due to current constraints at the intersection. It is recommended that the traffic signal remain and that a protected left-turn phase be added to mitigate the number of crashes at the intersection as a short-term solution. This approach satisfies stakeholder concerns regarding the eastbound to northbound left-turn movement at this intersection. This countermeasure investigated a 100 second cycle for both peaks with a protected-permitted southbound left-turn, protected only northbound left-turn and permitted only eastbound and westbound left-turns. If this counter measure underperforms, the intersection should be reevaluated in the future. Other treatments, such as a roundabout or $\frac{3}{4}$ access, may be effective.

A roundabout was considered at Road 5N to provide a U-turn movement and to accommodate existing and planned development in the area. The roadway typical section would taper to one lane in each direction north of this roundabout.

The following summarizes potential treatments within the planning horizon and their primary purpose. Note that safety improvements were developed to address fatal and incapacitating crashes, as well as less severe crashes.

- Perkinsville Road to Road 5N (MP 329.00 to MP 331.27) – Construct raised median and four-lane typical section between Road 3N and Road 5N (safety, access management, and accommodate future development).
- Road 3N (MP 329.20) – Add protected left-turn phase to existing signal (safety).
- Road 5N (MP 331.27) – Construct a two-lane roundabout (safety and access management).

The raised median and four-lane typical section could be constructed in two phases based upon funding availability. Perkinsville Road to the existing roundabout at Road 4N would be a logical first phase.

8.3. Road 5N to Sweet Valley Road (MP 331.28 to 336.69)

Potential improvements in this segment evaluated within the planning horizon were developed to ease existing and anticipated safety and access concerns. Currently, the approaches for Road 6N do not align; modifying this intersection was evaluated to improve access management. The *TRB Access Management Manual* (2014) recommends access points should align or be offset enough to create two clearly identifiable intersections; examples cited provided an offset of 600 to 750 feet with the posted or design speed over 45 mph. The intersection at Road 6N is offset by approximately 70 feet.

This segment includes several private roads and driveways where crashes have occurred within the past five years. The highest concentration of crashes in this segment is at Buffalo Run Road; these crashes are predominately rear end collisions, with one angle crash. A four-lane divided highway (bifurcated highway) conforming to the Fringe-Urban Highway Typical Section IS3 as

shown in Figure 306.3 of the ADOT RDG and **Figure 18** herein was considered between Old Highway 89 and Frontier Road, with two-lane roundabouts at each end to accommodate U-turn and left-turn movements. A northbound left-turn lane and a southbound right-turn lane were investigated at Little Ranch Road.

The following summarizes potential treatments within the planning horizon and their primary purpose. Note that safety improvements were developed to address fatal and incapacitating crashes, as well as less severe crashes.

- Road 6N (MP 332.35) – realign Road 6N approaches to SR 89 (access management).
- Construct divided median and four-lane typical section between Old Highway 89 and Frontier Road (access management, safety, and accommodate future development).
- Old Highway 89 (MP 333.41) – construct two-lane roundabout (access management).
- Frontier Road (MP 334.50) – construct two-lane roundabout (access management).
- Little Ranch Road (MP 335.77) – construct northbound left-turn lane (safety).

8.4. Sweet Valley Road to Bramble Drive (MP 336.69 to MP 338.80)

ADOT is currently developing a project between Sweet Valley Drive and the BNSF Railway overpass; it has been excluded from this analysis. No geometric improvements are being investigated within this segment as the project under development should address current needs; however, this study evaluated lighting at the Paulden Post Office. A cluster of crashes has occurred near the post office during the five year analysis period; a high percentage of these crashes occurred at night when compared to the statewide average. Further, there was an incapacitating crash involving a pedestrian. There is development on both sides of SR 89 near the post office, which lends itself to pedestrian crossings. If lighting is installed, an agreement with ADOT would be required, indicating that an improvement district or the local government would fund electricity and potentially installation. ADOT would typically maintain the lighting system.

North of the BNSF Railway overpass, existing development is limited; however, there is a large development platted east of Big Chino Road and commercial developments are underway. A roundabout was investigated at this location to accommodate future development and access management needs.

There is a concentration of crashes at Bramble Drive, including a fatal and incapacitating crash. A roundabout was investigated to mitigate crashes and for access management.

The following summarizes potential treatments within the planning horizon and their primary purpose(s). Note that safety improvements were developed to address fatal and incapacitating crashes, as well as less severe crashes.

- Paulden Post Office (MP 337.05) – install lighting (safety).
- Big Chino Road (MP 337.70) – construct roundabout (access management, future development, and safety).
- Bramble Drive (MP 338.80) – construct roundabout (safety and access management).

8.5. Bramble Drive to Study Limit (MP 338.80 to 341.42)

No infrastructure improvements were evaluated within this segment. The existing facility has adequate capacity through the planning horizon and almost all of the crashes in this segment are run off the road or animal collisions. Wildlife warning signage installation was investigated in accordance with the recommendations of the ADOT Statewide Wildlife Crash Analysis and Proposed Action Plan. Costs for signage were only developed within the Study Area. The following summarizes potential treatments within the planning horizon:

- MP 334.0 to study limit (and beyond) – install wildlife warning signage (safety).

8.6. Revised Project Concepts

The project concepts were refined after review and input from the Study Team, stakeholders, and the public. A summary of revisions includes:

- Two options for Perkinsville Road to Road 3N:
 - Construct the raised median north of Butterfield Road to the existing traffic signal at Road 3N. Butterfield Road should keep full access to SR 89.
 - Should a roundabout be constructed at Road 3N, construct the raised median north of Perkinsville Road, converting Butterfield Road to a right-in right-out access point.
- Construct a southbound right-turn lane at Little Ranch Road (MP 335.77).
- Construct roundabouts with a two-lane circulatory road. Big Chino Road and Bramble Drive will be constructed as two-lane roundabouts (MP 337.70 and MP 338.80).
- Provide a northbound two-lane section north of the Bramble Drive roundabout to provide a passing opportunity in lieu of a passing lane further north. This was assessed as part of the roundabout project, including impacts and cost.

The section between Perkinsville Road and Road 3N is currently a four-lane section with a TWLTL. Two potential approaches were identified: 1.) Construct a median from Perkinsville Road to Road 3N and provide a roundabout at Road 3N; or 2.) Retain the existing TWLTL from Perkinsville Road through the Butterfield Road intersection, construct a median north of Butterfield Road to Road 3N and retime the existing traffic signal. Either solution could be paired with the improvements described for Road 3N to 5N. As the latter solution is less costly and the signal at Road 3N is performing sufficiently, constructing a median north of Butterfield Road and retiming the existing traffic signal is currently recommended. The roundabout at Road 3N is included in the safety analysis.

8.7. Design Considerations

A Recommendations Map Book was developed to illustrate improvements considered within the planning horizon and to serve as the basis for potential probable cost estimates, included as **Appendix WP2-1**. The following design assumptions were used in its development:

- Roundabouts were designed to accommodate two WB-67 trucks side by side.
- 55 mph design speed south of 5N.

- 65 mph design speed north of 5N, with the exception of the taper approaching the Big Chino Road roundabout. The roundabout was configured based upon the 65 mph design speed; however, a 65 mph design speed taper extends under the BNSF railway bridge, which is too narrow to accommodate the taper. Therefore, shifting the roundabout location or adjusting the taper design speed to 55 mph should be considered.
- Based upon conceptual engineering, existing culverts near Road 3 ½ N and Frontier Road will need to be extended to accommodate improvements. These costs are included in the project contingency.
- The existing power poles within the right-of-way and near the edge of the proposed typical section will be relocated within the existing right-of-way, five feet from its outside edge (barring other utility conflicts), by the utility owner (no associated project cost).

8.8. Estimate of Probable Cost

Estimates of probable cost were developed for the potential improvements to provide an "order of magnitude" cost. These costs were developed utilizing 2016 dollars and are based on the general description of the potential improvement provided. Potential right-of-way costs are not included in the estimates. Right-of-way needs should be minimal except for a roundabout at Road 3N and realigning Road 6N. Planning level cost estimates considered the following factors:

- Construction items, such as pavement, earthwork, and traffic control;
- Administrative items, such as design, construction and engineering administration, and quality control; and
- Contingencies, including unidentified items (30%) and construction (5%).

Currently, the Arizona Highway Safety Improvement Program (HSIP) application indicates that if more than one countermeasure (improvement) is being installed, the cost of each countermeasure must be developed separately. In order to facilitate a high-level review of project components through that lens, the cost and safety benefits for each countermeasure are evaluated independently in this working paper. Project recommendations will combine countermeasures into logical, constructible projects.

As improvements advance in the project development process, more detailed project cost estimates that consider specific existing site conditions, such as topography and right-of-way constraints, will need to be developed.

Planning level cost estimates in 2016 dollars are presented **Appendix WP2-2** and summarized in **Table 26**. The costs were developed with the following assumptions:

Corridor-wide:

- All existing pavement is removed at roundabout locations.
- Earthwork estimates are based on \$8 per cubic yard.
- Work limits match shaded area in Recommendations Map Book.

Perkinsville Road to Road 3N:

- Existing curb and gutter remain.
- Raised median pavement sits on compacted subgrade.
- Mill and overlay existing pavement; full depth replacement within the saw cut where no median is placed.

Road 3N to Road 5N:

- 69-foot typical section with new curb and gutter. Final typical section (69-foot or match existing width south of Road 3N) to be determined during project design.
- Shoulders are full-depth pavement construction.
- All existing pavement removed and replaced with full depth section.
- Raised median pavement sits on compacted subgrade.

North of Road 5N:

- All existing pavement is removed for widening, full depth replacement is required.

Little Ranch Road:

- Improvements extend north to Big Chino Wash Bridge to avoid short stretch of "old" pavement.

Table 26 – Estimate of Probable Cost		
Location	Potential Improvement	Cost
Butterfield Road to Road 3N	Replace TWLTL with raised median north of Butterfield Road	\$490,000
Road 3N	Retime existing signal	N/A*
Road 3N	Roundabout	\$2,010,000
Road 3N to Road 4N	Widen to 4-lane section with raised median	\$5,890,000
Road 4N to Road 5N	Widen to 4-lane section with raised median	\$5,650,000
Road 5N	Roundabout	\$2,730,000
Road 6N	Align intersection	\$480,000
Old Highway 89	Roundabout	\$4,360,000
Old Highway 89 to Frontier Road	Widen to 4-lane section with raised median	\$5,070,000
Frontier Road	Roundabout	\$3,760,000
Little Ranch Road	Construct left-turn lane	\$1,270,000
Little Ranch Road	Construct right-turn lane	\$150,000
Paulden post office	Lighting	\$90,000
Big Chino Road	Roundabout	\$4,540,000
Bramble Drive	Roundabout	\$5,100,000
MP 343-341.42	Install wildlife warning signage	\$3,000**

*Assumes this project will be completed by ADOT staff.

**\$500 allowance per sign, 3 signs in the both the north and southbound directions.

8.9. Other Considerations

The project study team presented additional thoughts, concerns, and considerations for project development through the corridor. This input is summarized below.

- **Truck climbing lane** (MP 339.98-340.49) – the economic justification criteria set forth in the AASHTO *A Policy on Geometric Design of Highways and Streets* ("Green Book") for a climbing lane is achieved in this segment; however, based upon stakeholder input, extending two northbound lanes north of the Bramble Drive roundabout would provide a more cost effective passing opportunity.
- **Wildlife accommodations** – future projects should consider antelope wire for fencing. In addition, eagles have been spotted near Road 6N.
- **Pavement condition** – the existing pavement near the Drake Cement Plant was noted to be in poor condition; however, the plant is beyond limits of this study.

9.0 Traffic Analysis

Capacity analysis was conducted for the proposed improvements at the five study intersections identified in Working Paper 1, shown in **Figure 20**. *HCS* software, which uses the *Highway Capacity Manual* methodology, was used for the signalized intersection at Road 3N and the stop controlled intersection at Rolling Hills Road. *SIDRA* software was used to analyze the roundabouts at Road 4N, Big Chino Road, and Bramble Drive. *HCS* and *SIDRA* results are included in **Appendix WP2-3**. Roundabout analysis for Big Chino Road and Bramble Drive indicates a one-lane roundabout would perform adequately through the planning horizon; however, based on stakeholder input, the two-lane buildout configuration was used for project development, including the schematic and project cost estimate.

Figure 20 – Intersections Considered in Analysis




Table 27 summarizes the 2036 AM and PM peak hour capacity analysis results. Only the 2036 (20-year horizon) build conditions were analyzed.

Table 27 – 2036 AM and PM Peak Hour Build Capacity Analysis					
Intersection*	Approach	2036 AM Peak		2036 PM Peak	
		LOS	Delay (sec/veh)	LOS	Delay (sec/veh)
Intersection 1 SR 89 & Road 3N	Eastbound	D	35.5	D	42.4
	Westbound	D	35.2	D	39.8
	Northbound	C	21.0	C	20.6
	Southbound	B	19.4	C	21.6
	Overall	C	24.4	C	24.7
Intersection 2 SR 89 & Road 4N	Eastbound	A	7.2	A	6.0
	Westbound	A	5.8	A	8.1
	Northbound	A	5.7	A	9.2
	Southbound	A	8.6	A	7.2
	Overall	A	7.4	A	8.3
Intersection 3 SR 89 & Rolling Hills Road	Eastbound	B	14.3	B	14.2
	Northbound	A	1.0	A	0.5
	Southbound	A	0.0	A	0.0
	Overall	A	1.5	A	0.8
Intersection 4 SR 89 & Big Chino Road	Eastbound	A	8.5	A	6.8
	Northbound	A	5.8	B	10.7
	Southbound	A	6.7	B	10.8
	Overall	A	7.0	B	10.2
Intersection 5 SR 89 & Bramble Drive	Eastbound	A	4.9	A	5.8
	Westbound	A	4.3	A	4.6
	Northbound	A	5.2	A	6.2
	Southbound	A	4.2	A	8.0
	Overall	A	4.9	A	7.0

*Refer to **Figure 20** for intersection number.

The analysis indicates the five study intersections will operate acceptably through 2036 with LOS C or better. Depending on signal optimization at Road 3N, the eastbound and westbound LOS could be better than indicated as vehicles making a northbound left-turn could make the left-turn movement at the Perkinsville Road roundabout to avoid congestion and use Road 1W as a parallel route.

Beyond the planning horizon, the roundabouts at Big Chino Road and Bramble Drive are proposed to be converted into multilane roundabouts to accommodate the four-lane build out corridor vision. Because these intersections operate at LOS B or better under 2036 conditions with a one-lane roundabout, a multilane roundabout is expected to operate acceptably well into the future with minimal delays.

10.0 Potential Improvement Safety Analysis

The safety benefit of the potential improvements was evaluated by using Crash Modification Factors (CMF)s available through the Highway Safety Manual (HSM) and FHWA CMF Clearinghouse. A CMF is a multiplicative factor that indicates the proportion of crashes that would be expected after implementing a countermeasure. CMFs provide a quantitative estimate of the effectiveness of a safety countermeasure. CMFs with a value less than 1.0 indicate an expected decrease in crashes, while those greater than 1.0 indicate an expected increase. When combined with probable construction costs and costs associated with differing crash severities, CMFs provide a basis for cost-benefit analysis.

The safety analysis for this corridor used the five-year crash history, and was not normalized using HSM predictive analysis. Predictive analysis serves to adjust crash data to a “typical year,” reducing fluctuations in annual crash rates prior to analysis. A fatal crash was reported at Little Ranch Road after the original analysis period (2010-2015), as described in Working Paper 1. While not included in the original crash analysis, this crash was included as part of the benefit to cost ratio analysis as there are high costs associated with fatal crashes and this crash would be included in any potential funding application. Crashes with impaired drivers were not removed from analysis; however, these crashes cannot be considered to support an application for HSIP funding.

Not all CMFs can be applied to all crash types; for instance, lighting an intersection will not reduce daytime crashes. The raised median was not assumed to address crashes at Perkinsville Road, Road 4N, Road 5N, Old Highway 89, or Frontier Road. Constructing a raised median for the segment from Perkinsville Road to the end of the existing four-lane section has been evaluated separately from the transition to the two-lane section to Road 4N because the existing roadway section differs (four-lane with two-way left-turn lane vs. two-lane), so one CMF cannot be applied to both sections. The CMFs have been used as applicable for this analysis. An applicable CMF is not available for all of the potential improvements recommended within this corridor, e.g. installing wildlife signage. The potential safety benefit of these improvements was not quantified.

The safety analysis of potential improvements is shown in **Table 28** and **Table 29**. These tables use the KABCO injury classification scale, with the following values:

- K – Fatal Injury
- A – Incapacitating Injury
- B – Non-incapacitating Evident
- C – Possible Injury
- O – No Injury

A footnote is provided with a link to the CMF used in the analysis; details for the CMFs are provided in **Appendix WP2-4**.

Begin MP	End MP	Intersecting Road	Potential Improvement	Crashes												Injury Severity					CMF					Existing Crashes/Year	Anticipated Crashes/Year
				LT	O	RE	B	S	SV	HO	AG	AL	P	RR	TOTAL	K	A	B	C	O	CMF	Countermeasure	Application				
																							Crash Type	Crash Severity	Area Type		
329.20	329.20	Road 3N	Retime signal w/ protected left phase	6											6			1	1	4	0.01	Change Left-Turn Phase to Protected Phasing on one or more approaches ¹	Left-turn	K	Urban	0.00	0.00
																								A		0.00	0.00
																								B		0.20	0.00
																								C		0.20	0.00
																								O		0.80	0.01
329.20	329.20	Road 3N	Roundabout	6		8			1		1			3	19			2	3	14	0.81	Conversion of signalized intersection into single- or multi-lane roundabout ²	All	K	Urban/ Suburban	0.00	0.00
																								A		0.00	0.00
																								B		0.40	0.32
																								C		0.60	0.49
																								O		2.80	2.27
331.27	331.27	Road 5N	Roundabout			2		3			1				6			2	2	2	0.33	Convert high-speed rural intersection to roundabout ³	All	K	Rural	0.00	0.00
																								A		0.00	0.00
																								B		0.40	0.13
																								C		0.40	0.13
																								O		0.40	0.13
332.35	332.35	Road 6N	Align Road 6N on the east and west																								
333.40	333.40	Old Highway 89	Roundabout								2				2			1		1	0.33	Convert high-speed rural intersection to roundabout	All	K	Rural	0.00	0.00
																								A		0.00	0.00
																								B		0.20	0.07
																								C		0.00	0.00
																								O		0.20	0.07
334.50	334.50	Frontier Road	Roundabout											0						0.33	Convert high-speed rural intersection to roundabout	All	K	Rural	0.00	0.00	
																							A		0.00	0.00	
																							B		0.00	0.00	
																							C		0.00	0.00	
																							O		0.00	0.00	
335.78	335.78	Little Ranch Road	Install Left-Turn Lane			1		1	2			1		1	6	1	1			4	0.67	Install Left-Turn Lane*	All	K	Rural	0.20	0.13
																								A		0.20	0.13
																								B		0.00	0.00
																								C		0.00	0.00
																								O		0.80	0.54
335.78	335.78	Little Ranch Road	Install Right-Turn Lane			1		1	2			1		1	6	1	1			4	0.86	Install Right-Turn lane ⁴	All	K	All	0.20	0.17
																								A		0.20	0.17
																								B		0.00	0.00
																								C		0.00	0.00
																								O		0.80	0.69

Table 28 – Crash Modification Analysis for Intersection Improvements																											
Begin MP	End MP	Intersecting Road	Potential Improvement	Crashes												Injury Severity					CMF					Existing Crashes/ Year	Anticipated Crashes/ Year
				LT	O	RE	B	S	SV	HO	AG	AL	P	RR	TOTAL	K	A	B	C	O	CMF	Countermeasure	Application				
																							Crash Type	Crash Severity	Area Type		
337.00	337.11	N/A	Lighting			1	1					2			4				1	3	0.63	Install Lighting ⁵	Night-time	K	All	0.00	0.00
																								A		0.00	0.00
																								B		0.00	0.00
																								C		0.20	0.13
						0.84	Install Lighting ⁶	Night-time	O	All	0.60	0.50															
337.70	337.70	Big Chino Road	Roundabout			1						1			2					2	0.33	Convert high-speed rural intersection to roundabout	All	Rural	K	0.00	0.00
																									A	0.00	0.00
																									B	0.20	0.07
																									C	0.00	0.00
																									O	0.80	0.17
338.81	338.81	Bramble Drive	Roundabout	4						1					5	1	1	2		1	0.33	Convert high-speed rural intersection to roundabout	All	Rural	K	0.20	0.07
																									A	0.20	0.07
																									B	0.40	0.13
																									C	0.00	0.00
																									O	0.20	0.07

¹<http://www.cmfclearinghouse.org/detail.cfm?facid=4576>
²<http://www.cmfclearinghouse.org/detail.cfm?facid=4194>
³ <http://www.cmfclearinghouse.org/detail.cfm?facid=4695>
⁴ <http://www.cmfclearinghouse.org/cmfpdf.cfm?facid=285>
⁵<http://www.cmfclearinghouse.org/detail.cfm?facid=7774>
⁶<http://www.cmfclearinghouse.org/detail.cfm?facid=7775>
*From HSM

Table 29 – Crash Modification Analysis for Segment Improvements																													
Begin MP	End MP	Segment	Potential Improvement	Crashes												Injury Severity					CMF							Existing Crashes / Year	Anticipated Crashes/ Year
				LT	O	RE	B	S	SV	HO	AG	AL	P	RR	TOTAL	K	A	B	C	O	CMF	Countermeasure	Application						
																							Crash Type	Crash Severity	Area Type				
329.03	329.40	Butterfield Road to four to two-lane taper	Replace TWLTL with Raised Median	7	1	5		2				1			16			1	2	13	0.77	Replace TWLTL with Raised Median ¹	All	K	Urban	0.00	0.00		
																								A		0.00	0.00		
																								B		0.20	0.15		
																								C		0.40	0.31		
																								O		2.60	2.00		
329.40	330.20	Four to two-lane taper to Road 4N	Widen to 4-lane section with raised median	2	2	6		3	1				1	15		2	3		10	0.712	Convert 2 lane roadway to 4 lane divided roadway ²	All	K	Rural	0.00	0.00			
																							A		0.40	0.28			
																							B		0.60	0.43			
																							C		0.00	0.00			
																							O		2.00	1.42			
330.20	331.28	Road 4N to Road 5N	Widen to 4-lane section with raised median		3	3		3			1			3	13			2	2	9	0.712	Convert 2 lane roadway to 4 lane divided roadway ²	All	K	Rural	0.00	0.00		
																								A		0.00	0.00		
																								B		0.40	0.28		
																								C		0.40	0.28		
																								O		1.80	1.28		
333.40	334.50	Old Highway 89 to Frontier Road	Widen to 4-lane section with graded median			8		1			1	1		4	15		1	4	2	8	0.712	Convert 2 lane roadway to 4 lane divided roadway ²	All	K	Rural	0.00	0.00		
																								A		0.20	0.14		
																								B		0.80	0.57		
																								C		0.40	0.28		
																								O		1.60	1.14		
334.00	341.42	--	Wildlife warning signage																										

¹<http://www.cmfclearinghouse.org/detail.cfm?facid=2514>

²<http://www.cmfclearinghouse.org/detail.cfm?facid=7569>

10.1. Financial Benefit of Countermeasures

The financial benefit in terms of safety for each countermeasure with a corresponding CMF was obtained by comparing the number of existing crashes at a given severity to the anticipated number of crashes expected at a given severity over the anticipated life of the improvement. The lifespan of the countermeasure is assigned with the CMF. The cost per crash was determined using two bases for comparison, explained below and shown in **Table 30** and **Table 31**.

First, the crash costs provided in the 2015 Arizona Crash Facts Summary, published by ADOT and summarized in **Table 30**, were used to determine the economic loss associated with each crash type. This provides a cost for all crash severities. The financial benefit for each countermeasure using these values is shown in **Table 32**.

Table 30 – 2015 Arizona Crash Facts Summary Average Economic Cost per Incident	
Fatality	\$1,542,240
Incapacitating Injury	\$90,270
Non-incapacitating Injury	\$26,112
Possible Injury	\$21,420
Property Damage Only	\$11,526

"Cost estimates are based on a 2% increase of the 2014 National Safety Council estimates of the average cost of motor vehicle crashes, deaths, and injuries. These costs are an estimate of wage and productivity losses, medical expenses, administrative expenses, motor vehicle damage, and employer costs. A description of the National Safety Council's current cost estimating procedures may be found in the Technical Appendix of *Injury Facts*® (source: www.nsc.org/learn/safety-knowledge/Pages/injury-facts-estimating-cost-of-unintentional-injuries.aspx)."

The second costing method was based upon the HSIP application, which only assigns costs to fatal and incapacitating crashes as shown in **Table 31**. The HSIP B/C ratios are important because they are tied to a project's eligibility to receive this type of project funding. While MPOs and COGs currently receive HSIP allocations, the funds will be available on a competitive basis beginning in fiscal year 2019. The financial benefit for each countermeasure using these values is shown in **Table 33**.

Table 31 – 2017 HSIP Application Crash Severity Unit Costs	
Fatal	\$5,800,000
Incapacitating Injury	\$400,000

Table 32 – Financial Benefit of Countermeasures using 2015 Arizona Crash Facts Cost per Incident								
Begin MP	End MP	Intersecting Road	Potential Improvement	Existing Cost Per Year	Anticipated Cost Per Year	Net Benefit Per Year	Assumed Lifespan of Countermeasure	Total Financial Benefit of Countermeasure
329.20	329.20	Road 3N	Retime signal w/ protected left phase	\$18,727.20	\$187.27	\$18,539.93	20	\$370,798.56
329.20	329.20	Road 3N	Roundabout	\$55,569.60	\$45,011.38	\$10,558.22	20	\$211,164.48
331.27	331.27	Road 5N	Roundabout	\$23,623.20	\$7,795.66	\$15,827.54	20	\$316,550.88
332.35	332.35	Road 6N	Align Road 6N on the east and west	--	--	--	--	--
333.40	333.40	Old Highway 89	Roundabout	\$7,527.60	\$2,484.11	\$5043.49	20	\$100,869.84
334.50	334.50	Frontier Road	Roundabout	--	--	--	20	--
335.78	335.78	Little Ranch Road	Install left-turn lane	\$335,722.80	\$224,934.28	\$110,788.52	20	\$2,215,770.48
335.78	335.78	Little Ranch Road	Install right-turn lane	\$335,722.80	\$288,721.61	\$47,001.19	20	\$940,023.84
337.00	337.11	--	Lighting	\$11,199.60	\$8,508.02	\$2,691.58	20	\$53,831.52
337.70	337.70	Big Chino Road	Roundabout	\$4,610.40	\$1,521.43	\$3,088.97	20	\$61,779.36
338.81	338.81	Bramble Drive	Roundabout	\$339,252.00	\$111,953.16	\$227,298.84	20	\$4,545,976.80

Begin MP	End MP	Segment	Potential Improvement	Existing Cost Per Year	Anticipated Cost Per Year	Net Benefit Per Year	Assumed Lifespan of Countermeasure	Total Financial Benefit of Countermeasure
329.00	329.40	Butterfield Road to Road 3N	Convert TWLTL to Raised Median	\$43,758.00	\$33,693.66	\$10,064.34	20	\$201,286.80
329.40	330.20	Road 3N to Road 4N	Raised Median, 4 lanes	\$74,827.20	\$53,276.97	\$21,550.23	20	\$431,004.67
330.20	331.28	Road 4N to Road 5N	Raised Median, 4 lanes	\$39,759.60	\$28,308.84	\$11,450.76	20	\$229,015.30
333.40	334.50	Old Highway 89 to Frontier Road	Graded Median, 4 Lanes	\$65,953.20	\$46,958.68	\$18,994.52	20	\$379,890.43
334.00	341.42	--	Wildlife warning signage	--	--	--	--	--

Table 33 – Financial Benefit of Countermeasures using HSIP Cost per Incident								
Begin MP	End MP	Intersecting Road	Potential Improvement	Existing Cost Per Year	Anticipated Cost Per Year	Net Benefit Per Year	Assumed Lifespan of Countermeasure	Total Financial Benefit of Countermeasure
329.20	329.20	Road 3N	Retime signal w/ protected left phase					
329.20	329.20	Road 3N	Roundabout					
331.27	331.27	Road 5N	Roundabout					
332.35	332.35	Road 6N	Line up Road 6N on the east and west					
333.40	333.40	Old Highway 89	Roundabout					
334.50	334.50	Frontier Road	Roundabout					
335.78	335.78	Little Ranch Road	Install left-turn lane	\$1,240,000.00	\$830,800.00	\$409,200.00	20	\$8,184,000.00
335.78	335.78	Little Ranch Road	Install right-turn lane	\$1,240,000.00	\$1,066,400.00	\$173,600.00	20	\$3,472,000.00
337.00	337.11	--	Lighting					
337.70	337.70	Big Chino Road	Roundabout					
338.81	338.81	Bramble Drive	Roundabout	\$1,240,000.00	\$409,200.00	\$830,800.00	20	\$16,616,000.00

Begin MP	End MP	Segment	Potential Improvement	Existing Cost Per Year	Anticipated Cost Per Year	Net Benefit Per Year	Assumed Lifespan of Countermeasure	Total Financial Benefit of Countermeasure
329.00	329.40	Butterfield Road to Road 3N	Convert TWLTL to raised median	--	--	--	--	--
329.40	330.20	Road 3N to Road 4N	Raised Median, 4 lanes	\$160,000.00	\$113,920.00	\$46,080.00	20	\$921,600.00
330.20	331.28	Road 4N to Road 5N	Raised Median, 4 lanes	--	--			--
333.40	334.50	Old Highway 89 to Frontier Road	Graded Median, 4 Lanes	\$80,000.00	\$56,960.00	\$23,040.00	20	\$460,800.00
334.00	341.42	--	Wildlife warning signage	--	--	--	--	--

10.2. Benefit to Cost Ratio

The benefit to cost (B/C) ratio was determined by dividing the financial benefit in terms of safety for each countermeasure by the probable cost estimate. B/C ratios are summarized in **Table 34**. Improvements that did not have a financial benefit per Section 10.1 were excluded as the B/C ratio is zero.

Table 34 – Benefit to Cost Ratio for Potential Improvements			
Location	Potential Improvement	2015 Crash Facts B/C	2017 HSIP Application
Butterfield Road to Road 3N	Convert TWLTL to raised median	0.41	--
Road 3N	Retime signal w/ protected left phase	>100	--
Road 3N	Roundabout	0.11	
Road 3N to Road 4N	Raised Median, 4 lanes	0.07	0.16
Road 4N to Road 5N	Raised Median, 4 lanes	0.04	--
Road 5N	Roundabout	0.12	--
Old Highway 89	Roundabout	0.02	--
Old Highway 89 to Frontier Road	Graded Median, 4 Lanes	0.07	0.09
Little Ranch Road	Install left-turn lane	1.75	6.47
Little Ranch Road	Install right-turn lane	6.53	24.11
Paulden Post Office	Lighting	0.62	--
Big Chino Road	Roundabout	0.01	--
Bramble Drive	Roundabout	0.89	3.26

11.0 Evaluation of Potential Projects

11.1. Potential Projects

Improvements were combined into logical, constructible projects below and in **Appendix WP2-1**, the Recommendations Map Book. Each project description identifies the CMFs it includes. Projects are numbered from south to north.

Project P1A: Install Raised Median from Butterfield Road to Road 3N and Retime Signal at Road 3N

Description: This project combines two CMFs: 1) Converting the existing TWLTL to a raised median from Butterfield Road to Road 3N, and 2.) Provide a protected left-turn phase. The proposed section is the Urban Highway Typical Section UA as shown in Figure 306.4A of the ADOT RDG, modified to have an eight-foot wide raised median and five-foot wide sidewalk on both sides. The signal at Road 3N would be retimed with 100 second cycle for both peaks, with a protected-permitted southbound left-turn, protected only northbound left-turn, and permitted only eastbound and westbound left-turns.

Project P1B: Install Raised Median from Perkinsville Road to Road 3N with Roundabout at Road 3N

Description: This project combines two CMFs: 1) Converting the existing TWLTL to a raised median from Perkinsville Road to Road 3N, and 2.) Constructing a two-lane roundabout at Road 3N. The proposed section is the Urban Highway Typical Section UA as shown in Figure 306.4A of the ADOT RDG, modified to have an eight-foot wide raised median and five-foot wide sidewalk on both sides.

Project P2: Widen to Four-Lane Section with Raised Median from Road 3N to Road 4N

Description: This project combines two CMFs: 1) Converting the existing TWLTL to a raised median from Perkinsville Road to just north of Road 3N where the existing four to two-lane taper ends, and 2) Widening the road and adding a median between the four to two-lane taper and Road 4N. The proposed section is the Urban Highway Typical Section UA as shown in Figure 306.4A of the ADOT RDG, modified to have an eight-foot wide raised median and five-foot wide sidewalk on both sides. Road 3 1/2N will be a future roundabout, funded by private development.

Project P3: Widen to Four-Lane Section with Raised Median from Road 4N to Road 5N and Construct Roundabout at Road 5N

Description: This project combines two CMFs: 1) Widening the road and adding a median between Road 4N and Road 5N, and 2) Construct a two-lane roundabout at Road 5N. The proposed section is the Urban Highway Typical Section UA as shown in Figure 306.4A of the ADOT RDG, modified to have an eight-foot wide raised median and five-foot wide sidewalk on both sides. This project could be constructed in phases, with the roundabout at Road 5N as the first phase.

Project P4: Align Approaches at Road 6N

Description: This improvement was identified to address access; no corresponding CMF was identified. It includes reconstruction of the eastern and western approaches at the Road 6N intersection so that they align (offset approximately 70 feet).

Project P5: Widen to Four-Lane Section with Graded Median from Old Highway 89 to Frontier Road and Construct Roundabouts at Old Highway 89 and Frontier Road

Description: This project combines three CMFs: 1) widening the road and adding a median between Old Highway 89 to Frontier Road, 2) construct a two-lane roundabout at Old Highway 89, and 3) construct a two-lane roundabout at Frontier Road. The proposed section is the Fringe-Urban Highway Typical Section IS3 as shown in Figure 306.3 of the ADOT RDG. This project could be constructed in phases, with either/both roundabouts constructed as the first phase.

Project P6: Construct Left- and Right-Turn Lanes at Little Ranch Road

Description: This project implements the CMFs for adding left- and right- turn lanes at Little Ranch Road.

Project P7: Install lighting at Paulden Post Office

Description: This project implements the CMF for lighting at the Paulden Post Office. If possible, it should be incorporated in the project currently under development.

Project P8: Construct Roundabout at Big Chino Road

Description: This project implements the CMF for constructing a roundabout at Big Chino Road.

Project P9: Construct Roundabout at Bramble Drive

Description: This project implements the CMF for constructing a roundabout at Bramble Drive.

Project P10: Install Wildlife Warning Signage from MP 334 to MP 348

Description: This improvement was identified to improve alert drivers to the presence of wildlife per the recommendations of the Statewide Wildlife Crash Analysis and Proposed Action Plan; no corresponding CMF was identified. It includes signage from MP 334 to 348.

11.2. Evaluation Criteria

Potential improvements were evaluated using the following criteria:

- **Engineering features** – How challenging projects may be to implement and build, considering feasibility and difficulty of design and construction.
- **Property impacts** – How substantial potential improvements impact existing and planned land uses, including future development opportunities.
- **Environmental compatibility** – How potential improvements may impact the environment, such as the natural environment, land use, cultural resources, and socioeconomic factors. The likely extent of environmental permitting, investigations, and remediation was also considered.
- **Public input** – Input on potential improvements from stakeholders and the general public. The Public Involvement Summary is included as **Appendix WP2-5**.
- **Safety impact** – How well potential improvements may reduce crashes based upon analysis of five-year crash history with CMFs.
- **Access management impact** – How well potential improvements may improve access management.
- **Cost** – Planning-level cost estimate for each potential improvement in 2016 dollars.

11.3. Evaluation of Potential Improvements

The analysis of proposed improvements is summarized in **Figure 21**. The table includes a qualitative rating as follows for each criterion:

- (+) represents an advantage;
- (o) represents neutral impacts; and
- (-) represents a disadvantage.

The ratings will be used to determine whether potential improvements are feasible and to facilitate prioritization. The evaluation criteria are not weighted.

Figure 21 – Qualitative Project Evaluation

	Engineering Features	Property Impacts	Environmental Compatibility	Public Input	Safety Impact	Access Management Impact	Cost*
Project P1A	+	○	○	+	+	+	\$490,000
Project P1B	-	-	-	+	+	+	\$2,010,000
Project P2	○	○	○	+	+	+	\$5,890,000
Project P3	○	○	○	+	+	+	\$8,370,000
Project P4	○	-	○	○	○	+	\$480,000
Project P5	○	○	○	○	+	+	\$13,190,000
Project P6	○	○	○	+	+	+	\$1,410,000
Project P7	+	○	○	+	+	○	\$90,000
Project P8	○	○	○	○	+	+	\$4,540,000
Project P9	○	○	○	○	+	+	\$5,100,000
Project P10	+	○	+	+	+	○	\$3,000

*Potential right-of-way costs are not included.

Advantage + Neutral ○ Disadvantage -

11.4. Explanation of Ratings

The following describes anticipated advantages and disadvantages associated with each project. A neutral rating indicates no or balanced impacts, and was therefore not described.

Project P1A: There are no notable challenges associated with installing a raised median from Butterfield Road to Road 3N; there are safety and access management benefits. This project was well received by the public. This project maintains many of the advantages of Project P1B, with fewer disadvantages (assuming the CMF for adding a protected left-turn phase to the traffic signal performs as projected). These can be summarized as follows:

- Engineering features (+): median can be constructed within existing right-of-way; traffic signal improvements require no new infrastructure, simplifying implementation.
- Safety impact (+): the CMF for the raised median (0.77) is anticipated to reduce crashes of all types with a B/C ratio of 0.41 based on the Arizona Crash Facts Cost per Incident and 0 using HSIP cost per incident. The CMF for retiming the traffic signal at Road 3N is 0.01 and there is no cost associated with adding a protected left-turn phase to the traffic signal. The B/C ratio is >100 based on the Arizona Crash Facts Cost per Incident and 0 using the HSIP cost per incident.
- Access management impact (+): the median and protected left would eliminate left-turn conflicts. The median would also eliminate conflicts with vehicles making turns from opposite sides of the roadway and would improve corner clearance.
- Public Input (+): the public generally supported sidewalks and keeping the existing traffic signal.

Project P1B: While there are no notable challenges associated with installing a median from Perkinsville Road to Road 3N, there are engineering, property, and environmental challenges associated with the roundabout at Road 3N. There are safety and access management benefits associated with this project. These can be summarized as follows:

- Engineering features (-): limited right-of-way at Road 3N with adjacent development.
- Property impacts (-): Business on the southwest corner of Road 3N has parking within the likely roundabout footprint.
- Environmental compatibility (-): potentially historic property at the northwest corner of Road 3N; the property would likely be impacted by the roundabout footprint.
- Safety impact (+): Road 3N is the top crash location within the corridor. The CMF for the roundabout (0.81) and raised median (0.77) are anticipated to reduce crashes of all types and have B/C ratios of 0.11 and 0.41, respectively, based on the Arizona Crash Facts Cost per Incident and 0 using the HSIP cost per incident.
- Access management impact (+): both the roundabout and the raised median would eliminate left-turn conflicts. The raised median would also eliminate conflicts with vehicles making turns from opposite sides of the roadway and would improve corner clearance.
- Public Input (+): the public generally supported sidewalks. Some of the public expressed operational concerns with roundabouts, but most appeared to accept the safety benefits after receiving explanation from the Study Team.

Project P2: Widening to a four-lane section with a raised median from Road 3N to Road 4N has no strong disadvantages based upon the established evaluation criteria and has safety and access management advantages. These can be summarized as follows:

- Safety impact (+): the CMF for the widening/divided roadway (0.712) is anticipated to reduce crashes of all types and has a B/C ratio of 0.07 based on the Arizona Crash Facts Cost per Incident and 0.16 using the HSIP cost per incident.
- Access management impact (+): the median would eliminate left-turn conflicts, conflicts with vehicles making turns from opposite sides of the roadway, and would improve corner clearance.
- Public Input (+): the public generally supported sidewalks and safety improvements.

Project P3: Widening to a four-lane section with raised median from Road 4N to Road 5N and constructing a roundabout at Road 5N has no strong disadvantages based upon the established evaluation criteria, and has safety and access management advantages. These can be summarized as follows:

- Safety impact (+): the CMF for the roundabout (0.33) and widening/divided roadway (0.712) is anticipated to reduce crashes of all types and has B/C ratios of 0.12 and 0.04, respectively, based on the Arizona Crash Facts Cost per Incident and 0 using the HSIP cost per incident.
- Access management impact (+): both the roundabout and the raised median would eliminate left-turn conflicts. The median would eliminate conflicts with vehicles making turns from opposite sides of the roadway and would improve corner clearance.
- Public Input (+): the public generally supported sidewalks and safety improvements. Some of the public expressed operational concerns with roundabouts, but most appeared to accept the safety benefits after receiving explanation from the Study Team.

Project P4: Aligning the approaches at Road 6N has adverse property impacts. It was identified to improve access management; no corresponding CMF was identified. Therefore, there is no quantifiable safety benefit nor applicable B/C ratio. These can be summarized as follows:

- Property impacts (-): Private right-of-way would be required to align the intersection. The parcel is not currently developed nor part of a planned development.
- Access management impact (+): the offset intersection does not meet the guidelines provided in the *TRB Access Management Manual* (2014); aligning them would comply.
- Public Input (o): there were no recorded public comments related specifically to this project.

Project P5: Widening to a four-lane section with graded median from Old Highway 89 to Frontier Road and constructing roundabouts at Old Highway 89 and Frontier Road has no strong disadvantages based upon the established evaluation criteria, and has safety and access management advantages. These can be summarized as follows:

- Safety impact (+): the CMF for the roundabouts (0.33) and widening/divided roadway (0.712) is anticipated to reduce crashes of all types and has B/C ratios of 0.02, 0.07, and 0 based on the Arizona Crash Facts Cost per Incident for the roundabout at Old Highway 89, widening and dividing the roadway, and the roundabout at Frontier Road, respectively. These CMFs have B/C ratios of 0, 0.09, and 0, respectively, using the HSIP cost per incident.

- Access management impact (+): the roundabouts and the raised median would eliminate left-turn conflicts. The median would eliminate conflicts with vehicles making turns from opposite sides of the roadway and would improve corner clearance.
- Public Input (o): the public expressed concerns about safety in this area. Some of the public expressed operational concerns with roundabouts, but most appeared to accept the safety benefits after receiving explanation from the Study Team.

Project P6: There are no notable challenges associated with constructing left- and right-turn lanes at Little Ranch Road, and there are safety and access management advantages. These can be summarized as follows:

- Safety impact (+): the CMF for the left-turn lane (0.67) and right-turn lane (0.86) are anticipated to reduce crashes of all types and have B/C ratios of 1.75 and 6.53, respectively, based on the Arizona Crash Facts Cost per Incident and 6.47 and 24.11, respectively, using the HSIP cost per incident.
- Access management impact (+): the turn lanes would remove turning vehicles from the through lanes, thus improving operation.
- Public Input (+): the public supported turn lanes at this location.

Project P7: There are no notable challenges associated with installing lighting at the Paulden Post Office, and there are advantages for engineering features and safety impacts. These can be summarized as follows:

- Engineering features (+): lighting can be installed in the existing right-of-way, would not impact traffic during construction, and power is available at the site. Lighting could be implemented as part of a project currently under development.
- Safety impact (+): the CMF for lighting (0.63 and 0.84) are anticipated to reduce nighttime crashes of all types and have B/C ratios of 0.62 based on the Arizona Crash Facts Cost per Incident and 0 using the HSIP cost per incident.
- Public Input (+): the public supported lighting at various locations in the corridor.

Project P8: There are no notable challenges associated with constructing a roundabout at Big Chino Road, and there are safety and access management benefits. These can be summarized as follows:

- Safety impact (+): the CMF for the roundabout (0.33) is anticipated to reduce crashes of all types and has B/C ratio of 0.01 based on the Arizona Crash Facts Cost per Incident and 0 using the HSIP cost per incident.
- Access management impact (+): the roundabouts and the raised median would eliminate turning conflicts, provide an opportunity for U-turns, and fit with the long-term access management vision.
- Public Input (o): the public expressed concerns about safety in this area. Some of the public expressed operational concerns with roundabouts, but most appeared to accept the safety benefits after receiving explanation from the Study Team.

Project P9: There are no notable challenges associated with constructing a roundabout at Bramble Drive, and there are safety and access management benefits. These can be summarized as follows:

- Safety impact (+): the CMF for the roundabout (0.33) is anticipated to reduce crashes of all types and has B/C ratio of 0.89 based on the Arizona Crash Facts Cost per Incident and 3.26 using the HSIP cost per incident.
- Access management impact (+): the roundabout would eliminate turning conflicts, provide an opportunity for U-turns, and fit with the long-term access management vision.
- Public Input (o): the public expressed concerns about safety in this area. Some of the public expressed operational concerns with roundabouts, but most appeared to accept the safety benefits after receiving explanation from the Study Team.

Project P10: There are no notable challenges associated with installing wildlife warning signage from MP 334 to MP 348. There are engineering, environmental, and safety advantages. These can be summarized as follows:

- Engineering features (+): signage can be installed with little pre-installation activity.
- Environmental compatibility (+): signage to alert motorists could mitigate crashes involving animals.
- Safety impact (+): no corresponding CMF was identified; however, this segment of this corridor was identified as one of the top locations in the state for crashes involving animals. There is no quantifiable safety benefit nor applicable B/C ratio; however, sign installation would meet the recommendations of the Statewide Wildlife Crash Analysis and Proposed Action Plan developed by ADOT.
- Public Input (+): the public expressed concerns about antelope and other wildlife, though no specific comments on signage were recorded.

12.0 Recommendations

The following recommendations are based upon the five-year crash history, existing and anticipated development, stakeholder input, B/C ratios presented in **Table 34**, and the evaluations presented in **Figure 21**. Prioritization should be revisited if crash patterns or anticipated development change. Implementation could be impacted by the availability of potential partnerships or other funding opportunities.

In some cases, it may be desirable to construct improvements without constructing the entirety of the project; necessary sequencing has been identified to allow independent functionality.

For major highway reconstruction projects, such as adding lanes or a divided cross-section, a speed study should be conducted as soon as practical after all work has been completed and the roadway is open to free-flow traffic.

12.1. Near-term (5-year)

The following projects are recommended for implementation in the near-term:

- Project P1A: Install Raised Median from Butterfield Road to Road 3N and Retime Signal at Road 3N.
- Project P7: Install Lighting at Paulden Post Office.
- Project P10: Install Wildlife Warning Signage from MP 334 to MP 348.

These projects are lower cost. In addition to infrastructure improvements, access management should be considered for new development. It may be beneficial to conduct a safety campaign with targeting behavioral traits from the SHSP, including Slow Down, Buckle Up, Pay Attention, and Drive Sober.

12.2. Mid-term (10-year)

The following projects are recommended for implementation in the mid-term:

- Project P2: Widen to Four-Lane Section with Raised Median from Road 3N to Road 4N. Construct roundabout at Road 3 1/2N, as needed and funded by private development.
- Project P3: Widen to Four-Lane Section with Raised Median from Road 4N to Road 5N and Construct Roundabout at Road 5N.
- Project P6: Construct Left-and Right-Turn Lanes at Little Ranch Road.
- Project P8: Construct Roundabout at Big Chino Road.
- Project P9: Construct Roundabout at Bramble Drive.

Widening should begin at Road 3N and continue north to provide a consistent roadway section with the area south of the study area. This will maximize the access management and safety benefit associated with the divided roadway and widening as the majority of the existing conflict points and crashes occur in the southern extents of the corridor. Roundabouts that will accommodate U-turn and left-turn movements should be constructed at the same time or before the raised median.

12.3. Long-term (20-year)

The following projects are recommended for implementation in the long-term:

- Project P4: Align Approaches at Road 6N.
- Project P5: Widen to Four-Lane Section with Graded Median from Old Highway 89 to Frontier Road and Construct Roundabouts at Old Highway 89 and Frontier Road.

These recommendations are summarized in **Table 35**.

Table 35 – Project Recommendations

Project	Project Limits (MP)	Scope of Work	Planning Horizon	Estimate of Probable Cost
P1A – Install Raised Median from Butterfield Road to Road 3N and Retime Signal at Road 3N	329.03 – 329.20	Convert TWLTL to 8-foot raised median and construct 5-foot sidewalk on both sides, from Butterfield Road to Road 3N. Mill and overlay existing asphaltic concrete pavement; existing curb and gutter to remain. Retime the existing signal at Road 3N with a 100 second cycle for both peaks, with a protected permitted southbound left-turn, protected only northbound left-turn, and permitted only eastbound and westbound left-turns.	Near-term	\$490,000
P1B – Install Raised Median from Perkinsville Road to Road 3N with Roundabout at Road 3N	329.00 – 329.20	Convert TWLTL to 8-foot raised median and construct 5-foot sidewalk on both sides, from Perkinsville Road to Road 3N. Construct a two-lane roundabout at Road 3N.	Long-term	\$2,010,000
P2 – Widen to Four-Lane Section with Raised Median from Road 3N to Road 4N	329.20 – 330.20	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 3N to Road 4N roundabout. Construct future roundabout at Road 3 1/2N, funded by private development.	Mid-term	\$5,890,000
P3 – Widen to Four-Lane Section with Raised Median from Road 4N to Road 5N and Construct Roundabout at Road 5N	330.20 – 331.28	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 4N roundabout to proposed Road 5N Roundabout. This project could be constructed in phases, with the roundabout at Road 5N as the first phase.	Mid-term	\$8,370,000
P4 – Align Approaches at Road 6N	332.35	Reconstruct the east and westbound approaches at the Road 6N intersection so that they align (offset approximately 70 feet).	Long-term	\$480,000
P5 – Widen to Four-Lane Section with Graded Median from Old Highway 89 to Frontier Road and Construct Roundabouts at Old Highway 89 and Frontier Road	333.41 – 334.50	Widen to a four-lane facility conforming to ADOT's fringe urban typical section, with no curb and a standard width, graded median between Old Highway 89 and Frontier Road. Construct two-lane roundabouts at Old Highway 89 and Frontier Road. This project could be constructed in phases, with either/both roundabouts constructed as the first phase.	Long-term	\$13,190,000

Table 35 – Project Recommendations

Project	Project Limits (MP)	Scope of Work	Planning Horizon	Estimate of Probable Cost
P6 – Construct Left- and Right-Turn Lanes at Little Ranch Road	335.77	Construct left- and right-turn lanes at Little Ranch Road.	Mid-term	\$1,410,000
P7 – Install Lighting at Paulden Post Office	337.05	Install street lighting at the Paulden post office. Cost and CMF assume spot lighting with four poles. Bundling this project with the currently programmed project should be considered.	Near-term	\$90,000
P8 – Construct Roundabout at Big Chino Road	337.70	Construct a two-lane roundabout. This project could be bundled with the roundabout at Bramble Drive or constructed sequentially as needed.	Mid-term	\$4,540,000
P9 – Construct Roundabout at Bramble Drive	338.80	Construct a two-lane roundabout. This project could be bundled with the roundabout at Big Chino Road or constructed sequentially as needed.	Mid-term	\$5,100,000
P10 – Install Wildlife Warning Signage from MP 334 to MP 348	334.00 – 348.00	Install wildlife warning signage from MP 334 to 348.	Near-term	\$3,000

13.0 Field Review and Preliminary Scoping

The Study Team selected five of the recommended projects for further evaluation, including a field review and preliminary scoping (prescoping) based on the anticipated availability of funding and the recommended implementation schedule. The prescoping process facilitates programming projects by refining the project costs and schedule. The five projects are:

- Project P1A and P2: Widen to Four-Lane Section with Raised Median from Butterfield Road to Road 4N and retime the existing traffic signal at Road 3N.
- Project P6: Construct Left- and Right-Turn Lanes at Little Ranch Road.
- Project P8: Construct Roundabout at Big Chino Road.
- Project P9: Construct Roundabout at Bramble Drive.

The purpose of the field review is to assemble a knowledgeable team to identify known and potential engineering issues and deficiencies within the project study area. Prior to the field review, background data is assembled and presented to the team. The findings from the field review, including the background data, are documented using a Field Review Report and used to develop a Prescoping Report. The Field Review Report summarizes study area details including background data, bridge design, bridge hydraulics/drainage, environmental, geotechnical, pavement/materials, right-of-way, roadway/drainage, traffic/safety, utilities, and ADOT district constructability and maintenance.

The purpose of a Preliminary Scoping Report is to develop a scope of work; schedule; and planning level cost estimate to complete project design, obtain clearances, and construction. The Preliminary Scoping Report includes general project information, project need and purpose, risks, potential funding sources, cost estimate, and recommended project delivery method.

The field review was conducted on January 11, 2017. Preliminary Scoping Reports, including the Field Review Reports with kickoff meeting summaries identifying attendees, are included in Appendix FR-1.

APPENDIX WP1-1
Current Conditions Summary Map Book

**State Route 89 Chino Valley to Forest Boundary
Transportation Study**

ADOT Task Assignment MPD 0034-16

Appendix WP1-1 Current Conditions Summary Map Book

Prepared for:




AND



Prepared by:

BURGESS & NIPLE




MAP BOOK INDEX		
Area	Map Book Page No.	SR 89 Milepost Range
Chino Valley	1 – 10, 13 – 14	328.95 – 333.68, 335.22 – 335.77
Yavapai County	10 – 13, 14 – 25	333.68 – 335.22, 335.77 – 341.42

SYMBOLS	
	Left Turn Phasing – Protected/Permissive

Crash/Injury Type		
Injury	Symbol	Driver Impairment**
Fatal		
Incapacitating		
Non-Incapacitating		
Possible Injury		
No Injury Reported		

** Driver Impairment includes Alcohol, Illness, Physical Impairment, Fell Asleep/Fatigue, Drugs, Medications, Other, and Unknown



Page 1 of 25

CRASH HISTORY (2011-2015)										
Contributing Factors	Night Condition	25%	x		23%	7%	x			
	Incliment Weather	8%	x		8%	20%				
Driver Impairment (DI)	Alcohol/Drugs	x				x	x			
	Illness									
	Other/Unknown	x	x		x	x				
	Medications					x				
	Fatigue	x								
ROADWAY FEATURES										
Total Approximate R/W Width		100FT <—————> 100FT				125 FT <—————> 125 FT	200 FT <—————> 200 FT			
Rumble Strip										
Roadway Grade										
Overhead Power		10 FT SB EOP <—————> 10 FT SB EOP								
SB	Level of Service	2016*	LOS B							
		2036	LOS B							
	Right Turn Lane									
	Shoulder								10 FT	10 FT
	Access									
	Curb									
Centerline	Passing/No Passing									
	Left Turn Lane									
NB	Curb									
	Access									
	Shoulder								10 FT	10 FT
	Right Turn Lane									
	Level of Service	2016*	LOS A							
		2036	LOS B							

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 2 of 25

CRASH HISTORY (2011-2015)						
Contributing Factors	Night Condition		x			
	Incliment Weather					
Driver Impairment (DI)	Alcohol/Drugs					
	Illness					
	Other/Unknown					
	Medications					
	Fatigue					
ROADWAY FEATURES						
Total Approximate R/W Width		200 FT	< 200 FT			
Rumble Strip						
Roadway Grade						
Overhead Power		20 FT SB EOP	< 20 FT SB EOP			
SB	Level of Service	2016*	LOS B			
		2036	LOS B			
	Right Turn Lane					
	Shoulder		10 FT	10 FT		
	Access					
Centerline	Curb					
	Passing/No Passing					
NB	Left Turn Lane					
	Curb					
	Access					
	Shoulder		10 FT	10 FT		
	Right Turn Lane					
	Level of Service	2016*	LOS A			
		2036	LOS B			

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian


RR

Run off the road

Page 3 of 25

CRASH HISTORY (2011-2015)															
Contributing Factors	Night Condition		20%	18%											
	Incliment Weather		20%	18%											
Driver Impairment (DI)	Alcohol/Drugs		x												
	Illness														
	Other/Unknown		x	x											
	Medications			x											
	Fatigue			x											
ROADWAY FEATURES															
Total Approximate R/W Width		200 FT	←												
Rumble Strip															
Roadway Grade															
Overhead Power		20 FT SB EOP	←			20 FT SB EOP	20 FT NB EOP	←	20 FT NB EOP						
SB	Level of Service	2016*	LOS B	LOS A											
		2036	LOS B	LOS A											
	Right Turn Lane														
	Shoulder		10 FT	10 FT		10 FT									
	Access														
Centerline	Curb														
	Passing/No Passing														
NB	Left Turn Lane														
	Curb														
	Access														
	Shoulder		10 FT	10 FT		10 FT									
	Right Turn Lane														
	Level of Service	2016*	LOS A												
		2036	LOS B	LOS A											

7/01/2016



Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 5 of 25

CRASH HISTORY (2011-2015)															
Contributing Factors	Night Condition		x						x						
	Incliment Weather														
Driver Impairment (DI)	Alcohol/Drugs		x						x						
	Illness														
	Other/Unknown		x												
	Medications														
	Fatigue		x												
ROADWAY FEATURES															
Total Approximate R/W Width		200 FT <		> 200 FT		125 FT <		> 125 FT							
Rumble Strip															
Roadway Grade															
Overhead Power		20 FT NB EOP <		> 20 FT NB EOP		SB 80 FT FROM EOP <		> SB 80 FT FROM EOP							
SB	Level of Service	2016*	LOS A												
		2036	LOS A												
	Right Turn Lane														
	Shoulder		10 FT						10 FT						
	Access														
Centerline	Passing/No Passing														
	Left Turn Lane														
NB	Curb														
	Access														
	Shoulder		10 FT						10 FT						
	Right Turn Lane														
	Level of Service	2016*	LOS A												
		2036	LOS A												

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL


Animal

P

Pedestrian

RR

Run off the road



CRASH HISTORY (2011-2015)									
Contributing Factors	Night Condition		x						
	Incliment Weather								
Driver Impairment (DI)	Alcohol/Drugs								
	Illness								
	Other/Unknown								
	Medications								
	Fatigue								
ROADWAY FEATURES									
Total Approximate R/W Width			125 FT <=> 125 FT 200 FT < > 200 FT						
Rumble Strip									
Roadway Grade									
Overhead Power			SB 80 FT FROM EOP < > SB 80 FT FROM EOP						
SB	Level of Service	2016*	LOS A						
		2036	LOS A						
	Right Turn Lane								
	Shoulder		10 FT					10 FT	
	Access								
	Curb								
Centerline	Passing/No Passing								
	Left Turn Lane								
NB	Curb								
	Access								
	Shoulder		10 FT					10 FT	
	Right Turn Lane								
	Level of Service	2016*	LOS A						
		2036	LOS A						

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 7 of 25

CRASH HISTORY (2011-2015)				
Contributing Factors	Night Condition			
	Incliment Weather			
Driver Impairment (DI)	Alcohol/Drugs			
	Illness			
	Other/Unknown			
	Medications			
	Fatigue			
ROADWAY FEATURES				
Total Approximate R/W Width		200 FT	<	> 200 FT
Rumble Strip				
Roadway Grade				
Overhead Power		SB 80 FT FROM EOP < > SB 80 FT FROM EOP		
SB	Level of Service	2016*	LOS A	
		2036	LOS A	
	Right Turn Lane			
	Shoulder		10 FT	10 FT
	Access			
Centerline	Curb			
	Passing/No Passing			
NB	Left Turn Lane			
	Curb			
	Access			
	Shoulder		10 FT	10 FT
	Right Turn Lane			
	Level of Service	2016*	LOS A	
		2036	LOS A	

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 8 of 25

CRASH HISTORY (2011-2015)															
Contributing Factors	Night Condition		x						x x x						
	Incliment Weather														
Driver Impairment (DI)	Alcohol/Drugs														
	Illness														
	Other/Unknown														
	Medications														
	Fatigue														
ROADWAY FEATURES															
Total Approximate R/W Width		200 FT							200 FT						
Rumble Strip															
Roadway Grade															
Overhead Power		SB 80 FT FROM EOP < > SB 80 FT FROM EOP													
SB	Level of Service	2016*	LOS A												
		2036	LOS A												
	Right Turn Lane														
	Shoulder		10 FT						10 FT						
	Access														
Centerline	Curb														
	Passing/No Passing														
NB	Left Turn Lane														
	Curb														
	Access														
	Shoulder		10 FT						10 FT						
	Right Turn Lane														
	Level of Service	2016*	LOS A												
		2036	LOS A												

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 9 of 25

CRASH HISTORY (2011-2015)															
Contributing Factors	Night Condition								x						
	Incliment Weather								x						
Driver Impairment (DI)	Alcohol/Drugs														
	Illness														
	Other/Unknown														
	Medications														
	Fatigue														
ROADWAY FEATURES															
Total Approximate R/W Width		200 FT							> 200FT						
Rumble Strip															
Roadway Grade															
Overhead Power		SB 80 FT FROM EOP < > SB 80 FT FROM EOP NB 80 FT FROM EOP < > NB 80 FT FROM EOP													
SB	Level of Service	2016*	LOS A												
		2036	LOS A												
	Right Turn Lane														
	Shoulder		10 FT						10 FT						
	Access														
Centerline	Curb														
	Passing/No Passing														
NB	Left Turn Lane														
	Curb														
	Access														
	Shoulder		10 FT						10 FT						
	Right Turn Lane														
Level of Service	2016*		LOS A												
	2036		LOS A												

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 10 of 25

CRASH HISTORY (2011-2015)																
Contributing Factors	Night Condition															
	Incliment Weather															
Driver Impairment (DI)	Alcohol/Drugs															
	Illness															
	Other/Unknown															
	Medications															
	Fatigue															
ROADWAY FEATURES																
Total Approximate R/W Width			200 FT <													
Rumble Strip																
Roadway Grade																
Overhead Power			NB 80 FT FROM EOP <													
SB	Level of Service	2016*	LOS A													
		2036	LOS A													
	Right Turn Lane															
	Shoulder		10 FT													
	Access															
Centerline	Curb															
	Passing/No Passing															
NB	Left Turn Lane															
	Curb															
	Access															
	Shoulder		10 FT													
	Right Turn Lane															
	Level of Service	2016*	LOS A													
		2036	LOS A													

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 11 of 25

CRASH HISTORY (2011-2015)						
Contributing Factors	Night Condition		x	20%		
	Incliment Weather		x	20%		
Driver Impairment (DI)	Alcohol/Drugs					
	Illness					
	Other/Unknown					
	Medications	x				
	Fatigue	x	x			
ROADWAY FEATURES						
Total Approximate R/W Width		200 FT	> 200 FT			
Rumble Strip						
Roadway Grade						
Overhead Power		NB 80 FT FROM EOP >				
SB	Level of Service	2016*	LOS A			
		2036	LOS A			
	Right Turn Lane					
	Shoulder	10 FT	10 FT			
	Access					
Centerline	Passing/No Passing					
	Left Turn Lane					
NB	Curb					
	Access					
	Shoulder	10 FT	10 FT			
	Right Turn Lane					
	Level of Service	2016*	LOS A			
		2036	LOS A			

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 12 of 25

CRASH HISTORY (2011-2015)																								
Contributing Factors	Night Condition		x		x																			
	Incliment Weather		x																					
Driver Impairment (DI)	Alcohol/Drugs																							
	Illness																							
	Other/Unknown		x																					
	Medications																							
	Fatigue																							
ROADWAY FEATURES																								
Total Approximate R/W Width		200 FT	<-----> 200 FT																					
Rumble Strip																								
Roadway Grade																								
Overhead Power		NB 80 FT FROM EOP	SB 80 FT FROM EOP <-----> SB 80 FT FROM EOP																					
SB	Level of Service	2016*	LOS A																					
		2036	LOS A																					
	Right Turn Lane																							
	Shoulder		10 FT						10 FT															
	Access																							
Centerline	Curb																							
	Passing/No Passing																							
NB	Left Turn Lane																							
	Curb																							
	Access																							
	Shoulder		10 FT						10 FT															
	Right Turn Lane																							
	Level of Service	2016*	LOS A																					
		2036	LOS A																					

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 13 of 25

CRASH HISTORY (2011-2015)																	
Contributing Factors	Night Condition		x		x		x										
	Incliment Weather				x												
Driver Impairment (DI)	Alcohol/Drugs		x														
	Illness																
	Other/Unknown																
	Medications																
	Fatigue							x									
ROADWAY FEATURES																	
Total Approximate R/W Width		200 FT							200 FT								
Rumble Strip																	
Roadway Grade																	
Overhead Power		SB 80 FT FROM EOP < SB 80 FT FROM EOP NB 80 FT FROM EOP >															
SB	Level of Service	2016*	LOS A														
		2036	LOS A														
	Right Turn Lane																
	Shoulder		10 FT						10 FT								
	Access																
Centerline	Curb																
	Passing/No Passing																
NB	Left Turn Lane																
	Curb																
	Access																
	Shoulder		10 FT						10 FT								
	Right Turn Lane																
Level of Service	2016*		LOS A														
	2036		LOS A														

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 14 of 25

CRASH HISTORY (2011-2015)						
Contributing Factors	Night Condition		80%			
	Incliment Weather		40%			
Driver Impairment (DI)	Alcohol/Drugs		x			
	Illness		x			
	Other/Unknown					
	Medications					
	Fatigue					
ROADWAY FEATURES						
Total Approximate R/W Width		200 FT	> 200 FT			
Rumble Strip						
Roadway Grade						
Overhead Power		NB 80 FT FROM EOP < > NB 80 FT FROM EOP				
SB	Level of Service	2016*	LOS A			
		2036	LOS A			
	Right Turn Lane					
	Shoulder		10 FT	10 FT		
	Access					
Centerline	Passing/No Passing					
	Left Turn Lane					
NB	Curb					
	Access					
	Shoulder		10 FT	10 FT		
	Right Turn Lane					
	Level of Service	2016*	LOS A			
		2036	LOS A			

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL


Animal

P

Pedestrian

RR

Run off the road



CRASH HISTORY (2011-2015)				
Contributing Factors	Night Condition		x	
	Incliment Weather			
Driver Impairment (DI)	Alcohol/Drugs			
	Illness		x	
	Other/Unknown			
	Medications			
	Fatigue			
ROADWAY FEATURES				
Total Approximate R/W Width		200 ft < > 200 ft		
Rumble Strip				
Roadway Grade				
Overhead Power		NB 80 FT FROM EOP < > NB 80 FT FROM EOP		
SB	Level of Service	2016*	LOS A	
		2036	LOS A	
	Right Turn Lane			
	Shoulder		10 FT	
	Access			
	Curb			
Centerline	Passing/No Passing			
	Left Turn Lane			
NB	Curb			
	Access			
	Shoulder		10 FT	
	Right Turn Lane			
	Level of Service	2016*	LOS A	
		2036	LOS A	

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

0

100

200

400

Feet

0

0.025

0.05

0.1

Miles

STIP FY 2018: Design and construct two auxiliary lanes and a continuous left turn lane.

STATE ROUTE 89

337

AG

W27

REAG

E51

P

RE

HO

E52

W28

E53

E54

AL

RE

AL

RE

B

SWEET VALLEY RD

OLD HIGHWAY 89

Eagle Nest Area Shaded Orange

Proposed Future Chino Valley Corridor Shaded Purple

CRASH HISTORY (2011-2015)									
Contributing Factors	Night Condition							x	60%
	Incliment Weather							x	20%
Driver Impairment (DI)	Alcohol/Drugs								
	Illness								
	Other/Unknown		x					x	x
	Medications								
	Fatigue								
ROADWAY FEATURES									
Total Approximate R/W Width			200 FT <-----> 200 FT						
Rumble Strip									
Roadway Grade									
Overhead Power			> SB 80 FT FROM EOP <-----> SB 80 FT FROM EOP						
SB	Level of Service	2016*	LOS A						
		2036	LOS A						
	Right Turn Lane								
	Shoulder		10 FT						10 FT
	Access								
Curb									
Centerline	Passing/No Passing								
	Left Turn Lane								
NB	Curb								
	Access								
	Shoulder		10 FT						10 FT
	Right Turn Lane								
	Level of Service	2016*	LOS A						
2036		LOS A							

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 17 of 25

CRASH HISTORY (2011-2015)																		
Contributing Factors	Night Condition																	
	Incliment Weather																	
Driver Impairment (DI)	Alcohol/Drugs																	
	Illness																	
	Other/Unknown																	
	Medications																	
	Fatigue																	
ROADWAY FEATURES																		
Total Approximate R/W Width			200 FT <		> 200 FT													
Rumble Strip																		
Roadway Grade																		
Overhead Power			SB 80 FT FROM EOP		NB AND SB 80 FT FROM EOP <		> NB AND SB 80 FT FROM EOP		SB 80 FT FROM EOP <		> SB 80 FT FROM EOP							
SB	Level of Service	2016*	LOS A															
		2036	LOS A															
	Right Turn Lane																	
	Shoulder		10 FT		10 FT 8 FT					8 FT								
	Access																	
Centerline	Curb																	
	Passing/No Passing																	
NB	Left Turn Lane																	
	Curb																	
	Access																	
	Shoulder		10 FT							10 FT								
	Right Turn Lane																	
Level of Service		2016*	LOS A															
		2036	LOS A															

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 18 of 25

CRASH HISTORY (2011-2015)																
Contributing Factors	Night Condition		50%				X									
	Incliment Weather						X		X							
Driver Impairment (DI)	Alcohol/Drugs		X													
	Illness															
	Other/Unknown								X							
	Medications															
	Fatigue		X													
ROADWAY FEATURES																
Total Approximate R/W Width		200 FT		<		>		200 FT								
Rumble Strip																
Roadway Grade																
Overhead Power		SB 80 FT FROM EOP		<		>		SB 80 FT FROM EOP								
SB	Level of Service	2016*	LOS A													
		2036	LOS A													
	Right Turn Lane															
	Shoulder		8 FT						8 FT							
	Access															
Curb																
Centerline	Passing/No Passing															
	Left Turn Lane															
NB	Curb															
	Access															
	Shoulder		10 FT					10 FT 8 FT	8 FT							
	Right Turn Lane															
	Level of Service	2016*	LOS A													
		2036	LOS A													

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 19 of 25

CRASH HISTORY (2011-2015)																
Contributing Factors	Night Condition		x													
	Incliment Weather		x													
Driver Impairment (DI)	Alcohol/Drugs		x													
	Illness															
	Other/Unknown															
	Medications															
	Fatigue															
ROADWAY FEATURES																
Total Approximate R/W Width		200 FT	< 200 FT													
Rumble Strip																
Roadway Grade																
Overhead Power																
SB	Level of Service	2016*	LOS A													
		2036	LOS A													
	Right Turn Lane															
	Shoulder		8 FT						8 FT							
	Access															
Centerline	Curb															
	Passing/No Passing															
NB	Left Turn Lane															
	Curb															
	Access															
	Shoulder		8 FT						8 FT							
	Right Turn Lane															
	Level of Service	2016*	LOS A													
		2036	LOS A													

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 20 of 25

CRASH HISTORY (2011-2015)																					
Contributing Factors	Night Condition		x	25%																	
	Incliment Weather		x	25%																	
Driver Impairment (DI)	Alcohol/Drugs																				
	Illness																				
	Other/Unknown																				
	Medications																				
	Fatigue			x																	
ROADWAY FEATURES																					
Total Approximate R/W Width		200 FT																			
Rumble Strip																					
Roadway Grade																					
Overhead Power																					
SB	Level of Service	2016*	LOS A																		
		2036	LOS A																		
	Right Turn Lane																				
	Shoulder		8 FT						8 FT												
	Access																				
Centerline	Curb																				
	Passing/No Passing																				
NB	Left Turn Lane																				
	Curb																				
	Access																				
	Shoulder		8 FT						8 FT												
	Right Turn Lane																				
	Level of Service	2016*	LOS A																		
		2036	LOS A																		

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 21 of 25

CRASH HISTORY (2011-2015)						
Contributing Factors	Night Condition		x			
	Incliment Weather					
Driver Impairment (DI)	Alcohol/Drugs					
	Illness					
	Other/Unknown					
	Medications					
	Fatigue					
ROADWAY FEATURES						
Total Approximate R/W Width		200 FT	< 200 FT			
Rumble Strip						
Roadway Grade						
Overhead Power						
SB	Level of Service	2016*	LOS A			
		2036	LOS A			
	Right Turn Lane					
	Shoulder		8 FT	8 FT		
	Access					
Centerline	Curb					
	Passing/No Passing					
NB	Left Turn Lane					
	Curb					
	Access					
	Shoulder		8 FT	8 FT		
	Right Turn Lane					
	Level of Service	2016*	LOS A			
		2036	LOS A			

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 22 of 25

CRASH HISTORY (2011-2015)																	
Contributing Factors	Night Condition																
	Incliment Weather		x														
Driver Impairment (DI)	Alcohol/Drugs																
	Illness																
	Other/Unknown																
	Medications																
	Fatigue																
ROADWAY FEATURES																	
Total Approximate R/W Width			200 FT	<													
Rumble Strip																	
Roadway Grade																	
Overhead Power																	
SB	Level of Service	2016*	LOS A														
		2036	LOS A														
	Right Turn Lane																
	Shoulder		8 FT						8 FT								
	Access																
Centerline	Curb																
	Passing/No Passing																
NB	Left Turn Lane																
	Curb																
	Access																
	Shoulder		8 FT						8 FT								
	Right Turn Lane																
	Level of Service	2016*	LOS A														
		2036	LOS A														

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL


Animal

P

Pedestrian

RR

Run off the road



CRASH HISTORY (2011-2015)									
Contributing Factors	Night Condition		x						
	Incliment Weather								
Driver Impairment (DI)	Alcohol/Drugs								
	Illness								
	Other/Unknown								
	Medications								
	Fatigue		x						
ROADWAY FEATURES									
Total Approximate R/W Width			200 FT < > 200 FT						
Rumble Strip									
Roadway Grade									
Overhead Power									
SB	Level of Service	2016*	LOS A						
		2036	LOS A						
	Right Turn Lane								
	Shoulder		8 FT 8 FT 6 FT 6 FT						
	Access								
Curb									
Centerline	Passing/No Passing								
	Left Turn Lane								
NB	Curb								
	Access								
	Shoulder		8 FT 8 FT 6 FT 6 FT						
	Right Turn Lane								
	Level of Service	2016*	LOS A						
2036		LOS A							

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Map showing State Route 89 and surrounding area. The map includes a legend, a scale bar, and a north arrow. The road is labeled 'STATE ROUTE 89' and '341'. The map shows various crash types and locations, with a legend for 'SR 89 Crash Data' and 'Crash Type'. The map also shows '404 Permitted Resource' and 'Prescott National Forest Shaded Green'.

Page 24 of 25

CRASH HISTORY (2011-2015)																
Contributing Factors	Night Condition															
	Incliment Weather															
Driver Impairment (DI)	Alcohol/Drugs															
	Illness															
	Other/Unknown															
	Medications															
	Fatigue															
ROADWAY FEATURES																
Total Approximate R/W Width		200 FT	< 200 FT													
Rumble Strip																
Roadway Grade																
Overhead Power																
SB	Level of Service	2016*	LOS A													
		2036	LOS A													
	Right Turn Lane															
	Shoulder		6 FT						6 FT							
	Access															
Centerline	Curb															
	Passing/No Passing															
NB	Left Turn Lane															
	Curb															
	Access															
	Shoulder		6 FT						6 FT							
	Right Turn Lane															
	Level of Service	2016*	LOS A													
		2036	LOS A													

7/01/2016

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Driveway

Intersection – Signal

Intersection – Stop

Roundabout

SR 89 Crash Data

Fatal

Fatal – DI

Incapacitating

Incapacitating – DI

Non-Incapacitating

Non-Incapacitating – DI

Possible Injury

Possible Injury – DI

No Injury

No Injury – DI

Crash Type

LT

Left Turn

O

Other

RE

Rear End

B

Rear-to-Rear/Side (Backing)

S

Sideswipe

SV

Single Vehicle

HO

Head On

AG

Angle

AL

Animal

P

Pedestrian

RR

Run off the road

Page 25 of 25

CRASH HISTORY (2011-2015)															
Contributing Factors	Night Condition		x			x									
	Incliment Weather					x									
Driver Impairment (DI)	Alcohol/Drugs														
	Illness														
	Other/Unknown														
	Medications														
	Fatigue		x												
ROADWAY FEATURES															
Total Approximate R/W Width			200 FT <			> 200 FT									
Rumble Strip															
Roadway Grade															
Overhead Power															
SB	Level of Service	2016*	LOS A												
		2036	LOS A												
	Right Turn Lane														
	Shoulder		6 FT			6 FT									
	Access														
Centerline	Curb														
	Passing/No Passing														
NB	Left Turn Lane														
	Curb														
	Access														
	Shoulder		6 FT			6 FT									
	Right Turn Lane														
	Level of Service	2016*	LOS A												
		2036	LOS A												

7/01/2016

APPENDIX WP1-2
Reference Document Catalog

**SR 89 Chino Valley to Forest Boundary Transportation Study
Reference Documents Summary Table**

ID	Document				Source			
	Title	Description	Author	Dated	Provider	Contact	Date Provided	Collected By
B-001	Arizona 2014 Strategic Highway Safety Plan	statewide safety plan	various	Dec 2014	internet	N/A		DB
B-002	Chino Valley Extension Corridor Feasibility Study	feasibility study for corridor expansion from Regional Transportation Study	Civiltec/HDR	Feb 2009	internet	N/A		DB
B-003	CYMPO Regional Transportation Plan Update 2040	Update of 2011 RTP to prioritize transportation investments	CYMPO	Apr 2015	internet	N/A		DB
B-004	Town of Chino Valley General Plan 2014	Plan of improvements for growth and development	Dava & Associates	May 2014	internet	N/A		DB
B-005	FEMA Fimettes	Flood Insurance Rate Map for study area	FEMA	Sep 2010	internet	N/A		DB
B-006	Functional Classification Maps for Yavapai County and Chino Valley	Maps indicating roadway functional classification	ADOT	8/2013 and 3/2005	internet	N/A	Feb 2016	CA
B-007	ADOT 2014 AADT Report	2013 traffic volumes	ADOT	2014	internet	N/A	Feb 2016	DB
B-008	Chino Valley Unified Development Ordinance	zoning uses	RBF	N/A	internet	N/A	Feb 2016	DB
B-009	Yavapai County Comprehensive Plan	plan for future development	Yavapai County	Sep 2012	internet	N/A	Feb 2016	DB
B-010	Cable One utility info				CableOne	Johnny Cedillo	Feb 2016	DB
B-011	2015/2016 Class C Permits		ADOT	Feb 2016	ADOT	Christina Pippin	Feb 2016	DB
B-012	AASHTO US Bicycle Route System		Kimley Horn & Lee Engineering	Aug 2015	internet	N/A	Feb 2016	DB
B-013	APS utility info	overhead and underground utility information	Arizona Public Service	Feb 2016	APS	N/A	Feb 2016	CA
B-014	City's Water Service Area Within the Town of Chino Valley	Prescott water service area map	City of Prescott	Oct 2015	internet	N/A	Feb 2016	DB
B-015	Del Rio Ranch Development	Summary fact sheet						
B-016	Abra Water Company	map showing existing and proposed water line	Abra Water Company		Abra Water Co	Rod Yarbro	Mar 2016	CA
B-017	UniSource Energy	facility maps along SR 89	UniSource Energy Services	Mar 2016	UniSource Energy	Ken Manson	Mar 2016	CA
B-018	Arizona Roadway Departure Safety Implementation Plan		FHWA	May 2012	ADOT	Kohinoor Kar	Apr 2016	DB
B-019	Road 4N and Perkinsville Road Imp. Plans	line work and plans	Parsons		Parsons	Scott Sayles	Apr 2016	TC
B-020	Arizona State Highway Access Policy and Legislation Study		Lima & Associates, DMJM Harris	Mar 2001	ADOT	Dan Gabiou	Apr 2016	JP
B-021	Access Management Guidelines (draft)	ADOT draft access management guidelines	ADOT	Nov 2014	ADOT	Justin Feek	Mar 2015	JP
B-022	ADOT STIP FY 2016-2020		ADOT		internet		Apr 2016	DB
B-023	ADOT State Highway 89 As-Built	As-builts for projects along 89	ADOT		ADOT	N/A	May 2016	DL
B-024	Fatal Crash in Paulden	News article for crash 2/26/2016	The Daily Courier	2/1/2016	internet	N/A	May 2016	CA
B-025	2014 Motor Vehicle Crash Facts for the State of Arizona		ADOT	1-Jun-15	internet	N/A	May 2016	DB
B-026	Yavapai Regional Transit, Inc.	transit maps, flyer regarding service to Paulden	Yavapai Regional Transit, Inc.		internet	N/A	May 2016	DL
B-027	Del Rio Ranch Development Information	Council Meeting summaries, Preliminary Plat cover, etc.	various	various	Chino Valley	James Gardner	May 2016	DB
B-028	Pavement Data	pavement quality and composition	ADOT		ADOT	Ali Zareh	May 2016	DL
B-029	Inspection Reports	inspection reports for structures and culverts	ADOT		ADOT	Verna Celeya	May 2016	DL
B-030	Statewide Wildlife Crash Analysis and Proposed Action Plan		ADOT	Sept. 2014	AZTEC	Justin Hoppmann	Jun-16	DB
B-031	CYMPO Title VI Plan		CYMPO	Jun 2016	CYMPO	Chris Bridges	Jun-16	DB

APPENDIX WP1-3

Existing Traffic Counts

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602329
Route: AZ-89 (set 300' n/o 3N)
Location: N of E RD 3 N

Site Ref: 1
Direction: NB
Latitude: 34.77844
Longitude: -112.45279

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 0:00	3	0	1	1	0	0	0	0	0	0	0	1	0	0	0.0%	33.3%
3/23/2016 0:15	4	0	2	1	0	0	0	0	0	1	0	0	0	0	0.0%	25.0%
3/23/2016 0:30	10	0	3	4	0	0	0	0	0	3	0	0	0	0	0.0%	30.0%
3/23/2016 0:45	4	0	4	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 1:00	2	0	1	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 1:15	2	0	0	1	0	0	0	0	0	1	0	0	0	0	0.0%	50.0%
3/23/2016 1:30	5	0	3	1	0	0	0	0	0	1	0	0	0	0	0.0%	20.0%
3/23/2016 1:45	5	0	2	3	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 2:00	6	0	1	3	0	0	0	0	0	2	0	0	0	0	0.0%	33.3%
3/23/2016 2:15	3	0	1	0	0	1	0	0	0	1	0	0	0	0	33.3%	33.3%
3/23/2016 2:30	6	0	3	1	0	0	0	0	0	2	0	0	0	0	0.0%	33.3%
3/23/2016 2:45	12	0	5	3	0	0	0	0	0	3	0	1	0	0	0.0%	33.3%
3/23/2016 3:00	5	0	1	2	0	0	0	0	0	2	0	0	0	0	0.0%	40.0%
3/23/2016 3:15	5	0	2	1	0	0	0	0	0	2	0	0	0	0	0.0%	40.0%
3/23/2016 3:30	3	0	1	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 3:45	2	0	1	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 4:00	6	0	2	2	0	0	0	0	0	1	0	1	0	0	0.0%	33.3%
3/23/2016 4:15	8	0	2	4	0	0	0	0	0	2	0	0	0	0	0.0%	25.0%
3/23/2016 4:30	13	1	5	4	0	1	0	0	0	1	0	1	0	0	7.7%	15.4%
3/23/2016 4:45	13	0	6	6	0	0	0	0	0	1	0	0	0	0	0.0%	7.7%
3/23/2016 5:00	14	0	7	6	0	0	0	0	0	0	0	1	0	0	0.0%	7.1%
3/23/2016 5:15	21	1	7	12	0	0	0	0	1	0	0	0	0	0	0.0%	4.8%
3/23/2016 5:30	34	0	14	18	0	1	0	0	0	1	0	0	0	0	2.9%	2.9%
3/23/2016 5:45	26	0	10	12	0	1	0	0	0	3	0	0	0	0	3.8%	11.5%
3/23/2016 6:00	50	0	27	22	0	1	0	0	0	0	0	0	0	0	2.0%	0.0%
3/23/2016 6:15	52	1	17	23	3	1	2	0	0	5	0	0	0	0	11.5%	9.6%
3/23/2016 6:30	61	1	24	28	4	3	0	0	0	1	0	0	0	0	11.5%	1.6%
3/23/2016 6:45	69	0	36	23	5	1	0	1	0	3	0	0	0	0	10.1%	4.3%
3/23/2016 7:00	61	0	28	25	3	3	0	0	1	1	0	0	0	0	9.8%	3.3%
3/23/2016 7:15	92	0	55	30	2	1	1	0	0	2	0	0	0	1	4.3%	3.3%
3/23/2016 7:30	73	0	39	30	2	1	0	0	0	0	0	0	0	1	4.1%	1.4%
3/23/2016 7:45	90	0	40	43	2	1	1	2	0	1	0	0	0	0	6.7%	1.1%
3/23/2016 8:00	71	0	35	29	1	0	0	0	2	2	0	1	0	1	1.4%	8.5%
3/23/2016 8:15	74	0	33	35	1	1	0	0	0	3	0	0	0	1	2.7%	5.4%
3/23/2016 8:30	67	0	35	26	0	1	0	0	0	4	0	0	0	1	1.5%	7.5%
3/23/2016 8:45	81	0	54	25	1	0	0	0	1	0	0	0	0	0	1.2%	1.2%
3/23/2016 9:00	90	0	40	44	0	2	2	1	1	0	0	0	0	0	5.6%	1.1%
3/23/2016 9:15	71	0	29	35	0	0	0	1	1	5	0	0	0	0	1.4%	8.5%
3/23/2016 9:30	77	1	30	35	3	0	0	0	3	5	0	0	0	0	3.9%	10.4%
3/23/2016 9:45	82	1	45	33	0	0	0	0	1	2	0	0	0	0	0.0%	3.7%
3/23/2016 10:00	88	0	43	38	2	0	0	0	0	5	0	0	0	0	2.3%	5.7%
3/23/2016 10:15	102	0	51	41	2	2	0	0	2	4	0	0	0	0	3.9%	5.9%
3/23/2016 10:30	87	0	39	44	0	1	0	2	1	0	0	0	0	0	3.4%	1.1%
3/23/2016 10:45	92	2	36	47	0	1	0	0	0	4	1	1	0	0	1.1%	6.5%
3/23/2016 11:00	88	4	37	39	1	2	0	0	0	4	1	0	0	0	3.4%	5.7%
3/23/2016 11:15	96	1	53	38	1	1	0	0	0	2	0	0	0	0	2.1%	2.1%
3/23/2016 11:30	101	0	48	44	0	1	2	2	0	4	0	0	0	0	5.0%	4.0%
3/23/2016 11:45	90	3	52	34	0	0	0	0	0	1	0	0	0	0	0.0%	1.1%

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602329
Route: AZ-89 (set 300' n/o 3N)
Location: N of E RD 3 N

Site Ref: 1
Direction: NB
Latitude: 34.77844
Longitude: -112.45279

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 12:00	104	1	41	54	0	1	3	1	0	3	0	0	0	0	4.8%	2.9%
3/23/2016 12:15	86	1	34	47	1	0	2	0	0	1	0	0	0	0	3.5%	1.2%
3/23/2016 12:30	97	0	47	45	0	3	0	0	1	1	0	0	0	0	3.1%	2.1%
3/23/2016 12:45	112	1	58	50	1	0	0	0	0	2	0	0	0	0	0.9%	1.8%
3/23/2016 13:00	118	1	55	55	2	0	1	0	0	4	0	0	0	0	2.5%	3.4%
3/23/2016 13:15	119	0	58	52	4	3	1	0	0	1	0	0	0	0	6.7%	0.8%
3/23/2016 13:30	120	2	63	51	3	0	0	0	0	1	0	0	0	0	2.5%	0.8%
3/23/2016 13:45	109	0	59	47	0	1	2	0	0	0	0	0	0	0	2.8%	0.0%
3/23/2016 14:00	111	1	57	46	1	0	1	1	0	4	0	0	0	0	2.7%	3.6%
3/23/2016 14:15	129	0	74	49	0	3	0	0	0	3	0	0	0	0	2.3%	2.3%
3/23/2016 14:30	132	0	71	55	1	2	1	0	1	1	0	0	0	0	3.0%	1.5%
3/23/2016 14:45	131	1	72	53	0	1	0	0	2	2	0	0	0	0	0.8%	3.1%
3/23/2016 15:00	119	2	61	48	5	2	0	0	0	1	0	0	0	0	5.9%	0.8%
3/23/2016 15:15	140	1	88	47	1	1	0	0	0	2	0	0	0	0	1.4%	1.4%
3/23/2016 15:30	140	0	83	54	0	1	0	0	0	2	0	0	0	0	0.7%	1.4%
3/23/2016 15:45	136	2	72	58	1	2	0	0	0	1	0	0	0	0	2.2%	0.7%
3/23/2016 16:00	163	1	86	72	2	1	0	0	0	1	0	0	0	0	1.8%	0.6%
3/23/2016 16:15	141	1	79	54	0	4	1	0	0	2	0	0	0	0	3.5%	1.4%
3/23/2016 16:30	163	2	87	69	1	1	0	0	0	2	0	1	0	0	1.2%	1.8%
3/23/2016 16:45	148	0	82	58	0	5	0	0	1	2	0	0	0	0	3.4%	2.0%
3/23/2016 17:00	153	0	82	62	0	2	0	2	0	4	0	1	0	0	2.6%	3.3%
3/23/2016 17:15	140	0	68	67	0	2	1	0	0	2	0	0	0	0	2.1%	1.4%
3/23/2016 17:30	154	0	88	66	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 17:45	148	1	73	72	0	1	0	0	0	1	0	0	0	0	0.7%	0.7%
3/23/2016 18:00	135	0	88	45	0	2	0	0	0	0	0	0	0	0	1.5%	0.0%
3/23/2016 18:15	119	1	60	53	1	0	0	0	0	4	0	0	0	0	0.8%	3.4%
3/23/2016 18:30	119	0	74	44	0	0	1	0	0	0	0	0	0	0	0.8%	0.0%
3/23/2016 18:45	74	0	30	43	1	0	0	0	0	0	0	0	0	0	1.4%	0.0%
3/23/2016 19:00	71	0	38	32	0	0	0	0	0	1	0	0	0	0	0.0%	1.4%
3/23/2016 19:15	79	0	50	28	0	1	0	0	0	0	0	0	0	0	1.3%	0.0%
3/23/2016 19:30	60	0	33	26	0	0	0	0	0	1	0	0	0	0	0.0%	1.7%
3/23/2016 19:45	69	0	41	26	0	0	0	0	0	2	0	0	0	0	0.0%	2.9%
3/23/2016 20:00	61	0	30	31	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 20:15	59	0	39	17	0	1	0	0	0	2	0	0	0	0	1.7%	3.4%
3/23/2016 20:30	50	0	25	24	0	0	0	0	1	0	0	0	0	0	0.0%	2.0%
3/23/2016 20:45	50	0	30	18	0	0	0	0	0	2	0	0	0	0	0.0%	4.0%
3/23/2016 21:00	42	0	28	13	0	0	0	0	0	1	0	0	0	0	0.0%	2.4%
3/23/2016 21:15	31	0	17	13	0	0	0	0	0	1	0	0	0	0	0.0%	3.2%
3/23/2016 21:30	40	0	26	14	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 21:45	39	0	23	15	0	0	0	0	0	1	0	0	0	0	0.0%	2.6%
3/23/2016 22:00	22	0	10	11	0	0	0	0	0	1	0	0	0	0	0.0%	4.5%
3/23/2016 22:15	29	0	18	11	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:30	25	0	18	7	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:45	17	0	8	8	0	0	0	0	0	1	0	0	0	0	0.0%	5.9%
3/23/2016 23:00	11	0	10	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:15	10	0	9	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:30	16	0	9	6	0	0	0	0	0	1	0	0	0	0	0.0%	6.3%
3/23/2016 23:45	12	0	8	4	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
Day Totals	6470	35	3370	2722	58	68	22	13	20	146	2	9	0	5	2.5%	2.8%

AM Peak Hr 11:15 AM
AM Peak Vol 391
AM PHF 0.940
PM Peak Hr 4:00 PM
PM Peak Vol 615
PM PHF 0.943

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602329
Route: AZ-89 (set 300' n/o 3N)
Location: N of E RD 3 N

Site Ref: 1
Direction: NB
Latitude: 34.77844
Longitude: -112.45279

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+
3/23/2016 0:00	3	0	0	0	0	0	0	0	0	0	0	2	1	0	0	0	0	0
3/23/2016 0:15	4	0	0	0	0	0	0	0	0	0	2	2	0	0	0	0	0	0
3/23/2016 0:30	10	0	0	0	0	0	0	0	1	1	0	3	4	1	0	0	0	0
3/23/2016 0:45	4	0	0	0	0	0	0	0	0	0	0	1	2	1	0	0	0	0
3/23/2016 1:00	2	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0
3/23/2016 1:15	2	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0
3/23/2016 1:30	5	0	0	0	0	0	0	0	0	0	1	2	1	1	0	0	0	0
3/23/2016 1:45	5	0	0	0	0	0	0	0	0	1	1	2	1	0	0	0	0	0
3/23/2016 2:00	6	0	0	0	0	0	0	0	0	0	3	1	0	1	1	0	0	0
3/23/2016 2:15	3	0	0	0	0	0	0	0	0	0	1	0	2	0	0	0	0	0
3/23/2016 2:30	6	0	0	0	0	0	0	0	0	1	0	4	1	0	0	0	0	0
3/23/2016 2:45	12	0	0	0	0	0	0	0	0	0	2	5	3	2	0	0	0	0
3/23/2016 3:00	5	0	0	0	0	0	0	0	0	0	1	0	1	2	1	0	0	0
3/23/2016 3:15	5	0	0	0	0	0	0	0	0	0	1	1	3	0	0	0	0	0
3/23/2016 3:30	3	0	0	0	0	0	0	0	0	0	0	1	2	0	0	0	0	0
3/23/2016 3:45	2	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0
3/23/2016 4:00	6	0	0	0	0	0	0	0	1	0	0	2	1	2	0	0	0	0
3/23/2016 4:15	8	0	0	0	0	0	0	0	0	0	0	0	2	6	0	0	0	0
3/23/2016 4:30	13	0	0	0	0	0	0	0	0	0	1	4	3	4	1	0	0	0
3/23/2016 4:45	13	0	0	0	0	0	0	0	0	0	1	4	6	2	0	0	0	0
3/23/2016 5:00	14	0	0	0	0	0	0	0	0	0	3	5	2	0	4	0	0	0
3/23/2016 5:15	21	0	0	0	0	0	0	0	0	1	4	8	5	3	0	0	0	0
3/23/2016 5:30	34	0	0	0	0	0	0	0	0	4	4	16	7	2	1	0	0	0
3/23/2016 5:45	26	0	0	0	0	0	0	0	0	2	6	11	7	0	0	0	0	0
3/23/2016 6:00	50	0	0	0	0	0	0	0	0	5	16	19	7	3	0	0	0	0
3/23/2016 6:15	52	0	0	0	0	0	0	0	0	1	14	23	11	3	0	0	0	0
3/23/2016 6:30	61	0	0	0	0	0	0	0	0	3	15	20	18	4	1	0	0	0
3/23/2016 6:45	69	0	0	0	0	0	0	0	0	3	13	27	19	7	0	0	0	0
3/23/2016 7:00	61	0	0	0	0	0	0	0	0	2	13	25	17	4	0	0	0	0
3/23/2016 7:15	92	0	0	0	0	0	0	0	0	1	17	46	24	4	0	0	0	0
3/23/2016 7:30	73	0	0	0	0	0	0	0	0	2	13	28	23	6	1	0	0	0
3/23/2016 7:45	90	0	0	0	0	0	0	0	1	6	14	37	20	12	0	0	0	0
3/23/2016 8:00	71	0	0	0	0	0	0	0	2	4	14	38	11	1	1	0	0	0
3/23/2016 8:15	74	0	0	0	0	0	0	0	0	3	23	28	16	4	0	0	0	0
3/23/2016 8:30	67	0	0	0	0	0	0	0	0	1	17	26	17	5	1	0	0	0
3/23/2016 8:45	81	0	0	0	0	0	0	0	0	9	22	32	15	3	0	0	0	0
3/23/2016 9:00	90	0	0	0	0	0	0	0	0	9	23	31	24	2	0	1	0	0
3/23/2016 9:15	71	0	0	0	0	0	0	1	2	11	15	21	15	5	1	0	0	0
3/23/2016 9:30	77	0	0	0	0	0	0	0	0	4	23	34	13	3	0	0	0	0
3/23/2016 9:45	82	0	0	0	0	0	0	0	1	14	31	24	12	0	0	0	0	0
3/23/2016 10:00	88	0	0	0	0	0	0	0	1	9	25	34	17	2	0	0	0	0
3/23/2016 10:15	102	0	0	0	0	0	0	0	1	8	29	50	12	2	0	0	0	0
3/23/2016 10:30	87	0	0	0	0	0	0	0	0	6	24	37	18	2	0	0	0	0
3/23/2016 10:45	92	0	0	0	0	0	0	0	0	9	32	35	12	4	0	0	0	0
3/23/2016 11:00	88	0	0	0	0	0	0	0	0	6	23	31	24	4	0	0	0	0
3/23/2016 11:15	96	0	0	0	0	0	0	0	1	12	22	40	20	1	0	0	0	0
3/23/2016 11:30	101	0	0	0	0	0	0	0	0	8	27	32	25	8	0	1	0	0
3/23/2016 11:45	90	0	0	0	0	0	0	0	0	3	16	46	18	6	1	0	0	0
3/23/2016 12:00	104	0	0	0	0	0	0	0	1	10	30	44	17	2	0	0	0	0
3/23/2016 12:15	86	0	0	0	0	0	0	0	1	2	35	33	12	2	1	0	0	0
3/23/2016 12:30	97	0	0	0	0	0	0	0	2	9	16	39	23	7	0	0	1	0
3/23/2016 12:45	112	0	0	0	0	0	0	0	2	6	25	51	21	4	3	0	0	0
3/23/2016 13:00	118	0	0	0	0	0	0	0	0	7	31	52	25	3	0	0	0	0
3/23/2016 13:15	119	0	0	0	0	0	0	0	0	4	29	51	27	7	1	0	0	0
3/23/2016 13:30	120	0	0	0	0	0	0	0	0	3	42	46	19	8	2	0	0	0
3/23/2016 13:45	109	0	0	0	0	0	0	0	0	9	33	46	18	3	0	0	0	0
3/23/2016 14:00	111	0	0	0	0	0	0	0	0	9	31	39	25	7	0	0	0	0
3/23/2016 14:15	129	0	0	0	0	0	0	0	2	5	45	39	36	2	0	0	0	0
3/23/2016 14:30	132	0	0	0	0	0	0	0	2	9	42	52	19	7	1	0	0	0
3/23/2016 14:45	131	0	0	0	0	0	0	0	1	13	32	53	20	12	0	0	0	0
3/23/2016 15:00	119	0	0	0	0	0	0	0	3	3	29	54	25	5	0	0	0	0
3/23/2016 15:15	140	0	0	0	0	0	0	0	0	8	44	57	27	4	0	0	0	0
3/23/2016 15:30	140	0	0	0	0	0	0	0	7	10	32	57	32	2	0	0	0	0
3/23/2016 15:45	136	0	0	0	0	0	0	0	1	5	30	67	23	10	0	0	0	0
3/23/2016 16:00	163	0	0	0	0	0	0	0	1	19	55	58	24	6	0	0	0	0
3/23/2016 16:15	141	0	0	0	0	0	0	0	2	12	37	58	28	4	0	0	0	0
3/23/2016 16:30	163	0	0	0	0	0	0	2	3	11	46	63	30	7	1	0	0	0
3/23/2016 16:45	148	0	0	0	0	0	0	0	2	9	29	76	23	8	1	0	0	0
3/23/2016 17:00	153	0	0	0	0	0	0	0	3	15	48	46	33	8	0	0	0	0
3/23/2016 17:15	140	0	0	0	0	0	0	0	0	7	38	49	37	9	0	0	0	0
3/23/2016 17:30	154	0	0	0	0	0	0	0	0	7	30	65	51	1	0	0	0	0
3/23/2016 17:45	148	0	0	0	0	0	0	0	0	0	28	75	34	10	1	0	0	0
3/23/2016 18:00	135	0	0	0	0	0	0	0	0	4	22	64	35	9	1	0	0	0
3/23/2016 18:15	119	0	0	0	0	0	0	0	1	3	34	45	25	11	0	0	0	0
3/23/2016 18:30	119	0	0	0	0	0	0	0	0	4	32	56	16	11	0	0	0	0
3/23/2016 18:45	74	0	0	0	0	0	0	0	0	4	15	30	17	7	1	0	0	0
3/23/2016 19:00	71	0	0	0	0	0	0	0	1	5	17	30	15	3	0	0	0	0
3/23/2016 19:15	79	0	0	0	0	0	0	0	1	5	26	26	20	1	0	0	0	0
3/23/2016 19:30	60	0	0	0	0	0	0	0	0	2	19	23	11	5	0	0	0	0
3/23/2016 19:45	69	0	0	0	0	0	0	0	0	2	21	29	13	4	0	0	0	0
3/23/2016 20:00	61	0	0	0	0	0	0	0	0	3	18	24	14	2	0	0	0	0
3/23/2016 20:15	59	0	0	0	0	0	0	0	0	3	12	24	15	4	1	0	0	0
3/23/2016 20:30	50	0	0	0	0	0	0	0	0	1	16	17	14	2	0	0	0	0
3/23/2016 20:45	50	0	0	0	0	0	0	0	0	1	7	20	16	4	2	0	0	0
3/23/2016 21:00	42	0	0	0	0	0	0	0	0	6	4	13	16	3	0	0	0	0

Traffic Research & Analysis, Inc.
 3844 East Indian School Road
 Phoenix, AZ 85018
 (602) 840-1500

Client: Burgess & Niple, Inc.
 File Number: 1602329
 Route: AZ-89 (set 300' n/o 3N)
 Location: N of E RD 3 N

Site Ref: 1
 Direction: NB
 Latitude: 34.77844
 Longitude: -112.45279

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+
3/23/2016 21:15	31	0	0	0	0	0	0	0	0	2	6	12	8	3	0	0	0	0
3/23/2016 21:30	40	0	0	0	0	0	0	0	0	4	9	15	11	1	0	0	0	0
3/23/2016 21:45	39	0	0	0	0	0	0	0	0	5	2	14	17	1	0	0	0	0
3/23/2016 22:00	22	0	0	0	0	0	0	0	0	2	3	11	6	0	0	0	0	0
3/23/2016 22:15	29	0	0	0	0	0	0	0	1	4	8	6	5	5	0	0	0	0
3/23/2016 22:30	25	0	0	0	0	0	0	0	0	1	1	7	14	2	0	0	0	0
3/23/2016 22:45	17	0	0	0	0	0	0	0	0	0	3	6	4	2	2	0	0	0
3/23/2016 23:00	11	0	0	0	0	0	0	0	0	1	2	1	6	1	0	0	0	0
3/23/2016 23:15	10	0	0	0	0	0	0	0	0	0	1	5	4	0	0	0	0	0
3/23/2016 23:30	16	0	0	0	0	0	0	0	0	0	3	6	6	1	0	0	0	0
3/23/2016 23:45	12	0	0	0	0	0	0	0	0	0	2	8	1	1	0	0	0	0
Day Totals	6470	0	0	0	0	0	0	3	48	404	1633	2601	1402	344	32	2	1	0

AM Peak Hr	11:15 AM	Average Speed	52.2	Pct > 25 mph	100%
AM Peak Vol	391	Median Speed	52.2	Pct > 30 mph	100%
AM PHF	0.940	85th Pct Speed	57.8	Pct > 35 mph	100%
PM Peak Hr	4:00 PM	95th Pct Speed	60.7	Pct > 40 mph	99%
PM Peak Vol	615	Pace Speed	45	Pct > 45 mph	93%
PM PHF	0.943	Percent in Pace	64.8%	Pct > 50 mph	68%
		Speed Limit	35		
		Percent Speedin	100.0%		

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602330
Route: AZ-89 (set 300' n/o 3N)
Location: N of E RD 3 N

Site Ref: 1
Direction: SB
Latitude: 34.77844
Longitude: -112.45279

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 0:00	6	0	4	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 0:15	2	0	1	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 0:30	8	0	6	1	1	0	0	0	0	0	0	0	0	0	12.5%	0.0%
3/23/2016 0:45	4	0	3	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 1:00	2	0	1	0	0	0	0	0	0	0	0	1	0	0	0.0%	50.0%
3/23/2016 1:15	1	0	1	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 1:30	10	1	3	4	0	0	0	0	0	2	0	0	0	0	0.0%	20.0%
3/23/2016 1:45	5	0	2	1	0	0	0	0	0	2	0	0	0	0	0.0%	40.0%
3/23/2016 2:00	9	0	4	4	0	0	0	0	0	1	0	0	0	0	0.0%	11.1%
3/23/2016 2:15	9	0	5	3	0	0	0	0	0	1	0	0	0	0	0.0%	11.1%
3/23/2016 2:30	8	0	4	3	0	0	0	0	0	1	0	0	0	0	0.0%	12.5%
3/23/2016 2:45	7	0	1	5	0	0	0	0	0	1	0	0	0	0	0.0%	14.3%
3/23/2016 3:00	5	0	1	2	0	0	0	0	0	2	0	0	0	0	0.0%	40.0%
3/23/2016 3:15	12	0	9	2	0	0	0	0	0	1	0	0	0	0	0.0%	8.3%
3/23/2016 3:30	8	0	5	1	0	0	0	0	0	2	0	0	0	0	0.0%	25.0%
3/23/2016 3:45	6	0	2	2	0	0	0	0	0	2	0	0	0	0	0.0%	33.3%
3/23/2016 4:00	16	0	8	7	0	0	0	0	0	0	0	1	0	0	0.0%	6.3%
3/23/2016 4:15	22	0	11	7	0	0	0	0	0	4	0	0	0	0	0.0%	18.2%
3/23/2016 4:30	19	1	11	5	0	0	1	0	0	0	0	1	0	0	5.3%	5.3%
3/23/2016 4:45	16	0	7	6	0	0	0	0	0	3	0	0	0	0	0.0%	18.8%
3/23/2016 5:00	34	0	17	16	0	0	0	0	0	0	0	1	0	0	0.0%	2.9%
3/23/2016 5:15	36	0	21	13	0	0	0	0	0	2	0	0	0	0	0.0%	5.6%
3/23/2016 5:30	55	0	27	24	1	0	0	0	0	3	0	0	0	0	1.8%	5.5%
3/23/2016 5:45	75	0	39	32	0	1	0	0	0	2	0	1	0	0	1.3%	4.0%
3/23/2016 6:00	68	0	38	28	1	0	1	0	0	0	0	0	0	0	2.9%	0.0%
3/23/2016 6:15	102	0	63	38	0	1	0	0	0	0	0	0	0	0	1.0%	0.0%
3/23/2016 6:30	120	0	60	56	0	1	1	0	0	2	0	0	0	0	1.7%	1.7%
3/23/2016 6:45	129	0	74	50	0	1	0	0	0	3	0	1	0	0	0.8%	3.1%
3/23/2016 7:00	157	0	96	55	3	0	1	0	0	1	0	1	0	0	2.5%	1.3%
3/23/2016 7:15	157	1	81	70	1	1	0	0	0	2	0	0	0	1	1.3%	1.9%
3/23/2016 7:30	115	1	64	49	0	0	0	0	0	1	0	0	0	0	0.0%	0.9%
3/23/2016 7:45	132	1	70	57	0	1	0	0	0	3	0	0	0	0	0.8%	2.3%
3/23/2016 8:00	125	1	64	49	2	4	1	0	0	4	0	0	0	0	5.6%	3.2%
3/23/2016 8:15	130	0	77	45	2	0	0	1	1	3	0	1	0	0	2.3%	3.8%
3/23/2016 8:30	103	0	51	44	3	0	0	0	0	5	0	0	0	0	2.9%	4.9%
3/23/2016 8:45	108	0	56	47	0	1	0	0	0	3	0	0	0	1	0.9%	3.7%
3/23/2016 9:00	105	0	63	36	0	0	0	1	2	2	1	0	0	0	1.0%	4.8%
3/23/2016 9:15	122	1	65	45	2	1	2	0	0	6	0	0	0	0	4.1%	4.9%
3/23/2016 9:30	96	0	48	43	0	0	1	0	1	3	0	0	0	0	1.0%	4.2%
3/23/2016 9:45	119	0	70	44	1	0	1	0	0	2	0	1	0	0	1.7%	2.5%
3/23/2016 10:00	97	0	49	44	1	0	1	0	1	1	0	0	0	0	2.1%	2.1%
3/23/2016 10:15	99	0	57	36	0	3	1	0	0	2	0	0	0	0	4.0%	2.0%
3/23/2016 10:30	132	0	69	53	1	2	2	0	1	3	0	0	0	1	3.8%	3.8%
3/23/2016 10:45	96	0	46	44	1	0	1	1	1	2	0	0	0	0	3.1%	3.1%
3/23/2016 11:00	106	0	62	38	0	3	2	0	0	1	0	0	0	0	4.7%	0.9%
3/23/2016 11:15	131	0	53	67	1	3	1	1	1	4	0	0	0	0	4.6%	3.8%
3/23/2016 11:30	95	0	44	43	4	2	0	0	0	1	1	0	0	0	6.3%	2.1%
3/23/2016 11:45	103	1	46	52	0	0	1	1	0	2	0	0	0	0	1.9%	1.9%

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602330
Route: AZ-89 (set 300' n/o 3N)
Location: N of E RD 3 N

Site Ref: 1
Direction: SB
Latitude: 34.77844
Longitude: -112.45279

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 12:00	113	1	58	50	1	1	0	1	0	0	0	0	0	1	2.7%	0.9%
3/23/2016 12:15	102	1	56	34	1	0	2	0	0	4	1	3	0	0	2.9%	7.8%
3/23/2016 12:30	121	1	66	50	2	0	0	0	0	1	0	1	0	0	1.7%	1.7%
3/23/2016 12:45	121	1	62	53	0	1	0	0	1	3	0	0	0	0	0.8%	3.3%
3/23/2016 13:00	92	0	49	40	0	2	1	0	0	0	0	0	0	0	3.3%	0.0%
3/23/2016 13:15	80	0	49	28	2	0	0	0	0	1	0	0	0	0	2.5%	1.3%
3/23/2016 13:30	86	0	50	31	2	0	1	0	0	2	0	0	0	0	3.5%	2.3%
3/23/2016 13:45	117	1	65	42	5	1	0	0	3	0	0	0	0	0	5.1%	2.6%
3/23/2016 14:00	80	0	47	28	1	1	0	0	0	1	1	0	0	1	2.5%	3.8%
3/23/2016 14:15	104	1	55	43	1	2	0	0	0	2	0	0	0	0	2.9%	1.9%
3/23/2016 14:30	99	0	61	34	2	0	0	0	0	2	0	0	0	0	2.0%	2.0%
3/23/2016 14:45	83	1	57	24	0	0	0	0	1	0	0	0	0	0	0.0%	1.2%
3/23/2016 15:00	98	0	48	44	2	1	0	0	0	3	0	0	0	0	3.1%	3.1%
3/23/2016 15:15	117	1	63	49	2	0	1	0	0	1	0	0	0	0	2.6%	0.9%
3/23/2016 15:30	136	0	75	52	5	2	1	0	0	0	0	0	0	1	5.9%	0.7%
3/23/2016 15:45	117	3	56	53	2	0	0	0	2	0	0	1	0	0	1.7%	2.6%
3/23/2016 16:00	119	1	66	45	1	1	1	0	1	1	0	1	0	1	2.5%	3.4%
3/23/2016 16:15	116	0	62	46	1	3	0	0	0	4	0	0	0	0	3.4%	3.4%
3/23/2016 16:30	114	0	62	47	0	2	0	0	1	2	0	0	0	0	1.8%	2.6%
3/23/2016 16:45	120	0	78	38	0	1	0	0	0	3	0	0	0	0	0.8%	2.5%
3/23/2016 17:00	109	0	66	40	0	0	1	0	1	1	0	0	0	0	0.9%	1.8%
3/23/2016 17:15	96	0	52	43	0	0	0	0	0	1	0	0	0	0	0.0%	1.0%
3/23/2016 17:30	93	1	47	43	0	0	1	0	0	1	0	0	0	0	1.1%	1.1%
3/23/2016 17:45	76	1	42	31	0	0	1	0	0	1	0	0	0	0	1.3%	1.3%
3/23/2016 18:00	79	1	48	26	0	3	0	0	0	0	0	1	0	0	3.8%	1.3%
3/23/2016 18:15	58	0	32	25	0	0	0	0	0	0	0	1	0	0	0.0%	1.7%
3/23/2016 18:30	71	0	37	30	1	1	0	0	0	2	0	0	0	0	2.8%	2.8%
3/23/2016 18:45	66	0	36	29	0	0	0	0	1	0	0	0	0	0	0.0%	1.5%
3/23/2016 19:00	59	1	30	26	0	0	0	0	0	1	0	0	1	0	0.0%	3.4%
3/23/2016 19:15	53	0	36	14	0	0	1	0	0	1	0	0	0	1	1.9%	3.8%
3/23/2016 19:30	50	0	26	22	0	0	0	0	0	1	1	0	0	0	0.0%	4.0%
3/23/2016 19:45	74	0	45	28	0	0	0	0	0	1	0	0	0	0	0.0%	1.4%
3/23/2016 20:00	43	0	23	16	1	1	0	0	0	1	0	1	0	0	4.7%	4.7%
3/23/2016 20:15	36	0	24	11	0	0	0	0	0	1	0	0	0	0	0.0%	2.8%
3/23/2016 20:30	33	0	15	17	0	0	0	0	0	1	0	0	0	0	0.0%	3.0%
3/23/2016 20:45	23	0	12	11	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 21:00	32	0	21	11	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 21:15	29	0	19	9	0	0	0	0	0	1	0	0	0	0	0.0%	3.4%
3/23/2016 21:30	14	0	8	1	0	0	0	0	0	4	0	1	0	0	0.0%	35.7%
3/23/2016 21:45	11	0	9	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:00	9	0	6	3	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:15	10	0	7	2	0	0	0	0	0	1	0	0	0	0	0.0%	10.0%
3/23/2016 22:30	10	0	7	3	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:45	11	0	6	4	0	1	0	0	0	0	0	0	0	0	9.1%	0.0%
3/23/2016 23:00	10	0	6	4	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:15	8	0	5	3	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:30	5	0	4	0	0	0	0	0	0	1	0	0	0	0	0.0%	20.0%
3/23/2016 23:45	6	0	2	3	0	0	0	0	0	1	0	0	0	0	0.0%	16.7%
Day Totals	6431	24	3515	2563	57	49	29	6	19	136	5	19	1	8	2.2%	2.9%

AM Peak Hr **6:30 AM**
AM Peak Vol **563**
AM PHF **0.896**
PM Peak Hr **3:15 PM**
PM Peak Vol **489**
PM PHF **0.899**

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602330
Route: AZ-89 (set 300' n/o 3N)
Location: N of E RD 3 N

Site Ref: 1
Direction: SB
Latitude: 34.77844
Longitude: -112.45279

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+
3/23/2016 0:00	6	0	0	0	0	0	0	0	1	1	2	1	1	0	0	0	0	0
3/23/2016 0:15	2	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0	0
3/23/2016 0:30	8	0	0	0	0	0	0	1	2	1	3	1	0	0	0	0	0	0
3/23/2016 0:45	4	0	0	0	0	0	0	0	1	0	1	1	1	0	0	0	0	0
3/23/2016 1:00	2	0	0	0	0	0	0	0	0	0	1	0	1	0	0	0	0	0
3/23/2016 1:15	1	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0	0
3/23/2016 1:30	10	0	0	0	0	0	1	0	1	2	5	0	1	0	0	0	0	0
3/23/2016 1:45	5	0	0	0	0	0	0	0	2	2	1	0	0	0	0	0	0	0
3/23/2016 2:00	9	0	0	0	0	0	0	0	2	2	3	1	1	0	0	0	0	0
3/23/2016 2:15	9	0	0	0	0	0	0	0	0	6	3	0	0	0	0	0	0	0
3/23/2016 2:30	8	0	0	0	0	0	0	0	2	4	0	2	0	0	0	0	0	0
3/23/2016 2:45	7	0	0	0	0	0	0	0	0	3	2	1	1	0	0	0	0	0
3/23/2016 3:00	5	0	0	0	0	0	0	0	0	3	1	1	0	0	0	0	0	0
3/23/2016 3:15	12	0	0	0	0	0	0	2	1	4	3	2	0	0	0	0	0	0
3/23/2016 3:30	8	0	0	0	0	0	0	0	2	3	2	0	1	0	0	0	0	0
3/23/2016 3:45	6	0	0	0	0	0	0	0	0	2	2	0	2	0	0	0	0	0
3/23/2016 4:00	16	0	0	0	0	0	0	0	1	2	6	5	1	0	0	1	0	0
3/23/2016 4:15	22	0	0	0	0	0	0	0	5	6	5	3	3	0	0	0	0	0
3/23/2016 4:30	19	0	0	0	0	0	0	0	0	7	8	2	1	1	0	0	0	0
3/23/2016 4:45	16	0	0	0	0	0	0	0	3	4	4	2	2	0	1	0	0	0
3/23/2016 5:00	34	0	0	0	0	0	0	0	1	10	15	5	3	0	0	0	0	0
3/23/2016 5:15	36	0	0	0	0	0	0	3	7	9	6	8	2	0	1	0	0	0
3/23/2016 5:30	55	0	0	0	0	0	0	0	5	17	20	7	6	0	0	0	0	0
3/23/2016 5:45	75	0	0	0	0	0	0	0	11	20	28	13	3	0	0	0	0	0
3/23/2016 6:00	68	0	0	0	0	0	0	1	6	21	21	16	3	0	0	0	0	0
3/23/2016 6:15	102	0	0	0	0	0	0	2	16	17	46	20	1	0	0	0	0	0
3/23/2016 6:30	120	0	0	0	0	0	0	0	5	14	56	42	3	0	0	0	0	0
3/23/2016 6:45	129	0	0	0	0	0	0	0	12	40	60	16	1	0	0	0	0	0
3/23/2016 7:00	157	0	0	0	0	0	0	11	18	52	58	14	4	0	0	0	0	0
3/23/2016 7:15	157	0	0	0	0	0	4	4	10	40	74	24	1	0	0	0	0	0
3/23/2016 7:30	115	0	0	0	0	0	0	1	10	31	30	33	10	0	0	0	0	0
3/23/2016 7:45	132	0	0	0	0	0	0	0	10	44	50	22	4	2	0	0	0	0
3/23/2016 8:00	125	0	0	0	0	0	0	2	17	41	38	20	5	2	0	0	0	0
3/23/2016 8:15	130	0	0	0	0	0	7	14	17	38	27	20	7	0	0	0	0	0
3/23/2016 8:30	103	0	0	0	0	0	0	0	5	40	39	17	2	0	0	0	0	0
3/23/2016 8:45	108	0	0	0	0	0	0	2	14	39	31	17	5	0	0	0	0	0
3/23/2016 9:00	105	0	0	0	0	0	0	0	14	22	29	32	8	0	0	0	0	0
3/23/2016 9:15	122	0	0	0	0	0	0	3	38	35	36	6	4	0	0	0	0	0
3/23/2016 9:30	96	0	0	0	0	0	4	7	11	34	30	9	1	0	0	0	0	0
3/23/2016 9:45	119	0	0	0	0	0	0	2	13	38	45	18	3	0	0	0	0	0
3/23/2016 10:00	97	0	0	0	0	0	0	0	5	32	35	24	1	0	0	0	0	0
3/23/2016 10:15	99	0	0	0	0	0	0	6	20	32	27	13	1	0	0	0	0	0
3/23/2016 10:30	132	0	0	0	0	0	0	1	20	41	46	20	4	0	0	0	0	0
3/23/2016 10:45	96	0	0	0	0	0	0	1	5	32	37	17	3	1	0	0	0	0
3/23/2016 11:00	106	0	0	0	0	0	0	0	7	30	49	16	4	0	0	0	0	0
3/23/2016 11:15	131	0	0	0	0	0	3	13	41	43	22	8	1	0	0	0	0	0
3/23/2016 11:30	95	0	0	0	0	0	0	3	14	36	25	16	1	0	0	0	0	0
3/23/2016 11:45	103	0	0	0	0	0	0	3	18	43	29	8	1	1	0	0	0	0
3/23/2016 12:00	113	0	0	0	0	0	0	2	14	38	46	12	1	0	0	0	0	0
3/23/2016 12:15	102	0	0	0	0	0	12	7	17	35	25	3	2	1	0	0	0	0
3/23/2016 12:30	121	0	0	0	0	0	0	3	10	51	47	10	0	0	0	0	0	0
3/23/2016 12:45	121	0	0	0	0	0	0	3	19	43	41	11	4	0	0	0	0	0
3/23/2016 13:00	92	0	0	0	0	0	0	0	9	25	42	14	2	0	0	0	0	0
3/23/2016 13:15	80	0	0	0	0	0	0	0	6	33	24	15	1	1	0	0	0	0
3/23/2016 13:30	86	0	0	0	0	0	0	1	8	49	17	8	3	0	0	0	0	0
3/23/2016 13:45	117	0	0	0	0	0	0	3	17	48	32	16	1	0	0	0	0	0
3/23/2016 14:00	80	0	0	0	0	0	0	1	5	27	32	14	1	0	0	0	0	0
3/23/2016 14:15	104	0	0	0	0	0	0	3	6	27	42	21	4	1	0	0	0	0
3/23/2016 14:30	99	0	0	0	0	0	1	1	6	27	36	26	2	0	0	0	0	0
3/23/2016 14:45	83	0	0	0	0	0	0	0	14	20	33	10	4	2	0	0	0	0
3/23/2016 15:00	98	0	0	0	0	0	1	0	10	27	29	27	3	1	0	0	0	0
3/23/2016 15:15	117	0	0	0	0	0	0	0	2	45	43	23	4	0	0	0	0	0
3/23/2016 15:30	136	0	0	0	0	1	2	12	25	36	38	22	0	0	0	0	0	0
3/23/2016 15:45	117	0	0	0	0	0	0	0	24	29	42	17	5	0	0	0	0	0
3/23/2016 16:00	119	0	0	0	0	0	0	2	14	33	51	16	2	1	0	0	0	0
3/23/2016 16:15	116	0	0	0	0	0	0	3	15	36	42	19	1	0	0	0	0	0
3/23/2016 16:30	114	0	0	0	0	0	0	0	5	32	46	24	5	2	0	0	0	0
3/23/2016 16:45	120	0	0	0	0	0	0	0	16	43	36	18	6	1	0	0	0	0
3/23/2016 17:00	109	0	0	0	0	0	0	0	3	27	44	25	9	1	0	0	0	0
3/23/2016 17:15	96	0	0	0	0	0	0	1	7	18	37	29	3	1	0	0	0	0
3/23/2016 17:30	93	0	0	0	0	0	0	0	2	28	37	19	6	1	0	0	0	0
3/23/2016 17:45	76	0	0	0	0	0	0	0	3	4	29	27	12	1	0	0	0	0
3/23/2016 18:00	79	0	0	0	0	0	0	1	7	18	19	29	5	0	0	0	0	0
3/23/2016 18:15	58	0	0	0	0	0	0	0	2	3	37	14	2	0	0	0	0	0
3/23/2016 18:30	71	0	0	0	0	0	0	0	1	20	20	23	5	2	0	0	0	0
3/23/2016 18:45	66	0	0	0	0	0	0	0	6	14	22	20	3	1	0	0	0	0
3/23/2016 19:00	59	0	0	0	0	0	3	7	7	21	13	6	2	0	0	0	0	0
3/23/2016 19:15	53	0	0	0	0	0	0	4	5	26	11	6	1	0	0	0	0	0
3/23/2016 19:30	50	0	0	0	0	0	0	3	10	11	20	6	0	0	0	0	0	0
3/23/2016 19:45	74	0	0	0	0	0	0	4	20	24	17	9	0	0	0	0	0	0
3/23/2016 20:00	43	0	0	0	0	0	0	0	5	15	18	4	1	0	0	0	0	0
3/23/2016 20:15	36	0	0	0	0	0	0	0	13	13	8	2	0	0	0	0	0	0
3/23/2016 20:30	33	0	0	0	0	0	0	1	3	15	7	5	2	0	0	0	0	0
3/23/2016 20:45	23	0	0	0	0	0	0	0	1	6	9	6	1	0	0	0	0	0
3/23/2016 21:00	32	0	0	0	0	0	0	0	4	15	11	2	0	0	0	0	0	0

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602330
Route: AZ-89 (set 300' n/o 3N)
Location: N of E RD 3 N

Site Ref: 1
Direction: SB
Latitude: 34.77844
Longitude: -112.45279

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+
3/23/2016 21:15	29	0	0	0	0	0	0	0	4	11	8	4	2	0	0	0	0	0
3/23/2016 21:30	14	0	0	0	0	0	0	2	6	3	3	0	0	0	0	0	0	0
3/23/2016 21:45	11	0	0	0	0	0	0	1	0	5	1	2	1	0	1	0	0	0
3/23/2016 22:00	9	0	0	0	0	0	0	1	3	1	3	0	1	0	0	0	0	0
3/23/2016 22:15	10	0	0	0	0	0	0	2	2	2	3	1	0	0	0	0	0	0
3/23/2016 22:30	10	0	0	0	0	0	0	0	0	2	5	2	1	0	0	0	0	0
3/23/2016 22:45	11	0	0	0	0	0	0	0	0	6	3	2	0	0	0	0	0	0
3/23/2016 23:00	10	0	0	0	0	0	0	1	0	3	1	2	3	0	0	0	0	0
3/23/2016 23:15	8	0	0	0	0	0	0	0	2	3	2	1	0	0	0	0	0	0
3/23/2016 23:30	5	0	0	0	0	0	0	0	0	3	1	1	0	0	0	0	0	0
3/23/2016 23:45	6	0	0	0	0	0	0	1	1	2	0	1	1	0	0	0	0	0
Day Totals	6431	0	0	0	0	1	38	152	753	1967	2195	1077	220	24	3	1	0	0
AM Peak Hr	6:30 AM	Average Speed										45.6	Pct > 25 mph				100%	
AM Peak Vol	563	Median Speed										45.6	Pct > 30 mph				99%	
AM PHF	0.896	85th Pct Speed										51.5	Pct > 35 mph				97%	
PM Peak Hr	3:15 PM	95th Pct Speed										54.7	Pct > 40 mph				85%	
PM Peak Vol	489	Pace Speed										40	Pct > 45 mph				55%	
PM PHF	0.899	Percent in Pace										64.1%	Pct > 50 mph				21%	
		Speed Limit										35						
		Percent Speedin										97.0%						

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602331
Route: AZ-89
Location: Btwn BALD EAGLE TRAIL & ROLLING HILLS RD

Site Ref: 2
Direction: NB
Latitude: 34.85875
Longitude: -112.46866

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 0:00	6	0	4	1	0	0	0	0	0	0	0	1	0	0	0.0%	16.7%
3/23/2016 0:15	2	0	2	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 0:30	9	0	4	1	0	0	0	0	0	4	0	0	0	0	0.0%	44.4%
3/23/2016 0:45	5	0	4	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 1:00	3	0	3	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 1:15	4	0	1	2	0	0	0	0	0	1	0	0	0	0	0.0%	25.0%
3/23/2016 1:30	1	0	0	0	0	0	0	0	0	1	0	0	0	0	0.0%	100.0%
3/23/2016 1:45	3	0	3	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 2:00	5	0	0	3	0	0	0	0	0	1	0	0	0	1	0.0%	40.0%
3/23/2016 2:15	3	0	1	1	0	0	0	0	0	1	0	0	0	0	0.0%	33.3%
3/23/2016 2:30	4	0	1	1	0	0	0	0	0	2	0	0	0	0	0.0%	50.0%
3/23/2016 2:45	8	0	2	2	0	0	0	0	0	3	0	1	0	0	0.0%	50.0%
3/23/2016 3:00	5	0	4	0	0	0	0	0	0	1	0	0	0	0	0.0%	20.0%
3/23/2016 3:15	3	0	1	0	0	0	0	0	0	2	0	0	0	0	0.0%	66.7%
3/23/2016 3:30	6	0	2	3	0	0	0	0	0	1	0	0	0	0	0.0%	16.7%
3/23/2016 3:45	3	0	1	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 4:00	7	0	4	1	0	0	0	0	0	1	0	1	0	0	0.0%	28.6%
3/23/2016 4:15	4	0	1	2	0	0	0	0	0	1	0	0	0	0	0.0%	25.0%
3/23/2016 4:30	8	0	4	2	0	1	0	0	0	1	0	0	0	0	12.5%	12.5%
3/23/2016 4:45	14	0	7	5	0	0	0	0	0	1	0	1	0	0	0.0%	14.3%
3/23/2016 5:00	15	0	8	4	0	0	0	0	1	1	0	1	0	0	0.0%	20.0%
3/23/2016 5:15	19	1	8	9	0	0	0	0	1	0	0	0	0	0	0.0%	5.3%
3/23/2016 5:30	24	0	7	15	0	0	0	1	0	1	0	0	0	0	4.2%	4.2%
3/23/2016 5:45	16	0	6	8	0	0	0	0	0	2	0	0	0	0	0.0%	12.5%
3/23/2016 6:00	32	0	17	12	0	0	0	0	0	3	0	0	0	0	0.0%	9.4%
3/23/2016 6:15	44	0	21	18	1	0	0	0	0	4	0	0	0	0	2.3%	9.1%
3/23/2016 6:30	41	1	16	19	1	0	2	0	0	2	0	0	0	0	7.3%	4.9%
3/23/2016 6:45	43	0	22	14	2	0	0	0	0	4	0	0	1	0	4.7%	11.6%
3/23/2016 7:00	39	0	21	10	0	2	0	0	1	5	0	0	0	0	5.1%	15.4%
3/23/2016 7:15	56	0	32	17	3	0	0	0	0	0	4	0	0	0	5.4%	7.1%
3/23/2016 7:30	66	0	43	17	1	1	0	0	0	1	3	0	0	0	3.0%	6.1%
3/23/2016 7:45	38	0	22	14	0	0	0	0	0	2	0	0	0	0	0.0%	5.3%
3/23/2016 8:00	50	0	29	15	0	0	1	0	3	2	0	0	0	0	2.0%	10.0%
3/23/2016 8:15	49	0	25	14	0	1	0	1	0	3	4	1	0	0	4.1%	16.3%
3/23/2016 8:30	30	0	14	12	0	0	0	0	0	3	1	0	0	0	0.0%	13.3%
3/23/2016 8:45	57	0	43	12	0	0	1	0	0	1	0	0	0	0	1.8%	1.8%
3/23/2016 9:00	66	0	42	20	0	4	0	0	0	0	0	0	0	0	6.1%	0.0%
3/23/2016 9:15	51	0	28	11	0	0	2	0	0	5	5	0	0	0	3.9%	19.6%
3/23/2016 9:30	52	0	24	20	0	1	1	0	2	3	1	0	0	0	3.8%	11.5%
3/23/2016 9:45	62	0	39	19	0	0	1	0	1	2	0	0	0	0	1.6%	4.8%
3/23/2016 10:00	58	0	31	19	1	1	0	0	1	5	0	0	0	0	3.4%	10.3%
3/23/2016 10:15	70	0	38	22	1	0	0	0	1	1	6	0	0	1	1.4%	12.9%
3/23/2016 10:30	63	0	34	27	1	0	0	0	1	0	0	0	0	0	1.6%	1.6%
3/23/2016 10:45	54	0	34	18	0	1	0	0	0	1	0	0	0	0	1.9%	1.9%
3/23/2016 11:00	71	1	37	23	2	2	0	0	0	4	1	1	0	0	5.6%	8.5%
3/23/2016 11:15	79	2	43	22	1	1	1	0	2	2	5	0	0	0	3.8%	11.4%
3/23/2016 11:30	70	0	37	29	0	0	0	0	0	3	1	0	0	0	0.0%	5.7%
3/23/2016 11:45	59	2	46	10	0	0	0	0	0	1	0	0	0	0	0.0%	1.7%

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602331
Route: AZ-89
Location: Btwn BALD EAGLE TRAIL & ROLLING HILLS RD

Site Ref: 2
Direction: NB
Latitude: 34.85875
Longitude: -112.46866

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 12:00	74	1	46	25	0	0	0	0	0	1	1	0	0	0	0.0%	2.7%
3/23/2016 12:15	68	0	44	14	0	0	0	1	0	4	4	0	1	0	1.5%	13.2%
3/23/2016 12:30	55	0	34	19	0	0	1	0	0	0	1	0	0	0	1.8%	1.8%
3/23/2016 12:45	72	1	49	19	1	0	1	0	0	0	0	0	0	1	2.8%	1.4%
3/23/2016 13:00	87	1	53	27	0	1	0	0	0	3	2	0	0	0	1.1%	5.7%
3/23/2016 13:15	89	0	48	28	4	1	1	0	0	3	3	0	1	0	6.7%	7.9%
3/23/2016 13:30	74	1	47	20	4	0	0	0	0	2	0	0	0	0	5.4%	2.7%
3/23/2016 13:45	76	1	46	24	0	1	2	0	0	1	1	0	0	0	3.9%	2.6%
3/23/2016 14:00	74	1	51	17	2	0	0	0	0	3	0	0	0	0	2.7%	4.1%
3/23/2016 14:15	84	0	56	19	0	0	1	0	0	3	4	0	0	1	1.2%	9.5%
3/23/2016 14:30	92	0	62	25	0	2	0	0	1	1	1	0	0	0	2.2%	3.3%
3/23/2016 14:45	100	0	61	35	1	0	0	0	1	2	0	0	0	0	1.0%	3.0%
3/23/2016 15:00	74	0	47	26	0	0	0	0	0	1	0	0	0	0	0.0%	1.4%
3/23/2016 15:15	94	0	59	23	5	0	0	1	1	4	1	0	0	0	6.4%	6.4%
3/23/2016 15:30	98	1	58	38	0	0	0	0	0	1	0	0	0	0	0.0%	1.0%
3/23/2016 15:45	88	0	63	22	1	0	0	0	0	2	0	0	0	0	1.1%	2.3%
3/23/2016 16:00	125	0	82	39	2	0	0	0	0	2	0	0	0	0	1.6%	1.6%
3/23/2016 16:15	98	0	61	35	0	0	0	0	0	2	0	0	0	0	0.0%	2.0%
3/23/2016 16:30	118	0	73	41	1	0	0	0	2	0	0	1	0	0	0.8%	2.5%
3/23/2016 16:45	105	0	71	31	0	0	0	0	0	2	0	1	0	0	0.0%	2.9%
3/23/2016 17:00	127	0	83	43	0	0	0	0	0	1	0	0	0	0	0.0%	0.8%
3/23/2016 17:15	116	0	65	46	1	1	0	0	0	3	0	0	0	0	1.7%	2.6%
3/23/2016 17:30	109	0	66	38	0	2	1	0	1	1	0	0	0	0	2.8%	1.8%
3/23/2016 17:45	112	0	74	37	0	0	0	0	0	1	0	0	0	0	0.0%	0.9%
3/23/2016 18:00	84	0	60	23	0	0	0	0	0	1	0	0	0	0	0.0%	1.2%
3/23/2016 18:15	83	0	53	29	0	0	0	0	0	1	0	0	0	0	0.0%	1.2%
3/23/2016 18:30	84	0	49	33	0	0	1	0	0	0	0	0	0	1	1.2%	1.2%
3/23/2016 18:45	72	0	45	26	1	0	0	0	0	0	0	0	0	0	1.4%	0.0%
3/23/2016 19:00	47	0	31	15	0	0	0	0	0	1	0	0	0	0	0.0%	2.1%
3/23/2016 19:15	53	0	37	16	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 19:30	47	0	33	12	0	1	0	0	0	1	0	0	0	0	2.1%	2.1%
3/23/2016 19:45	56	0	38	18	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 20:00	52	0	36	14	0	0	0	0	0	2	0	0	0	0	0.0%	3.8%
3/23/2016 20:15	44	0	31	13	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 20:30	34	0	19	13	0	0	0	0	0	2	0	0	0	0	0.0%	5.9%
3/23/2016 20:45	41	0	31	8	0	0	0	0	0	2	0	0	0	0	0.0%	4.9%
3/23/2016 21:00	37	0	29	8	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 21:15	40	0	32	7	0	0	0	0	0	1	0	0	0	0	0.0%	2.5%
3/23/2016 21:30	35	0	25	9	0	0	0	0	0	1	0	0	0	0	0.0%	2.9%
3/23/2016 21:45	26	0	20	5	0	0	0	0	0	1	0	0	0	0	0.0%	3.8%
3/23/2016 22:00	14	0	6	8	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:15	25	0	12	12	0	0	0	0	0	1	0	0	0	0	0.0%	4.0%
3/23/2016 22:30	18	0	16	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:45	13	0	9	3	0	0	0	0	0	1	0	0	0	0	0.0%	7.7%
3/23/2016 23:00	11	0	9	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:15	6	0	6	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:30	13	0	9	3	0	0	0	0	0	1	0	0	0	0	0.0%	7.7%
3/23/2016 23:45	10	0	6	4	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
Day Totals	4631	14	2857	1451	37	24	17	4	20	141	49	9	3	5	1.8%	4.9%

AM Peak Hr **11:15 AM**
AM Peak Vol **282**
AM PHF **0.892**
PM Peak Hr **4:30 PM**
PM Peak Vol **466**
PM PHF **0.917**

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602331
Route: AZ-89
Location: Btwn BALD EAGLE TRAIL & ROLLING HILLS RD

Site Ref: 2
Direction: NB
Latitude: 34.85875
Longitude: -112.46866

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+
3/23/2016 0:00	6	0	0	0	0	0	0	0	0	0	0	0	0	2	4	0	0	0
3/23/2016 0:15	2	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0
3/23/2016 0:30	9	0	0	0	0	0	0	0	0	0	0	0	1	4	4	0	0	0
3/23/2016 0:45	5	0	0	0	0	0	0	0	0	0	0	0	1	2	2	0	0	0
3/23/2016 1:00	3	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	0	0
3/23/2016 1:15	4	0	0	0	0	0	0	0	0	0	0	0	2	2	0	0	0	0
3/23/2016 1:30	1	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0
3/23/2016 1:45	3	0	0	0	0	0	0	0	0	0	1	0	0	2	0	0	0	0
3/23/2016 2:00	5	0	0	0	0	0	0	0	0	0	0	0	1	1	2	1	0	0
3/23/2016 2:15	3	0	0	0	0	0	0	0	0	0	0	0	0	2	1	0	0	0
3/23/2016 2:30	4	0	0	0	0	0	0	0	0	0	0	0	1	0	3	0	0	0
3/23/2016 2:45	8	0	0	0	0	0	0	0	0	0	1	0	0	4	3	0	0	0
3/23/2016 3:00	5	0	0	0	0	0	0	0	0	0	0	0	0	3	2	0	0	0
3/23/2016 3:15	3	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	0	0
3/23/2016 3:30	6	0	0	0	0	0	0	0	0	0	0	0	0	2	4	0	0	0
3/23/2016 3:45	3	0	0	0	0	0	0	0	0	0	0	0	0	2	1	0	0	0
3/23/2016 4:00	7	0	0	0	0	0	0	0	0	0	0	0	0	0	6	1	0	0
3/23/2016 4:15	4	0	0	0	0	0	0	0	0	0	0	0	0	1	2	1	0	0
3/23/2016 4:30	8	0	0	0	0	0	0	0	0	0	0	0	1	2	3	2	0	0
3/23/2016 4:45	14	0	0	0	0	0	0	0	0	0	0	0	0	3	7	3	1	0
3/23/2016 5:00	15	0	0	0	0	0	0	0	0	0	0	0	1	9	3	1	1	0
3/23/2016 5:15	19	0	0	0	0	0	0	0	0	0	0	0	0	5	14	0	0	0
3/23/2016 5:30	24	0	0	0	0	0	0	0	0	0	0	0	5	8	9	2	0	0
3/23/2016 5:45	16	0	0	0	0	0	0	0	0	0	0	0	3	7	5	1	0	0
3/23/2016 6:00	32	0	0	0	0	0	0	0	0	0	0	2	3	15	11	1	0	0
3/23/2016 6:15	44	0	0	0	0	0	0	0	4	4	1	0	3	18	13	1	0	0
3/23/2016 6:30	41	0	0	0	0	0	0	0	0	0	0	1	6	20	12	1	0	1
3/23/2016 6:45	43	0	0	0	0	0	0	0	0	0	0	3	9	19	11	1	0	0
3/23/2016 7:00	39	0	0	0	0	0	0	0	0	0	1	1	11	8	16	2	0	0
3/23/2016 7:15	56	0	0	0	0	0	0	0	0	0	0	4	8	28	11	5	0	0
3/23/2016 7:30	66	0	0	0	0	0	0	0	0	0	1	1	7	34	14	9	0	0
3/23/2016 7:45	38	0	0	0	0	0	0	0	0	0	0	0	2	17	16	2	1	0
3/23/2016 8:00	50	0	0	0	0	0	0	0	0	0	0	0	7	15	23	5	0	0
3/23/2016 8:15	49	0	0	0	0	0	0	0	0	0	0	2	7	28	10	2	0	0
3/23/2016 8:30	30	0	0	0	0	0	0	0	0	0	3	4	10	7	5	1	0	0
3/23/2016 8:45	57	0	0	0	0	0	0	0	0	0	2	1	7	32	13	2	0	0
3/23/2016 9:00	66	0	0	0	0	0	0	0	0	0	2	12	17	21	11	3	0	0
3/23/2016 9:15	51	0	0	0	0	0	0	0	0	0	1	2	12	19	16	1	0	0
3/23/2016 9:30	52	0	0	0	0	0	0	0	0	0	2	5	8	22	11	4	0	0
3/23/2016 9:45	62	0	0	0	0	0	0	0	0	0	0	7	20	25	9	1	0	0
3/23/2016 10:00	58	0	0	0	0	0	0	0	1	4	1	9	13	20	9	1	0	0
3/23/2016 10:15	70	0	0	0	0	0	0	0	0	0	2	8	12	34	13	1	0	0
3/23/2016 10:30	63	0	0	0	0	0	0	0	0	0	2	6	15	25	13	2	0	0
3/23/2016 10:45	54	0	0	0	0	0	0	0	0	0	1	1	8	33	10	0	1	0
3/23/2016 11:00	71	0	0	0	0	0	0	0	0	1	3	20	16	17	9	4	1	0
3/23/2016 11:15	79	0	0	0	0	0	0	0	0	3	7	4	20	38	5	2	0	0
3/23/2016 11:30	70	0	0	0	0	0	0	0	0	0	0	6	25	29	10	0	0	0
3/23/2016 11:45	59	0	0	0	0	0	0	0	0	0	0	1	4	36	17	1	0	0
3/23/2016 12:00	74	0	0	0	0	0	0	0	0	0	0	6	12	29	22	5	0	0
3/23/2016 12:15	68	0	0	0	0	0	0	0	0	0	1	12	22	16	15	2	0	0
3/23/2016 12:30	55	0	0	0	0	0	0	0	0	0	0	1	15	26	10	2	0	1
3/23/2016 12:45	72	0	0	0	0	0	0	0	0	0	1	3	15	30	20	2	1	0
3/23/2016 13:00	87	0	0	0	0	0	0	0	0	0	2	11	8	33	30	2	1	0
3/23/2016 13:15	89	0	0	0	0	0	0	0	0	0	2	5	20	46	14	2	0	0
3/23/2016 13:30	74	0	0	0	0	0	0	0	0	3	6	9	19	24	9	4	0	0
3/23/2016 13:45	76	0	0	0	0	0	0	0	0	0	1	1	14	39	18	3	0	0
3/23/2016 14:00	74	0	0	0	0	0	0	0	0	0	0	1	19	41	12	1	0	0
3/23/2016 14:15	84	0	0	0	0	0	0	0	0	0	0	1	21	46	10	6	0	0
3/23/2016 14:30	92	0	0	0	0	0	0	0	0	1	0	8	18	43	19	3	0	0
3/23/2016 14:45	100	0	0	0	0	0	0	0	0	0	4	2	18	51	23	2	0	0
3/23/2016 15:00	74	0	0	0	0	0	0	0	0	0	0	6	9	35	22	1	1	0
3/23/2016 15:15	94	0	0	0	0	0	0	0	0	0	3	8	19	38	22	4	0	0
3/23/2016 15:30	98	0	0	0	0	0	0	0	0	0	2	7	16	52	21	0	0	0
3/23/2016 15:45	88	0	0	0	0	0	0	0	0	0	0	2	13	36	33	4	0	0
3/23/2016 16:00	125	0	0	0	0	0	0	0	0	0	0	3	42	58	17	5	0	0
3/23/2016 16:15	98	0	0	0	0	0	0	0	0	0	0	5	17	48	20	8	0	0
3/23/2016 16:30	118	0	0	0	0	0	0	0	0	0	0	0	15	74	26	3	0	0
3/23/2016 16:45	105	0	0	0	0	0	0	0	0	0	1	0	16	46	39	3	0	0
3/23/2016 17:00	127	0	0	0	0	0	0	0	0	0	1	15	28	49	33	1	0	0
3/23/2016 17:15	116	0	0	0	0	0	0	0	0	0	4	14	12	42	39	5	0	0
3/23/2016 17:30	109	0	0	0	0	0	0	0	0	0	0	1	17	43	42	6	0	0
3/23/2016 17:45	112	0	0	0	0	0	0	0	0	0	1	4	19	50	32	6	0	0
3/23/2016 18:00	84	0	0	0	0	0	0	0	0	0	0	1	10	28	42	2	1	0
3/23/2016 18:15	83	0	0	0	0	0	0	0	0	0	0	2	8	32	36	3	0	2
3/23/2016 18:30	84	0	0	0	0	0	0	0	0	0	0	0	12	33	33	5	1	0
3/23/2016 18:45	72	0	0	0	0	0	0	0	0	0	0	5	16	34	16	0	1	0
3/23/2016 19:00	47	0	0	0	0	0	0	0	0	0	0	3	14	21	9	0	0	0
3/23/2016 19:15	53	0	0	0	0	0	0	0	0	1	1	4	12	25	10	0	0	0
3/23/2016 19:30	47	0	0	0	0	0	0	0	1	3	3	6	5	19	7	3	0	0
3/23/2016 19:45	56	0	0	0	0	0	0	0	0	0	1	3	10	23	12	5	2	0
3/23/2016 20:00	52	0	0	0	0	0	0	0	0	0	0	4	6	24	15	3	0	0
3/23/2016 20:15	44	0	0	0	0	0	0	0	0	1	0	4	9	22	6	2	0	0
3/23/2016 20:30	34	0	0	0	0	0	0	0	0	1	6	2	3	13	8	1	0	0
3/23/2016 20:45	41	0	0	0	0	0	0	0	0	0	4	4	6	18	8	1	0	0
3/23/2016 21:00	37	0	0	0	0	0	0	0	0	0	0	0	5	14	13	5	0	0

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602331
Route: AZ-89
Location: Btwn BALD EAGLE TRAIL & ROLLING HILLS RD

Site Ref: 2
Direction: NB
Latitude: 34.85875
Longitude: -112.46866

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+
3/23/2016 21:15	40	0	0	0	0	0	0	0	0	0	0	4	9	17	9	1	0	0
3/23/2016 21:30	35	0	0	0	0	0	0	0	0	0	1	0	8	16	7	3	0	0
3/23/2016 21:45	26	0	0	0	0	0	0	0	0	0	0	3	3	15	5	0	0	0
3/23/2016 22:00	14	0	0	0	0	0	0	0	0	0	1	1	3	5	3	1	0	0
3/23/2016 22:15	25	0	0	0	0	0	0	0	0	0	0	5	6	6	8	0	0	0
3/23/2016 22:30	18	0	0	0	0	0	0	0	0	0	0	4	2	4	7	1	0	0
3/23/2016 22:45	13	0	0	0	0	0	0	0	0	0	1	0	4	1	6	1	0	0
3/23/2016 23:00	11	0	0	0	0	0	0	0	0	0	0	0	0	4	5	0	1	1
3/23/2016 23:15	6	0	0	0	0	0	0	0	0	0	0	0	1	2	2	0	1	0
3/23/2016 23:30	13	0	0	0	0	0	0	0	0	0	0	0	1	5	6	1	0	0
3/23/2016 23:45	10	0	0	0	0	0	0	0	0	0	0	0	1	2	6	1	0	0
Day Totals	4631	0	0	0	0	0	0	0	6	22	78	281	845	2002	1192	185	15	5

AM Peak Hr	11:15 AM	Average Speed	62.4	Pct > 25 mph	100%
AM Peak Vol	282	Median Speed	62.7	Pct > 30 mph	100%
AM PHF	0.892	85th Pct Speed	67.9	Pct > 35 mph	100%
PM Peak Hr	4:30 PM	95th Pct Speed	69.8	Pct > 40 mph	100%
PM Peak Vol	466	Pace Speed	60	Pct > 45 mph	99%
PM PHF	0.917	Percent in Pace	68.7%	Pct > 50 mph	98%
		Speed Limit	65		
		Percent Speedin	30.2%		

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602332
Route: AZ-89
Location: Btwn BALD EAGLE TRAIL & ROLLING HILLS RD

Site Ref: 2
Direction: SB
Latitude: 34.85875
Longitude: -112.46866

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 0:00	2	0	1	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 0:15	4	0	4	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 0:30	5	0	3	1	1	0	0	0	0	0	0	0	0	0	20.0%	0.0%
3/23/2016 0:45	4	0	2	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 1:00	2	0	1	0	0	0	0	0	0	0	1	0	0	0	0.0%	50.0%
3/23/2016 1:15	5	0	3	0	0	0	0	0	0	2	0	0	0	0	0.0%	40.0%
3/23/2016 1:30	3	0	1	1	0	0	0	0	0	1	0	0	0	0	0.0%	33.3%
3/23/2016 1:45	4	0	1	1	0	0	0	0	0	2	0	0	0	0	0.0%	50.0%
3/23/2016 2:00	7	0	5	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 2:15	8	0	5	2	0	0	0	0	0	1	0	0	0	0	0.0%	12.5%
3/23/2016 2:30	7	0	2	3	0	0	0	0	0	2	0	0	0	0	0.0%	28.6%
3/23/2016 2:45	6	0	1	2	0	0	1	0	0	2	0	0	0	0	16.7%	33.3%
3/23/2016 3:00	2	0	1	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 3:15	12	0	9	1	0	0	0	0	0	2	0	0	0	0	0.0%	16.7%
3/23/2016 3:30	5	0	3	0	0	0	0	0	0	2	0	0	0	0	0.0%	40.0%
3/23/2016 3:45	9	0	5	3	0	0	0	0	0	1	0	0	0	0	0.0%	11.1%
3/23/2016 4:00	16	0	8	5	0	0	0	0	0	2	0	1	0	0	0.0%	18.8%
3/23/2016 4:15	15	0	10	2	0	0	0	0	0	2	0	1	0	0	0.0%	20.0%
3/23/2016 4:30	13	0	5	5	0	0	0	0	0	3	0	0	0	0	0.0%	23.1%
3/23/2016 4:45	11	0	5	5	0	0	0	0	0	1	0	0	0	0	0.0%	9.1%
3/23/2016 5:00	25	0	14	10	0	0	0	0	0	0	0	1	0	0	0.0%	4.0%
3/23/2016 5:15	33	0	16	12	1	0	0	0	0	4	0	0	0	0	3.0%	12.1%
3/23/2016 5:30	57	0	29	27	0	0	0	0	0	1	0	0	0	0	0.0%	1.8%
3/23/2016 5:45	51	0	25	22	0	1	0	0	1	1	0	1	0	0	2.0%	5.9%
3/23/2016 6:00	62	0	32	27	0	1	1	0	0	1	0	0	0	0	3.2%	1.6%
3/23/2016 6:15	91	0	61	30	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 6:30	100	0	44	53	0	0	0	0	0	2	0	1	0	0	0.0%	3.0%
3/23/2016 6:45	117	0	73	42	1	0	0	0	0	1	0	0	0	0	0.9%	0.9%
3/23/2016 7:00	127	0	64	54	5	1	0	0	0	2	0	1	0	0	4.7%	2.4%
3/23/2016 7:15	115	1	65	47	0	1	0	0	0	1	0	0	0	0	0.9%	0.9%
3/23/2016 7:30	86	0	52	31	2	0	0	0	0	1	0	0	0	0	2.3%	1.2%
3/23/2016 7:45	102	0	49	44	2	1	0	0	0	5	1	0	0	0	2.9%	5.9%
3/23/2016 8:00	91	0	51	33	5	1	0	0	0	1	0	0	0	0	6.6%	1.1%
3/23/2016 8:15	77	0	40	32	1	1	1	0	0	2	0	0	0	0	3.9%	2.6%
3/23/2016 8:30	80	1	46	28	1	0	0	0	0	4	0	0	0	0	1.3%	5.0%
3/23/2016 8:45	67	0	35	27	1	0	1	0	0	2	1	0	0	0	3.0%	4.5%
3/23/2016 9:00	84	1	55	21	1	0	1	0	1	3	1	0	0	0	2.4%	6.0%
3/23/2016 9:15	80	0	49	29	0	0	0	0	0	2	0	0	0	0	0.0%	2.5%
3/23/2016 9:30	65	0	30	33	0	0	0	0	1	1	0	0	0	0	0.0%	3.1%
3/23/2016 9:45	75	0	40	27	5	0	1	0	0	2	0	0	0	0	8.0%	2.7%
3/23/2016 10:00	81	0	44	28	1	0	3	0	2	3	0	0	0	0	4.9%	6.2%
3/23/2016 10:15	87	0	50	32	0	1	1	0	0	2	1	0	0	0	2.3%	3.4%
3/23/2016 10:30	80	0	46	29	1	0	2	0	0	2	0	0	0	0	3.8%	2.5%
3/23/2016 10:45	75	0	39	27	2	0	2	1	2	2	0	0	0	0	6.7%	5.3%
3/23/2016 11:00	75	0	36	31	2	2	3	0	0	1	0	0	0	0	9.3%	1.3%
3/23/2016 11:15	70	0	38	27	1	1	0	0	0	2	1	0	0	0	2.9%	4.3%
3/23/2016 11:30	73	0	31	34	3	1	2	0	0	2	0	0	0	0	8.2%	2.7%
3/23/2016 11:45	77	0	38	30	4	1	1	1	0	1	1	0	0	0	9.1%	2.6%

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602332
Route: AZ-89
Location: Btwn BALD EAGLE TRAIL & ROLLING HILLS RD

Site Ref: 2
Direction: SB
Latitude: 34.85875
Longitude: -112.46866

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 12:00	80	0	49	25	1	2	1	0	0	0	1	1	0	0	5.0%	2.5%
3/23/2016 12:15	67	2	39	19	1	0	2	0	0	4	0	0	0	0	4.5%	6.0%
3/23/2016 12:30	70	0	39	28	1	1	0	0	0	1	0	0	0	0	2.9%	1.4%
3/23/2016 12:45	82	0	41	35	1	0	2	1	0	1	1	0	0	0	4.9%	2.4%
3/23/2016 13:00	80	0	45	27	4	0	4	0	0	0	0	0	0	0	10.0%	0.0%
3/23/2016 13:15	61	0	38	20	2	0	0	0	0	1	0	0	0	0	3.3%	1.6%
3/23/2016 13:30	51	0	24	18	4	1	2	0	1	1	0	0	0	0	13.7%	3.9%
3/23/2016 13:45	66	0	36	18	8	1	1	0	1	1	0	0	0	0	15.2%	3.0%
3/23/2016 14:00	64	0	39	20	2	0	0	0	0	3	0	0	0	0	3.1%	4.7%
3/23/2016 14:15	77	2	39	27	4	1	1	0	0	3	0	0	0	0	7.8%	3.9%
3/23/2016 14:30	62	0	38	20	0	0	2	0	0	2	0	0	0	0	3.2%	3.2%
3/23/2016 14:45	55	1	30	22	0	0	1	0	1	0	0	0	0	0	1.8%	1.8%
3/23/2016 15:00	75	0	37	26	4	0	4	0	1	3	0	0	0	0	10.7%	5.3%
3/23/2016 15:15	90	0	47	35	1	0	3	1	1	2	0	0	0	0	5.6%	3.3%
3/23/2016 15:30	83	0	51	25	5	0	1	0	1	0	0	0	0	0	7.2%	1.2%
3/23/2016 15:45	80	2	45	30	0	1	1	0	1	0	0	0	0	0	2.5%	1.3%
3/23/2016 16:00	73	0	44	24	1	0	1	0	0	2	0	0	0	1	2.7%	4.1%
3/23/2016 16:15	77	0	44	28	0	2	0	0	0	3	0	0	0	0	2.6%	3.9%
3/23/2016 16:30	81	1	44	30	2	1	0	0	0	3	0	0	0	0	3.7%	3.7%
3/23/2016 16:45	83	0	45	35	1	0	1	0	0	1	0	0	0	0	2.4%	1.2%
3/23/2016 17:00	66	0	39	24	1	0	0	0	0	1	0	1	0	0	1.5%	3.0%
3/23/2016 17:15	56	0	36	16	1	0	1	0	0	2	0	0	0	0	3.6%	3.6%
3/23/2016 17:30	75	0	43	27	1	1	1	0	0	1	1	0	0	0	4.0%	2.7%
3/23/2016 17:45	42	0	20	21	0	0	0	0	0	0	1	0	0	0	0.0%	2.4%
3/23/2016 18:00	52	1	29	19	0	1	0	0	0	0	0	2	0	0	1.9%	3.8%
3/23/2016 18:15	42	0	25	16	0	0	0	0	0	1	0	0	0	0	0.0%	2.4%
3/23/2016 18:30	44	0	29	13	0	0	0	0	0	2	0	0	0	0	0.0%	4.5%
3/23/2016 18:45	48	0	26	19	0	2	0	0	0	1	0	0	0	0	4.2%	2.1%
3/23/2016 19:00	27	0	13	13	1	0	0	0	0	0	0	0	0	0	3.7%	0.0%
3/23/2016 19:15	43	0	27	12	0	0	1	0	0	2	1	0	0	0	2.3%	7.0%
3/23/2016 19:30	38	0	17	20	0	0	0	0	0	1	0	0	0	0	0.0%	2.6%
3/23/2016 19:45	28	0	14	11	0	1	0	0	0	2	0	0	0	0	3.6%	7.1%
3/23/2016 20:00	17	0	10	6	0	0	0	0	0	0	0	1	0	0	0.0%	5.9%
3/23/2016 20:15	16	0	7	7	0	0	0	0	0	2	0	0	0	0	0.0%	12.5%
3/23/2016 20:30	16	0	10	6	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 20:45	24	0	15	9	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 21:00	15	0	9	6	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 21:15	14	0	7	3	0	0	0	0	0	4	0	0	0	0	0.0%	28.6%
3/23/2016 21:30	16	0	10	3	0	0	0	0	0	2	0	1	0	0	0.0%	18.8%
3/23/2016 21:45	4	0	4	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:00	6	0	5	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:15	6	0	5	0	0	0	0	0	0	1	0	0	0	0	0.0%	16.7%
3/23/2016 22:30	11	0	7	3	0	1	0	0	0	0	0	0	0	0	9.1%	0.0%
3/23/2016 22:45	12	0	7	5	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:00	4	0	0	4	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:15	3	0	3	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:30	1	0	0	0	0	0	0	0	0	1	0	0	0	0	0.0%	100.0%
3/23/2016 23:45	5	0	1	3	0	0	0	0	0	1	0	0	0	0	0.0%	20.0%
Day Totals	4531	12	2499	1683	86	29	50	4	14	129	12	12	0	1	3.7%	3.7%

AM Peak Hr **6:30 AM**
AM Peak Vol **459**
AM PHF **0.904**
PM Peak Hr **3:00 PM**
PM Peak Vol **328**
PM PHF **0.911**

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602332
Route: AZ-89
Location: Btwn BALD EAGLE TRAIL & ROLLING HILLS RD

Site Ref: 2
Direction: SB
Latitude: 34.85875
Longitude: -112.46866

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+
3/23/2016 0:00	2	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	0
3/23/2016 0:15	4	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	1	0
3/23/2016 0:30	5	0	0	0	0	0	0	0	0	0	0	0	1	2	1	1	0	0
3/23/2016 0:45	4	0	0	0	0	0	0	0	0	1	0	0	0	1	1	0	1	0
3/23/2016 1:00	2	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	0
3/23/2016 1:15	5	0	0	0	0	0	0	0	0	0	0	0	0	4	1	0	0	0
3/23/2016 1:30	3	0	0	0	0	0	0	0	1	0	0	0	0	0	2	0	0	0
3/23/2016 1:45	4	0	0	0	0	0	0	0	0	0	0	0	0	0	4	0	0	0
3/23/2016 2:00	7	0	0	0	0	0	0	0	0	0	0	0	0	2	4	0	1	0
3/23/2016 2:15	8	0	0	0	0	0	0	0	1	0	1	0	0	2	1	3	0	0
3/23/2016 2:30	7	0	0	0	0	0	0	0	0	0	0	0	0	0	3	1	3	0
3/23/2016 2:45	6	0	0	0	0	0	0	0	0	0	1	0	0	1	2	1	0	1
3/23/2016 3:00	2	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	0	0
3/23/2016 3:15	12	0	0	0	0	0	0	0	0	0	1	0	0	3	4	4	0	0
3/23/2016 3:30	5	0	0	0	0	0	0	0	0	1	0	0	0	0	2	1	1	0
3/23/2016 3:45	9	0	0	0	0	0	0	0	0	0	0	0	0	2	4	2	1	0
3/23/2016 4:00	16	0	0	0	0	0	0	0	0	0	0	1	2	1	9	3	0	0
3/23/2016 4:15	15	0	0	0	0	0	0	0	0	0	0	0	0	1	3	8	0	3
3/23/2016 4:30	13	0	0	0	0	0	0	0	0	0	1	1	2	3	2	2	1	1
3/23/2016 4:45	11	0	0	0	0	0	0	0	0	0	1	0	2	2	2	2	1	1
3/23/2016 5:00	25	0	0	0	0	0	0	0	0	0	0	0	1	4	13	3	3	1
3/23/2016 5:15	33	0	0	0	0	0	0	0	0	0	0	2	3	5	10	8	5	0
3/23/2016 5:30	57	0	0	0	0	0	0	0	0	2	1	1	3	16	19	11	2	2
3/23/2016 5:45	51	0	0	0	0	0	0	0	0	0	1	4	1	7	25	8	5	0
3/23/2016 6:00	62	0	0	0	0	0	0	0	0	0	0	0	5	15	21	15	5	1
3/23/2016 6:15	91	0	0	0	0	0	0	0	0	0	2	1	1	14	40	28	5	0
3/23/2016 6:30	100	0	0	0	0	0	0	0	0	0	3	6	3	26	33	18	7	4
3/23/2016 6:45	117	0	0	0	0	0	0	0	1	1	4	8	15	27	40	17	4	0
3/23/2016 7:00	127	0	0	0	0	0	0	0	0	1	2	3	6	42	44	23	5	1
3/23/2016 7:15	115	0	0	0	0	0	0	0	0	0	6	2	14	30	37	22	4	0
3/23/2016 7:30	86	0	0	0	0	0	0	0	0	0	1	4	5	16	35	15	7	3
3/23/2016 7:45	102	0	0	0	0	0	0	0	0	1	4	8	4	20	35	23	6	1
3/23/2016 8:00	91	0	0	0	0	0	0	0	1	0	2	12	6	18	28	20	4	0
3/23/2016 8:15	77	0	0	0	0	0	0	0	0	1	1	3	3	16	27	21	3	2
3/23/2016 8:30	80	0	0	0	0	0	0	0	0	1	4	6	1	16	35	15	2	0
3/23/2016 8:45	67	0	0	0	0	0	0	1	0	3	1	2	4	14	29	10	3	0
3/23/2016 9:00	84	0	0	0	0	0	0	0	0	1	2	4	5	22	36	10	4	0
3/23/2016 9:15	80	0	0	0	0	0	0	0	0	0	3	4	5	30	26	11	1	0
3/23/2016 9:30	65	0	0	0	0	0	0	0	0	2	1	0	9	20	29	4	0	0
3/23/2016 9:45	75	0	0	0	0	0	0	0	0	2	3	4	11	24	20	9	1	1
3/23/2016 10:00	81	0	0	0	0	0	0	0	0	0	2	3	6	28	29	12	1	0
3/23/2016 10:15	87	0	0	0	0	0	0	0	0	1	5	2	9	17	40	12	1	0
3/23/2016 10:30	80	0	0	0	0	0	0	0	0	0	6	4	6	25	27	5	5	2
3/23/2016 10:45	75	0	0	0	0	0	0	0	0	2	1	4	10	14	25	18	0	1
3/23/2016 11:00	75	0	0	0	0	0	0	0	0	0	2	3	6	13	32	18	1	0
3/23/2016 11:15	70	0	0	0	0	0	0	0	0	0	0	3	10	27	20	9	0	1
3/23/2016 11:30	73	0	0	0	0	0	0	0	0	2	5	3	13	18	22	8	2	0
3/23/2016 11:45	77	0	0	0	0	0	0	0	0	1	2	3	12	21	30	6	1	1
3/23/2016 12:00	80	0	0	0	0	0	0	0	0	1	4	2	9	31	24	7	1	1
3/23/2016 12:15	67	0	0	0	0	0	0	0	0	0	1	3	8	22	21	10	2	0
3/23/2016 12:30	70	0	0	0	0	0	0	0	0	0	2	1	2	28	26	9	1	1
3/23/2016 12:45	82	0	0	0	0	0	0	1	0	0	3	4	5	23	33	12	1	0
3/23/2016 13:00	80	0	0	0	0	0	0	0	0	0	3	1	11	24	28	9	4	0
3/23/2016 13:15	61	0	0	0	0	0	0	0	0	1	3	1	8	18	20	8	2	0
3/23/2016 13:30	51	0	0	0	0	0	0	0	0	3	0	2	3	13	25	3	2	0
3/23/2016 13:45	66	0	0	0	0	0	0	0	0	2	0	4	4	14	34	6	2	0
3/23/2016 14:00	64	0	0	0	0	0	0	0	0	1	3	0	7	25	21	6	0	1
3/23/2016 14:15	77	0	0	0	0	0	0	0	0	0	1	2	6	25	23	16	3	1
3/23/2016 14:30	62	0	0	0	0	0	0	0	0	1	2	0	7	15	23	11	3	0
3/23/2016 14:45	55	0	0	0	0	0	0	0	0	1	2	1	5	18	21	5	0	2
3/23/2016 15:00	75	0	0	0	0	0	0	0	0	1	5	3	1	12	29	20	3	1
3/23/2016 15:15	90	0	0	0	0	0	0	0	0	1	4	4	13	21	28	15	3	1
3/23/2016 15:30	83	0	0	0	0	0	0	0	0	2	2	0	7	14	41	17	0	0
3/23/2016 15:45	80	0	0	0	0	0	0	0	0	0	0	1	6	19	28	21	5	0
3/23/2016 16:00	73	0	0	0	0	0	0	0	0	0	3	1	2	30	27	10	0	0
3/23/2016 16:15	77	0	0	0	0	0	0	0	0	0	4	1	13	18	27	11	3	0
3/23/2016 16:30	81	0	0	0	0	0	0	0	0	1	7	5	13	25	24	4	1	1
3/23/2016 16:45	83	0	0	0	0	0	0	0	0	1	1	3	13	25	26	12	2	0
3/23/2016 17:00	66	0	0	0	0	0	0	0	0	1	1	4	12	13	25	8	2	0
3/23/2016 17:15	56	0	0	0	0	0	0	0	0	0	1	0	2	15	28	10	0	0
3/23/2016 17:30	75	0	0	0	0	0	0	1	0	2	1	3	7	16	33	11	1	0
3/23/2016 17:45	42	0	0	0	0	0	0	0	0	3	2	5	10	19	3	0	0	0
3/23/2016 18:00	52	0	0	0	0	0	0	0	0	0	1	1	7	14	24	5	0	0
3/23/2016 18:15	42	0	0	0	0	0	0	0	1	1	0	3	2	9	14	10	2	0
3/23/2016 18:30	44	0	0	0	0	0	0	0	0	0	1	0	6	15	17	4	0	1
3/23/2016 18:45	48	0	0	0	0	0	0	0	0	0	1	0	3	15	23	3	1	2
3/23/2016 19:00	27	0	0	0	0	0	0	0	0	2	1	0	2	8	11	1	2	0
3/23/2016 19:15	43	0	0	0	0	0	0	0	0	0	1	3	4	16	14	5	0	0
3/23/2016 19:30	38	0	0	0	0	0	0	0	0	0	0	1	7	11	13	5	0	1
3/23/2016 19:45	28	0	0	0	0	0	0	0	0	1	0	2	8	6	5	6	0	0
3/23/2016 20:00	17	0	0	0	0	0	0	0	1	0	1	2	3	4	4	2	0	0
3/23/2016 20:15	16	0	0	0	0	0	0	0	0	0	1	2	5	4	4	0	0	0
3/23/2016 20:30	16	0	0	0	0	0	0	0	0	0	0	2	4	3	5	1	0	1
3/23/2016 20:45	24	0	0	0	0	0	0	0	0	0	1	3	1	15	3	1	0	0
3/23/2016 21:00	15	0	0	0	0	0	0	0	0	0	0	5	3	2	4	1	0	0

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602332
Route: AZ-89
Location: Btwn BALD EAGLE TRAIL & ROLLING HILLS RD

Site Ref: 2
Direction: SB
Latitude: 34.85875
Longitude: -112.46866

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+
3/23/2016 21:15	14	0	0	0	0	0	0	0	0	0	2	2	0	5	3	2	0	0
3/23/2016 21:30	16	0	0	0	0	0	0	0	0	0	0	0	1	7	5	3	0	0
3/23/2016 21:45	4	0	0	0	0	0	0	0	0	0	0	0	1	0	1	1	1	0
3/23/2016 22:00	6	0	0	0	0	0	0	0	0	0	0	0	0	2	3	0	1	0
3/23/2016 22:15	6	0	0	0	0	0	0	0	0	0	0	0	2	2	2	0	0	0
3/23/2016 22:30	11	0	0	0	0	0	0	0	0	0	0	1	1	5	1	3	0	0
3/23/2016 22:45	12	0	0	0	0	0	0	0	0	0	0	0	3	2	5	2	0	0
3/23/2016 23:00	4	0	0	0	0	0	0	0	0	0	0	0	0	0	2	1	1	0
3/23/2016 23:15	3	0	0	0	0	0	0	0	0	0	0	1	1	1	0	0	0	0
3/23/2016 23:30	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0
3/23/2016 23:45	5	0	0	0	0	0	0	0	0	0	0	0	0	1	2	0	2	0
Day Totals	4531	0	0	0	0	0	0	3	6	46	135	177	417	1193	1655	709	149	41

AM Peak Hr	6:30 AM	Average Speed	65.0	Pct > 25 mph	100%
AM Peak Vol	459	Median Speed	66.0	Pct > 30 mph	100%
AM PHF	0.904	85th Pct Speed	71.6	Pct > 35 mph	100%
PM Peak Hr	3:00 PM	95th Pct Speed	74.6	Pct > 40 mph	100%
PM Peak Vol	328	Pace Speed	60	Pct > 45 mph	99%
PM PHF	0.911	Percent in Pace	62.3%	Pct > 50 mph	96%
		Speed Limit	65		
		Percent Speedin	56.4%		

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602333
Route: AZ-89 (NEAR TOP OF HILL @ 1000' N/O MP341)
Location: N of MP 341

Site Ref: 3
Direction: NB
Latitude: 34.93629
Longitude: -112.43351

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 0:00	2	0	0	1	0	1	0	0	0	0	0	0	0	0	50.0%	0.0%
3/23/2016 0:15	1	0	0	0	0	0	0	0	0	0	0	1	0	0	0.0%	100.0%
3/23/2016 0:30	3	0	0	0	0	0	0	0	0	3	0	0	0	0	0.0%	100.0%
3/23/2016 0:45	2	0	1	0	0	0	0	0	0	1	0	0	0	0	0.0%	50.0%
3/23/2016 1:00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	--	--
3/23/2016 1:15	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 1:30	2	0	1	0	0	0	0	0	0	1	0	0	0	0	0.0%	50.0%
3/23/2016 1:45	1	0	0	0	0	0	0	0	0	1	0	0	0	0	0.0%	100.0%
3/23/2016 2:00	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 2:15	2	0	0	0	0	0	0	0	0	2	0	0	0	0	0.0%	100.0%
3/23/2016 2:30	2	0	0	0	0	0	0	0	0	2	0	0	0	0	0.0%	100.0%
3/23/2016 2:45	1	0	0	0	0	0	0	0	0	1	0	0	0	0	0.0%	100.0%
3/23/2016 3:00	9	0	2	2	0	0	0	0	0	4	0	1	0	0	0.0%	55.6%
3/23/2016 3:15	3	0	1	1	0	0	0	0	0	1	0	0	0	0	0.0%	33.3%
3/23/2016 3:30	7	0	4	1	0	0	0	0	0	2	0	0	0	0	0.0%	28.6%
3/23/2016 3:45	3	0	0	3	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 4:00	6	0	4	1	0	0	0	0	0	0	0	1	0	0	0.0%	16.7%
3/23/2016 4:15	3	0	1	1	0	0	0	0	0	1	0	0	0	0	0.0%	33.3%
3/23/2016 4:30	9	0	3	4	0	0	0	0	0	2	0	0	0	0	0.0%	22.2%
3/23/2016 4:45	11	0	5	3	0	1	0	0	0	1	0	1	0	0	9.1%	18.2%
3/23/2016 5:00	14	0	4	7	0	0	0	0	1	1	0	1	0	0	0.0%	21.4%
3/23/2016 5:15	17	0	7	9	0	0	0	0	1	0	0	0	0	0	0.0%	5.9%
3/23/2016 5:30	34	1	14	19	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 5:45	24	0	7	13	0	0	0	0	1	3	0	0	0	0	0.0%	16.7%
3/23/2016 6:00	26	0	9	14	0	1	0	0	0	2	0	0	0	0	3.8%	7.7%
3/23/2016 6:15	42	0	19	19	0	1	0	0	0	3	0	0	0	0	2.4%	7.1%
3/23/2016 6:30	54	0	23	26	0	0	2	0	0	3	0	0	0	0	3.7%	5.6%
3/23/2016 6:45	42	1	16	22	0	0	0	0	0	3	0	0	0	0	0.0%	7.1%
3/23/2016 7:00	34	0	15	9	0	2	0	0	0	7	1	0	0	0	5.9%	23.5%
3/23/2016 7:15	30	0	13	12	1	0	1	0	2	0	1	0	0	0	6.7%	10.0%
3/23/2016 7:30	41	0	21	11	0	0	1	0	0	3	5	0	0	0	2.4%	19.5%
3/23/2016 7:45	25	0	11	13	0	0	0	0	0	1	0	0	0	0	0.0%	4.0%
3/23/2016 8:00	30	0	14	13	0	0	1	0	0	2	0	0	0	0	3.3%	6.7%
3/23/2016 8:15	21	0	10	4	0	0	0	0	2	3	1	1	0	0	0.0%	33.3%
3/23/2016 8:30	31	0	13	9	0	0	0	0	0	5	4	0	0	0	0.0%	29.0%
3/23/2016 8:45	30	0	20	8	0	0	0	0	0	2	0	0	0	0	0.0%	6.7%
3/23/2016 9:00	26	0	17	7	1	0	0	0	0	1	0	0	0	0	3.8%	3.8%
3/23/2016 9:15	39	0	20	10	0	1	0	1	2	2	2	0	0	1	5.1%	17.9%
3/23/2016 9:30	32	0	13	11	1	0	0	0	1	3	3	0	0	0	3.1%	21.9%
3/23/2016 9:45	40	0	17	12	1	0	0	0	4	5	1	0	0	0	2.5%	25.0%
3/23/2016 10:00	27	0	15	8	0	0	1	0	1	2	0	0	0	0	3.7%	11.1%
3/23/2016 10:15	47	0	20	14	0	2	0	0	1	5	5	0	0	0	4.3%	23.4%
3/23/2016 10:30	44	0	25	14	1	1	0	0	0	2	1	0	0	0	4.5%	6.8%
3/23/2016 10:45	31	0	17	12	0	0	0	0	1	1	0	0	0	0	0.0%	6.5%
3/23/2016 11:00	37	1	18	16	0	0	0	0	0	1	0	1	0	0	0.0%	5.4%
3/23/2016 11:15	35	3	12	9	1	0	0	0	1	4	5	0	0	0	2.9%	28.6%
3/23/2016 11:30	38	1	21	9	0	1	1	1	0	2	2	0	0	0	7.9%	10.5%
3/23/2016 11:45	35	0	18	14	0	0	1	0	0	1	0	0	0	1	2.9%	5.7%

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602333
Route: AZ-89 (NEAR TOP OF HILL @ 1000' N/O MP341)
Location: N of MP 341

Site Ref: 3
Direction: NB
Latitude: 34.93629
Longitude: -112.43351

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 12:00	29	2	13	13	0	0	0	0	0	1	0	0	0	0	0.0%	3.4%
3/23/2016 12:15	38	1	17	13	0	0	0	1	0	4	1	0	0	1	2.6%	15.8%
3/23/2016 12:30	37	0	20	12	0	0	0	0	0	2	3	0	0	0	0.0%	13.5%
3/23/2016 12:45	25	1	12	9	1	0	0	0	0	0	0	0	0	2	4.0%	8.0%
3/23/2016 13:00	34	1	20	11	0	0	0	0	0	2	0	0	0	0	0.0%	5.9%
3/23/2016 13:15	42	0	21	14	0	1	0	0	0	4	2	0	0	0	2.4%	14.3%
3/23/2016 13:30	30	0	17	7	1	0	1	0	0	1	3	0	0	0	6.7%	13.3%
3/23/2016 13:45	37	1	11	20	1	0	1	0	0	3	0	0	0	0	5.4%	8.1%
3/23/2016 14:00	21	0	13	7	0	0	0	0	0	1	0	0	0	0	0.0%	4.8%
3/23/2016 14:15	38	0	18	11	0	0	0	0	0	5	3	0	0	1	0.0%	23.7%
3/23/2016 14:30	29	0	21	5	0	0	0	0	0	0	3	0	0	0	0.0%	10.3%
3/23/2016 14:45	34	0	19	11	1	1	0	0	1	1	0	0	0	0	5.9%	5.9%
3/23/2016 15:00	26	0	11	11	0	0	0	0	1	3	0	0	0	0	0.0%	15.4%
3/23/2016 15:15	22	0	11	7	1	0	1	1	0	1	0	0	0	0	13.6%	4.5%
3/23/2016 15:30	28	0	17	9	0	0	0	0	0	2	0	0	0	0	0.0%	7.1%
3/23/2016 15:45	25	0	9	12	0	0	0	0	1	3	0	0	0	0	0.0%	16.0%
3/23/2016 16:00	22	0	7	13	0	0	0	0	0	2	0	0	0	0	0.0%	9.1%
3/23/2016 16:15	34	0	20	11	1	0	1	0	0	1	0	0	0	0	5.9%	2.9%
3/23/2016 16:30	22	0	12	7	0	0	0	0	1	1	0	1	0	0	0.0%	13.6%
3/23/2016 16:45	27	0	14	11	0	0	0	0	0	1	1	0	0	0	0.0%	7.4%
3/23/2016 17:00	28	0	15	10	0	0	0	0	0	1	0	2	0	0	0.0%	10.7%
3/23/2016 17:15	35	0	16	14	1	0	0	0	0	4	0	0	0	0	2.9%	11.4%
3/23/2016 17:30	19	0	8	9	0	1	0	0	0	1	0	0	0	0	5.3%	5.3%
3/23/2016 17:45	19	0	10	8	0	0	0	0	0	1	0	0	0	0	0.0%	5.3%
3/23/2016 18:00	23	0	10	12	0	0	0	0	0	1	0	0	0	0	0.0%	4.3%
3/23/2016 18:15	20	0	11	9	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 18:30	17	0	8	7	0	0	0	0	0	2	0	0	0	0	0.0%	11.8%
3/23/2016 18:45	27	0	12	13	0	1	0	0	0	0	0	1	0	0	3.7%	3.7%
3/23/2016 19:00	16	0	9	5	1	0	0	0	0	1	0	0	0	0	6.3%	6.3%
3/23/2016 19:15	13	0	9	4	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 19:30	10	0	7	3	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 19:45	12	0	5	6	0	0	0	0	0	1	0	0	0	0	0.0%	8.3%
3/23/2016 20:00	10	0	6	2	0	0	0	0	0	2	0	0	0	0	0.0%	20.0%
3/23/2016 20:15	5	0	0	5	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 20:30	9	0	5	2	0	0	0	0	0	2	0	0	0	0	0.0%	22.2%
3/23/2016 20:45	9	0	5	3	0	0	0	0	0	1	0	0	0	0	0.0%	11.1%
3/23/2016 21:00	8	0	4	3	0	0	0	0	0	1	0	0	0	0	0.0%	12.5%
3/23/2016 21:15	7	0	6	0	0	0	0	0	0	1	0	0	0	0	0.0%	14.3%
3/23/2016 21:30	7	0	2	4	0	0	0	0	0	1	0	0	0	0	0.0%	14.3%
3/23/2016 21:45	3	0	2	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:00	2	0	0	1	0	0	0	0	0	1	0	0	0	0	0.0%	50.0%
3/23/2016 22:15	5	0	2	2	0	0	0	0	0	1	0	0	0	0	0.0%	20.0%
3/23/2016 22:30	5	0	2	3	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:45	3	0	1	1	0	0	0	0	0	1	0	0	0	0	0.0%	33.3%
3/23/2016 23:00	2	0	1	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:15	0	0	0	0	0	0	0	0	0	0	0	0	0	0	--	--
3/23/2016 23:30	3	0	2	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:45	2	0	0	1	0	0	0	0	0	1	0	0	0	0	0.0%	50.0%
Day Totals	1914	13	912	707	14	15	12	4	22	151	47	11	0	6	2.4%	12.4%

AM Peak Hr 6:15 AM
AM Peak Vol 172
AM PHF 0.796
PM Peak Hr 1:00 PM
PM Peak Vol 143
PM PHF 0.851

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602333
Route: AZ-89 (NEAR TOP OF HILL @ 1000' N/O MP341)
Location: N of MP 341

Site Ref: 3
Direction: NB
Latitude: 34.93629
Longitude: -112.43351

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+
3/23/2016 0:00	2	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	0	0
3/23/2016 0:15	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0
3/23/2016 0:30	3	0	0	0	0	0	0	0	0	0	0	0	0	0	3	0	0	0
3/23/2016 0:45	2	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0
3/23/2016 1:00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3/23/2016 1:15	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0
3/23/2016 1:30	2	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	0
3/23/2016 1:45	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0
3/23/2016 2:00	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0
3/23/2016 2:15	2	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	0
3/23/2016 2:30	2	0	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0
3/23/2016 2:45	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0
3/23/2016 3:00	9	0	0	0	0	0	0	0	0	0	0	0	3	1	2	2	1	0
3/23/2016 3:15	3	0	0	0	0	0	0	0	0	0	0	0	0	1	2	0	0	0
3/23/2016 3:30	7	0	0	0	0	0	0	0	0	0	0	0	0	1	2	3	1	0
3/23/2016 3:45	3	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	1	0
3/23/2016 4:00	6	0	0	0	0	0	0	0	0	0	0	0	0	0	4	1	1	0
3/23/2016 4:15	3	0	0	0	0	0	0	0	0	0	0	0	0	0	2	1	0	0
3/23/2016 4:30	9	0	0	0	0	0	0	0	0	0	0	0	0	1	3	3	0	2
3/23/2016 4:45	11	0	0	0	0	0	0	0	0	0	0	0	1	2	5	1	1	1
3/23/2016 5:00	14	0	0	0	0	0	0	0	0	0	0	0	0	2	3	6	1	2
3/23/2016 5:15	17	0	0	0	0	0	0	0	0	0	0	0	0	1	10	5	1	0
3/23/2016 5:30	34	0	0	0	0	0	0	0	0	0	0	0	1	3	17	11	2	0
3/23/2016 5:45	24	0	0	0	0	0	0	0	0	0	0	2	4	1	10	3	3	1
3/23/2016 6:00	26	0	0	0	0	0	0	0	0	0	2	2	0	4	12	5	1	0
3/23/2016 6:15	42	0	0	0	0	0	0	0	0	0	0	0	3	5	18	12	4	0
3/23/2016 6:30	54	0	0	0	0	0	0	0	0	4	1	0	1	12	22	11	2	1
3/23/2016 6:45	42	0	0	0	0	0	1	0	0	0	1	2	2	8	22	6	0	0
3/23/2016 7:00	34	0	0	0	0	0	0	0	0	0	0	0	3	6	18	5	1	1
3/23/2016 7:15	30	0	0	0	0	0	0	0	0	0	0	0	3	6	10	10	1	0
3/23/2016 7:30	41	0	0	0	0	1	0	0	0	0	5	4	1	6	14	9	1	0
3/23/2016 7:45	25	0	0	0	0	0	0	0	0	0	2	0	0	1	12	8	2	0
3/23/2016 8:00	30	0	0	0	0	0	0	0	0	0	0	1	2	5	17	5	0	0
3/23/2016 8:15	21	0	0	0	0	0	0	0	0	0	0	4	4	1	10	2	0	0
3/23/2016 8:30	31	0	0	0	0	0	0	0	0	0	5	2	2	10	9	2	1	0
3/23/2016 8:45	30	0	0	0	0	0	0	0	0	0	0	0	1	7	16	5	1	0
3/23/2016 9:00	26	0	0	0	0	0	0	0	0	0	0	0	2	6	12	5	0	1
3/23/2016 9:15	39	0	0	0	0	0	0	0	0	1	5	7	10	5	8	3	0	0
3/23/2016 9:30	32	0	0	0	0	0	0	0	0	4	6	6	6	5	10	1	0	0
3/23/2016 9:45	40	0	0	0	0	0	0	0	0	0	0	0	5	9	17	7	1	1
3/23/2016 10:00	27	0	0	0	0	0	0	0	0	0	1	0	3	10	11	1	0	1
3/23/2016 10:15	47	0	0	0	0	0	0	0	2	2	1	7	7	14	12	2	0	0
3/23/2016 10:30	44	0	0	0	0	0	0	0	1	1	3	2	7	9	13	7	0	1
3/23/2016 10:45	31	0	0	0	0	0	0	0	0	0	0	0	6	4	15	4	2	0
3/23/2016 11:00	37	0	0	0	0	0	0	0	0	0	0	2	9	2	19	4	1	0
3/23/2016 11:15	35	0	0	0	0	0	0	0	0	3	5	6	8	2	4	5	2	0
3/23/2016 11:30	38	0	0	0	0	0	0	0	0	0	4	2	1	12	13	6	0	0
3/23/2016 11:45	35	0	0	0	0	0	0	0	0	1	6	0	0	5	12	8	3	0
3/23/2016 12:00	29	0	0	0	0	0	0	2	1	0	0	0	1	2	14	6	3	0
3/23/2016 12:15	38	0	0	0	0	0	0	0	3	8	0	1	3	4	13	5	1	0
3/23/2016 12:30	37	0	0	0	0	0	0	0	0	0	5	0	8	5	13	5	0	1
3/23/2016 12:45	25	0	0	0	0	0	0	5	0	0	0	4	1	4	7	4	0	0
3/23/2016 13:00	34	0	0	0	0	0	0	0	0	0	0	0	2	9	15	7	1	0
3/23/2016 13:15	42	0	0	0	0	0	0	0	0	0	1	6	7	8	12	4	3	1
3/23/2016 13:30	30	0	0	0	0	0	0	0	0	1	4	5	7	3	5	4	0	1
3/23/2016 13:45	37	0	0	0	0	0	0	0	0	0	0	0	6	6	21	3	1	0
3/23/2016 14:00	21	0	0	0	0	0	0	0	0	0	0	0	1	3	10	6	1	0
3/23/2016 14:15	38	0	0	0	0	0	0	0	0	3	1	4	4	4	16	6	0	0
3/23/2016 14:30	29	0	0	0	0	0	0	0	0	0	0	1	3	11	8	3	3	0
3/23/2016 14:45	34	0	0	0	0	0	0	0	0	0	6	1	7	13	5	2	0	0
3/23/2016 15:00	26	0	0	0	0	0	0	0	0	1	1	0	3	12	8	1	0	0
3/23/2016 15:15	22	0	0	0	0	0	0	0	0	0	2	2	3	3	4	5	3	0
3/23/2016 15:30	28	0	0	0	0	0	0	0	0	0	0	0	2	5	13	8	0	0
3/23/2016 15:45	25	0	0	0	0	0	0	0	0	0	0	0	3	5	12	5	0	0
3/23/2016 16:00	22	0	0	0	0	0	0	0	0	0	0	0	0	7	10	5	0	0
3/23/2016 16:15	34	0	0	0	0	0	0	0	0	0	3	1	0	7	9	12	2	0
3/23/2016 16:30	22	0	0	0	0	0	0	0	0	0	0	0	1	5	8	8	0	0
3/23/2016 16:45	27	0	0	0	0	0	0	0	0	0	0	0	4	4	11	6	2	0
3/23/2016 17:00	28	0	0	0	0	0	0	0	0	0	0	0	4	2	15	5	2	0
3/23/2016 17:15	35	0	0	0	0	0	0	0	0	0	0	0	0	7	16	9	3	0
3/23/2016 17:30	19	0	0	0	0	0	0	0	0	0	0	0	0	5	4	4	4	2
3/23/2016 17:45	19	0	0	0	0	0	0	0	0	0	0	0	1	4	11	3	0	0
3/23/2016 18:00	23	0	0	0	0	0	0	0	0	0	0	0	0	2	16	4	0	1
3/23/2016 18:15	20	0	0	0	0	0	0	0	0	0	0	0	1	4	10	4	1	0
3/23/2016 18:30	17	0	0	0	0	0	0	0	0	0	0	2	0	4	7	4	0	0
3/23/2016 18:45	27	0	0	0	0	0	0	0	0	0	0	0	1	4	13	5	4	0
3/23/2016 19:00	16	0	0	0	0	0	0	0	0	0	2	0	2	3	3	5	1	0
3/23/2016 19:15	13	0	0	0	0	0	0	0	0	0	0	0	0	4	7	1	1	0
3/23/2016 19:30	10	0	0	0	0	0	0	0	0	0	0	3	0	3	3	1	0	0
3/23/2016 19:45	12	0	0	0	0	0	0	0	0	0	0	0	1	4	4	3	0	0
3/23/2016 20:00	10	0	0	0	0	0	0	0	0	0	0	2	0	1	3	4	0	0
3/23/2016 20:15	5	0	0	0	0	0	0	0	0	0	0	0	0	0	4	0	1	0
3/23/2016 20:30	9	0	0	0	0	0	0	0	2	0	0	0	0	2	4	1	0	0
3/23/2016 20:45	9	0	0	0	0	0	0	0	0	0	0	0	0	0	9	0	0	0
3/23/2016 21:00	8	0	0	0	0	0	0	0	0	0	0	0	0	2	0	6	0	0

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602333
Route: AZ-89 (NEAR TOP OF HILL @ 1000' N/O MP341)
Location: N of MP 341

Site Ref: 3
Direction: NB
Latitude: 34.93629
Longitude: -112.43351

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+	
3/23/2016 21:15	7	0	0	0	0	0	0	0	0	0	0	1	0	1	2	3	0	0	
3/23/2016 21:30	7	0	0	0	0	0	0	0	0	0	0	0	1	2	3	1	0	0	
3/23/2016 21:45	3	0	0	0	0	0	0	0	0	0	0	0	1	1	0	1	0	0	
3/23/2016 22:00	2	0	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	
3/23/2016 22:15	5	0	0	0	0	0	0	0	0	0	0	0	1	0	1	3	0	0	
3/23/2016 22:30	5	0	0	0	0	0	0	0	0	0	0	1	0	0	1	1	1	1	
3/23/2016 22:45	3	0	0	0	0	0	0	0	0	0	0	0	2	0	1	0	0	0	
3/23/2016 23:00	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	
3/23/2016 23:15	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
3/23/2016 23:30	3	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	0	0	
3/23/2016 23:45	2	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0	
Day Totals	1914	0	0	0	0	1	1	7	9	25	64	88	170	341	762	351	76	19	
AM Peak Hr	6:15 AM											Average Speed	65.2	Pct > 25 mph		100%			
AM Peak Vol	172											Median Speed	66.5	Pct > 30 mph		100%			
AM PHF	0.796											85th Pct Speed	72.1	Pct > 35 mph		100%			
PM Peak Hr	1:00 PM											95th Pct Speed	75.0	Pct > 40 mph		99%			
PM Peak Vol	143											Pace Speed	62	Pct > 45 mph		98%			
PM PHF	0.851											Percent in Pace	58.5%	Pct > 50 mph		94%			
												Speed Limit	65						
												Percent Speedin	63.1%						

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602334
Route: AZ-89 (NEAR TOP OF HILL @ 1000' N/O MP341)
Location: N of MP 341

Site Ref: 3
Direction: SB
Latitude: 34.93629
Longitude: -112.43351

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 0:00	2	0	2	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 0:15	4	0	2	1	1	0	0	0	0	0	0	0	0	0	25.0%	0.0%
3/23/2016 0:30	2	0	2	0	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 0:45	2	0	1	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 1:00	2	0	1	0	0	0	0	0	0	0	0	0	0	1	0.0%	50.0%
3/23/2016 1:15	3	0	0	1	0	0	0	0	0	1	1	0	0	0	0.0%	66.7%
3/23/2016 1:30	3	0	1	0	0	0	0	0	0	2	0	0	0	0	0.0%	66.7%
3/23/2016 1:45	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 2:00	3	0	0	2	0	0	0	0	0	1	0	0	0	0	0.0%	33.3%
3/23/2016 2:15	0	0	0	0	0	0	0	0	0	0	0	0	0	0	--	--
3/23/2016 2:30	2	0	0	0	0	1	0	0	0	0	0	0	0	1	50.0%	50.0%
3/23/2016 2:45	1	0	0	0	0	0	0	0	0	1	0	0	0	0	0.0%	100.0%
3/23/2016 3:00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	--	--
3/23/2016 3:15	5	0	3	1	0	0	0	0	0	1	0	0	0	0	0.0%	20.0%
3/23/2016 3:30	2	0	0	1	0	0	0	0	0	1	0	0	0	0	0.0%	50.0%
3/23/2016 3:45	0	0	0	0	0	0	0	0	0	0	0	0	0	0	--	--
3/23/2016 4:00	5	0	1	0	0	0	0	0	0	2	1	0	0	1	0.0%	80.0%
3/23/2016 4:15	5	0	1	1	0	0	0	0	1	0	1	1	0	0	0.0%	60.0%
3/23/2016 4:30	2	0	0	0	0	0	0	0	0	2	0	0	0	0	0.0%	100.0%
3/23/2016 4:45	4	0	2	1	0	0	0	0	0	1	0	0	0	0	0.0%	25.0%
3/23/2016 5:00	6	0	1	2	0	0	0	0	0	1	1	0	0	1	0.0%	50.0%
3/23/2016 5:15	6	0	2	1	1	0	0	0	0	2	0	0	0	0	16.7%	33.3%
3/23/2016 5:30	9	0	5	2	0	0	0	0	0	2	0	0	0	0	0.0%	22.2%
3/23/2016 5:45	8	0	1	4	0	1	0	0	1	1	0	0	0	0	12.5%	25.0%
3/23/2016 6:00	8	0	4	4	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 6:15	9	0	4	5	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 6:30	17	0	8	6	0	0	0	0	1	1	0	0	0	1	0.0%	17.6%
3/23/2016 6:45	13	0	3	8	0	0	0	0	0	0	1	1	0	0	0.0%	15.4%
3/23/2016 7:00	17	0	8	6	0	1	1	0	0	0	1	0	0	0	11.8%	5.9%
3/23/2016 7:15	10	0	4	6	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 7:30	9	0	5	3	0	0	0	0	0	1	0	0	0	0	0.0%	11.1%
3/23/2016 7:45	23	0	7	8	4	1	0	0	0	1	2	0	0	0	21.7%	13.0%
3/23/2016 8:00	18	0	10	6	0	0	0	0	0	2	0	0	0	0	0.0%	11.1%
3/23/2016 8:15	18	0	8	6	1	1	0	0	1	0	1	0	0	0	11.1%	11.1%
3/23/2016 8:30	33	0	13	17	0	1	0	0	1	1	0	0	0	0	3.0%	6.1%
3/23/2016 8:45	24	0	9	7	4	0	0	1	0	1	2	0	0	0	20.8%	12.5%
3/23/2016 9:00	26	0	10	9	2	0	0	0	0	2	3	0	0	0	7.7%	19.2%
3/23/2016 9:15	28	0	9	15	0	0	1	0	1	2	0	0	0	0	3.6%	10.7%
3/23/2016 9:30	35	0	16	17	0	0	0	0	1	1	0	0	0	0	0.0%	5.7%
3/23/2016 9:45	26	0	8	8	5	1	0	0	0	3	1	0	0	0	23.1%	15.4%
3/23/2016 10:00	33	0	12	15	0	1	1	0	2	2	0	0	0	0	6.1%	12.1%
3/23/2016 10:15	30	0	17	11	1	0	0	0	0	0	1	0	0	0	3.3%	3.3%
3/23/2016 10:30	34	0	16	12	1	1	0	1	1	1	0	1	0	0	8.8%	8.8%
3/23/2016 10:45	37	0	16	14	3	3	1	0	0	0	0	0	0	0	18.9%	0.0%
3/23/2016 11:00	37	0	18	17	0	0	0	0	0	1	1	0	0	0	0.0%	5.4%
3/23/2016 11:15	31	0	14	12	1	1	0	0	0	3	0	0	0	0	6.5%	9.7%
3/23/2016 11:30	37	1	13	17	2	0	1	1	0	2	0	0	0	0	10.8%	5.4%
3/23/2016 11:45	38	0	19	13	3	1	0	0	1	0	1	0	0	0	10.5%	5.3%

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602334
Route: AZ-89 (NEAR TOP OF HILL @ 1000' N/O MP341)
Location: N of MP 341

Site Ref: 3
Direction: SB
Latitude: 34.93629
Longitude: -112.43351

Date/Time	Total	cls01	cls02	cls03	cls04	cls05	cls06	cls07	cls08	cls09	cls10	cls11	cls12	cls13	pct SU	pct CB
3/23/2016 12:00	29	0	18	8	1	1	0	0	0	0	0	0	0	1	6.9%	3.4%
3/23/2016 12:15	35	2	13	16	1	0	0	0	0	2	1	0	0	0	2.9%	8.6%
3/23/2016 12:30	40	0	14	19	3	0	0	0	0	2	2	0	0	0	7.5%	10.0%
3/23/2016 12:45	42	0	20	18	4	0	0	0	0	0	0	0	0	0	9.5%	0.0%
3/23/2016 13:00	26	0	12	11	2	0	0	0	0	1	0	0	0	0	7.7%	3.8%
3/23/2016 13:15	23	0	8	8	2	1	1	0	1	1	0	0	0	1	17.4%	13.0%
3/23/2016 13:30	32	0	14	14	2	0	0	0	2	0	0	0	0	0	6.3%	6.3%
3/23/2016 13:45	27	0	17	4	0	1	1	1	0	2	0	0	0	1	11.1%	11.1%
3/23/2016 14:00	33	0	20	11	0	1	0	0	0	0	1	0	0	0	3.0%	3.0%
3/23/2016 14:15	36	2	13	19	0	0	0	0	0	1	1	0	0	0	0.0%	5.6%
3/23/2016 14:30	36	0	18	14	0	0	0	1	1	1	0	0	0	1	2.8%	8.3%
3/23/2016 14:45	26	1	9	13	0	0	1	1	0	1	0	0	0	0	7.7%	3.8%
3/23/2016 15:00	54	0	19	26	4	1	2	0	0	1	1	0	0	0	13.0%	3.7%
3/23/2016 15:15	37	0	19	14	0	1	0	1	1	0	0	0	0	1	5.4%	5.4%
3/23/2016 15:30	49	2	29	16	0	0	1	0	1	0	0	0	0	0	2.0%	2.0%
3/23/2016 15:45	54	1	28	19	2	0	0	1	0	1	2	0	0	0	5.6%	5.6%
3/23/2016 16:00	56	0	22	30	0	1	1	0	0	1	1	0	0	0	3.6%	3.6%
3/23/2016 16:15	56	0	23	28	0	3	0	0	0	2	0	0	0	0	5.4%	3.6%
3/23/2016 16:30	54	0	23	27	0	1	1	0	1	1	0	0	0	0	3.7%	3.7%
3/23/2016 16:45	49	0	25	22	0	0	0	0	1	1	0	0	0	0	0.0%	4.1%
3/23/2016 17:00	41	0	25	14	0	1	0	0	0	0	1	0	0	0	2.4%	2.4%
3/23/2016 17:15	36	0	12	21	0	0	0	0	1	1	1	0	0	0	0.0%	8.3%
3/23/2016 17:30	34	1	18	14	0	0	1	0	0	0	0	0	0	0	2.9%	0.0%
3/23/2016 17:45	31	1	12	17	0	0	0	0	0	0	0	0	0	1	0.0%	3.2%
3/23/2016 18:00	20	0	13	5	1	0	0	0	0	0	0	0	0	1	5.0%	5.0%
3/23/2016 18:15	25	0	13	9	0	0	0	0	0	3	0	0	0	0	0.0%	12.0%
3/23/2016 18:30	24	0	12	12	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 18:45	28	0	19	7	1	0	0	0	0	0	0	0	1	0	3.6%	3.6%
3/23/2016 19:00	13	0	4	6	0	0	1	0	0	1	1	0	0	0	7.7%	15.4%
3/23/2016 19:15	14	0	8	5	0	1	0	0	0	0	0	0	0	0	7.1%	0.0%
3/23/2016 19:30	16	0	8	7	0	0	0	0	0	0	0	0	0	1	0.0%	6.3%
3/23/2016 19:45	15	0	7	6	0	0	0	0	0	1	0	1	0	0	0.0%	13.3%
3/23/2016 20:00	8	0	3	4	0	0	0	0	0	1	0	0	0	0	0.0%	12.5%
3/23/2016 20:15	12	0	5	6	0	0	0	0	0	1	0	0	0	0	0.0%	8.3%
3/23/2016 20:30	9	0	6	3	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 20:45	8	0	4	4	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 21:00	9	0	7	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 21:15	12	0	8	0	0	0	0	0	0	0	3	0	0	1	0.0%	33.3%
3/23/2016 21:30	11	0	6	4	0	0	0	0	0	0	1	0	0	0	0.0%	9.1%
3/23/2016 21:45	3	0	2	1	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:00	4	0	2	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 22:15	7	0	6	0	0	0	0	0	0	0	1	0	0	0	0.0%	14.3%
3/23/2016 22:30	9	0	3	5	0	1	0	0	0	0	0	0	0	0	11.1%	0.0%
3/23/2016 22:45	5	0	2	3	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
3/23/2016 23:00	3	0	1	1	0	0	0	0	0	0	1	0	0	0	0.0%	33.3%
3/23/2016 23:15	2	0	1	0	0	1	0	0	0	0	0	0	0	0	50.0%	0.0%
3/23/2016 23:30	2	0	0	1	0	0	0	0	0	1	0	0	0	0	0.0%	50.0%
3/23/2016 23:45	2	0	0	2	0	0	0	0	0	0	0	0	0	0	0.0%	0.0%
Day Totals	1865	11	847	759	52	29	15	8	20	69	36	4	1	14	5.6%	7.7%

AM Peak Hr 11:00 AM
AM Peak Vol 143
AM PHF 0.941
PM Peak Hr 3:45 PM
PM Peak Vol 220
PM PHF 0.982

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602334
Route: AZ-89 (NEAR TOP OF HILL @ 1000' N/O MP341)
Location: N of MP 341

Site Ref: 3
Direction: SB
Latitude: 34.93629
Longitude: -112.43351

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+
3/23/2016 0:00	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1
3/23/2016 0:15	4	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	1	1
3/23/2016 0:30	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0
3/23/2016 0:45	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	0
3/23/2016 1:00	2	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1
3/23/2016 1:15	3	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	0
3/23/2016 1:30	3	0	0	0	0	0	0	0	0	0	0	1	0	0	2	0	0	0
3/23/2016 1:45	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0
3/23/2016 2:00	3	0	0	0	0	0	0	0	0	0	0	0	1	0	1	0	1	0
3/23/2016 2:15	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3/23/2016 2:30	2	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	0
3/23/2016 2:45	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0
3/23/2016 3:00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3/23/2016 3:15	5	0	0	0	0	0	0	0	0	0	0	0	0	1	3	1	0	0
3/23/2016 3:30	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	0
3/23/2016 3:45	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3/23/2016 4:00	5	0	0	0	0	0	0	0	0	0	0	0	0	0	2	2	1	0
3/23/2016 4:15	5	0	0	0	0	0	0	0	0	0	0	1	0	2	1	1	0	0
3/23/2016 4:30	2	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1	0	0
3/23/2016 4:45	4	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	2
3/23/2016 5:00	6	0	0	0	0	0	0	0	0	0	0	0	0	0	2	2	1	1
3/23/2016 5:15	6	0	0	0	0	0	0	0	0	0	0	0	0	1	1	4	0	0
3/23/2016 5:30	9	0	0	0	0	0	0	0	0	0	0	0	0	0	6	3	0	0
3/23/2016 5:45	8	0	0	0	0	0	0	0	0	0	0	0	0	0	2	3	2	1
3/23/2016 6:00	8	0	0	0	0	0	0	0	0	0	0	0	0	0	1	3	3	1
3/23/2016 6:15	9	0	0	0	0	0	0	0	0	0	0	0	0	0	1	2	6	0
3/23/2016 6:30	17	0	0	0	0	0	0	0	0	0	0	0	1	1	5	4	6	0
3/23/2016 6:45	13	0	0	0	0	0	0	0	0	0	0	0	0	0	4	7	1	1
3/23/2016 7:00	17	0	0	0	0	0	0	0	0	0	0	0	1	0	3	6	6	1
3/23/2016 7:15	10	0	0	0	0	0	0	0	0	0	0	0	0	0	1	3	2	4
3/23/2016 7:30	9	0	0	0	0	0	0	0	0	0	0	0	0	0	3	3	3	0
3/23/2016 7:45	23	0	0	0	0	0	0	0	0	0	0	0	1	1	7	7	5	2
3/23/2016 8:00	18	0	0	0	0	0	0	0	0	0	0	0	0	1	2	10	5	0
3/23/2016 8:15	18	0	0	0	0	0	0	0	0	0	0	0	0	2	3	10	1	2
3/23/2016 8:30	33	0	0	0	0	0	0	0	0	0	0	0	0	7	12	8	6	0
3/23/2016 8:45	24	0	0	0	0	0	0	0	0	0	0	0	0	0	9	9	5	1
3/23/2016 9:00	26	0	0	0	0	0	0	0	0	0	0	0	0	3	6	12	3	2
3/23/2016 9:15	28	0	0	0	0	0	0	0	0	0	0	2	0	3	10	10	3	0
3/23/2016 9:30	35	0	0	0	0	0	0	0	0	0	0	0	1	2	10	19	2	1
3/23/2016 9:45	26	0	0	0	0	0	0	0	0	0	0	0	0	1	13	9	3	0
3/23/2016 10:00	33	0	0	0	0	0	0	0	0	0	0	0	0	3	9	15	3	3
3/23/2016 10:15	30	0	0	0	0	0	0	0	0	0	0	0	0	3	6	16	5	0
3/23/2016 10:30	34	0	0	0	0	0	0	0	0	0	0	0	0	4	16	7	5	2
3/23/2016 10:45	37	0	0	0	0	0	0	0	0	0	0	1	1	3	17	10	5	0
3/23/2016 11:00	37	0	0	0	0	0	0	0	0	0	0	0	0	3	14	17	2	1
3/23/2016 11:15	31	0	0	0	0	0	0	0	0	0	0	0	1	4	12	13	1	0
3/23/2016 11:30	37	0	0	0	0	0	0	0	0	0	0	0	1	0	17	10	8	1
3/23/2016 11:45	38	0	0	0	0	0	0	0	0	0	0	0	0	3	10	19	6	0
3/23/2016 12:00	29	0	0	0	0	0	0	0	0	0	0	0	0	8	12	8	1	0
3/23/2016 12:15	35	0	0	0	0	0	0	0	0	0	0	0	0	3	13	16	2	1
3/23/2016 12:30	40	0	0	0	0	0	0	0	0	0	0	0	0	3	19	15	3	0
3/23/2016 12:45	42	0	0	0	0	0	0	0	0	0	0	0	2	6	19	10	5	0
3/23/2016 13:00	26	0	0	0	0	0	0	0	0	0	0	0	1	4	7	10	2	2
3/23/2016 13:15	23	0	0	0	0	0	0	0	0	0	0	0	1	3	9	7	3	0
3/23/2016 13:30	32	0	0	0	0	0	0	0	0	0	2	0	0	6	10	11	3	0
3/23/2016 13:45	27	0	0	0	0	0	0	0	0	0	0	0	1	4	11	8	2	1
3/23/2016 14:00	33	0	0	0	0	0	0	0	0	0	0	0	0	0	18	14	1	0
3/23/2016 14:15	36	0	0	0	0	0	0	0	0	0	0	0	2	4	14	10	5	1
3/23/2016 14:30	36	0	0	0	0	0	0	0	0	0	0	0	1	3	18	10	4	0
3/23/2016 14:45	26	0	0	0	0	0	0	0	0	0	0	0	1	3	9	9	4	0
3/23/2016 15:00	54	0	0	0	0	0	0	0	0	0	0	0	0	5	22	19	5	3
3/23/2016 15:15	37	0	0	0	0	0	0	0	0	0	0	0	1	4	16	13	3	0
3/23/2016 15:30	49	0	0	0	0	0	0	0	0	0	0	0	0	5	16	25	2	1
3/23/2016 15:45	54	0	0	0	0	0	0	0	0	0	0	1	0	3	23	21	4	2
3/23/2016 16:00	56	0	0	0	0	0	0	0	0	0	0	0	0	3	22	20	10	1
3/23/2016 16:15	56	0	0	0	0	0	0	0	0	0	0	0	2	13	24	12	5	0
3/23/2016 16:30	54	0	0	0	0	0	0	0	0	0	0	0	1	12	24	14	1	2
3/23/2016 16:45	49	0	0	0	0	0	0	0	0	0	0	0	2	0	15	23	7	2
3/23/2016 17:00	41	0	0	0	0	0	0	0	0	0	0	1	0	2	19	13	4	2
3/23/2016 17:15	36	0	0	0	0	0	0	0	0	0	0	0	0	0	12	19	4	1
3/23/2016 17:30	34	0	0	0	0	0	0	0	0	0	0	0	0	2	8	19	5	0
3/23/2016 17:45	31	0	0	0	0	0	0	0	0	0	0	0	1	0	10	17	3	0
3/23/2016 18:00	20	0	0	0	0	0	0	0	0	0	0	0	1	0	9	8	2	0
3/23/2016 18:15	25	0	0	0	0	0	0	0	0	0	0	0	0	0	11	11	2	1
3/23/2016 18:30	24	0	0	0	0	0	0	0	0	0	0	0	0	1	8	7	7	1
3/23/2016 18:45	28	0	0	0	0	0	0	0	0	0	0	0	0	1	9	12	3	3
3/23/2016 19:00	13	0	0	0	0	0	0	0	0	0	0	0	0					

Traffic Research & Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Client: Burgess & Niple, Inc.
File Number: 1602334
Route: AZ-89 (NEAR TOP OF HILL @ 1000' N/O MP341)
Location: N of MP 341

Site Ref: 3
Direction: SB
Latitude: 34.93629
Longitude: -112.43351

Date/Time	Total	0-5	5-10	10-15	15-20	20-25	25-30	30-35	35-40	40-45	45-50	50-55	55-60	60-65	65-70	70-75	75-80	80+	
3/23/2016 21:15	12	0	0	0	0	0	0	0	0	0	1	0	0	0	5	4	2	0	
3/23/2016 21:30	11	0	0	0	0	0	0	0	0	0	0	0	0	0	3	2	5	1	
3/23/2016 21:45	3	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	2	0	
3/23/2016 22:00	4	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	0	1	
3/23/2016 22:15	7	0	0	0	0	0	0	0	0	0	0	0	0	0	3	3	1	0	
3/23/2016 22:30	9	0	0	0	0	0	0	0	0	0	0	0	0	1	3	3	2	0	
3/23/2016 22:45	5	0	0	0	0	0	0	0	0	0	0	0	0	0	2	3	0	0	
3/23/2016 23:00	3	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1	1	0	
3/23/2016 23:15	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	
3/23/2016 23:30	2	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1	
3/23/2016 23:45	2	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	0	
Day Totals	1865	0	0	0	0	0	0	0	0	0	3	8	29	156	677	688	242	62	
AM Peak Hr	11:00 AM											Average Speed	70.5	Pct > 25 mph		100%			
AM Peak Vol	143											Median Speed	70.6	Pct > 30 mph		100%			
AM PHF	0.941											85th Pct Speed	75.7	Pct > 35 mph		100%			
PM Peak Hr	3:45 PM											95th Pct Speed	79.2	Pct > 40 mph		100%			
PM Peak Vol	220											Pace Speed	65	Pct > 45 mph		100%			
PM PHF	0.982											Percent in Pace	72.5%	Pct > 50 mph		100%			
												Speed Limit	65						
												Percent Speedin	89.5%						

Traffic Research and Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500

Site ID	File Name	Route	Location	Direction	Count Type	Count Dur	Start Date	Start Time	Avg Vol	AM PkHr	AM PkVol	AM PHF	PM PkHr	PM PkVol	PM PHF	Day Corr	Dir Split	pctSU	pctCB	Avg Spd	Spd 50pct	Spd 85pct
1	1602329	AZ-89	N of E RD 3 N	NB	SPD	24	3/23/2016	0:00	6470	11:15	391	0.9399	16:00	615	0.9433	1.0000	50.2%	2.5%	2.8%	52.202	52.3	57.8
1	1602330	AZ-89	N of E RD 3 N	SB	SPD	24	3/23/2016	0:00	6431	6:30	563	0.8965	15:15	489	0.8989	1.0000	49.8%	2.2%	2.9%	45.554	45.8	51.7
2	1602331	AZ-89	Btwn BALD EAGLE TRAIL & ROLLING HILLS R	NB	SPD	24	3/23/2016	0:00	4631	11:15	282	0.8924	16:30	466	0.9173	1.0000	50.5%	1.8%	4.9%	62.349	62.8	67.9
2	1602332	AZ-89	Btwn BALD EAGLE TRAIL & ROLLING HILLS R	SB	SPD	24	3/23/2016	0:00	4531	6:30	459	0.9035	15:00	328	0.9111	1.0000	49.5%	3.7%	3.7%	64.995	66.0	71.6
3	1602333	AZ-89	N of MP 341	NB	SPD	24	3/23/2016	0:00	1914	6:15	172	0.7963	13:00	143	0.8512	1.0000	50.6%	2.4%	12.4%	65.189	66.5	72.0
3	1602334	AZ-89	N of MP 341	SB	SPD	24	3/23/2016	0:00	1865	11:00	143	0.9408	15:45	220	0.9821	1.0000	49.4%	5.6%	7.7%	70.490	70.4	75.5

Traffic Research and Analysis, Inc.
3844 East Indian School Road
Phoenix, AZ 85018
(602) 840-1500


Site ID	File Name	Route	Location	Direction	Latitude	Longitude	Comments
1	1602329	AZ-89	N of E RD 3 N	NB	34.7784	-112.4528	
1	1602330	AZ-89	N of E RD 3 N	SB	34.7784	-112.4528	
2	1602331	AZ-89	Btwn BALD EAGLE TRAIL & ROLLING HILLS R	NB	34.8588	-112.4687	
2	1602332	AZ-89	Btwn BALD EAGLE TRAIL & ROLLING HILLS R	SB	34.8588	-112.4687	SPC ADJ 939mm
3	1602333	AZ-89	N of MP 341	NB	34.9363	-112.4335	NEAR TOP OF HILL @ 1000' N/O MP341
3	1602334	AZ-89	N of MP 341	SB	34.9363	-112.4335	NEAR TOP OF HILL @ 1000' N/O MP341

Traffic Research & Analysis, Inc.
3844 E. Indian School Rd.
Phoenix, AZ 85018
(602) 840-1500 FAX (602) 840-1577


Job Number	File ID	North / South Streets	East / West Streets	Start Date / Time	End Date /Time	Count Intvl	Count Total	Peak Hour	Peak Hr Total	Peak Hr Factor
15146	1602336	AZ 89	E RD 3 N	3/23/16 7:00	3/23/16 8:45	15	2371	7:00 AM	1254	0.8831
15146	1602336	AZ 89	E RD 3 N	3/23/16 16:00	3/23/16 17:45	15	2893	4:15 PM	1518	0.9806
15146	1602337	AZ89	W RD 4 N	3/23/16 7:00	3/23/16 8:45	15	1672	7:00 AM	920	0.8915
15146	1602337	AZ89	W RD 4 N	3/23/16 16:00	3/23/16 17:45	15	2135	4:00 PM	1110	0.9158
15146	1602338	AZ 89	ROLLING HILLS RD	3/23/16 7:00	3/23/16 8:45	15	1149	7:00 AM	642	0.9331
15146	1602338	AZ 89	ROLLING HILLS RD	3/23/16 16:00	3/23/16 17:45	15	1494	4:00 PM	784	0.9159
15146	1602339	AZ 89	BIG CHINO RD	3/23/16 7:00	3/23/16 8:45	15	1046	7:00 AM	592	0.9024
15146	1602339	AZ 89	BIG CHINO RD	3/23/16 16:00	3/23/16 17:45	15	1496	4:00 PM	787	0.9789
15146	1602340	AZ 89	BRAMBLE DR	3/23/16 7:00	3/23/16 8:45	15	554	7:00 AM	295	0.8676
15146	1602340	AZ 89	BRAMBLE DR	3/23/14 16:00	3/23/14 17:45	15	857	4:00 PM	476	0.9597




Intersection TMC: 1602336
Count Date: 3/23/2016



	From North				From East				From South				From West				INTSEC
	AZ 89				E RD 3 N				AZ 89				E RD 3 N				
Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
7:00	5	139	21	0	11	13	5	0	9	46	5	0	10	9	35	0	308
7:15	2	130	24	0	13	18	13	0	21	66	9	0	17	14	28	0	355
7:30	7	93	13	0	7	7	3	0	18	52	8	0	15	15	38	0	276
7:45	3	113	11	0	12	7	9	0	17	72	6	0	11	11	43	0	315
8:00	1	119	7	0	12	3	2	0	16	62	4	0	13	8	28	0	275
8:15	5	116	10	0	11	6	3	0	22	72	5	0	9	5	41	0	305
8:30	0	104	5	0	8	5	5	0	31	51	7	0	12	4	24	0	256
8:45	1	102	10	0	13	6	0	0	30	76	6	0	7	5	25	0	281
Total	24	916	101	0	87	65	40	0	164	497	50	0	94	71	262	0	2371
Pk Hr																	7:00 AM
Pk Vol	17	475	69	0	43	45	30	0	65	236	28	0	53	49	144	0	1254
PHF	0.607	0.854	0.719	0.000	0.827	0.625	0.577	0.000	0.774	0.819	0.778	0.000	0.779	0.817	0.837	0.000	0.883



Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Pk Hr																	
Pk Vol																	
PHF																	



Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
16:00	2	113	6	0	11	7	4	0	41	131	6	0	30	12	18	0	381
16:15	3	106	7	0	6	3	0	0	48	132	19	0	8	10	26	0	368
16:30	7	99	3	0	8	6	3	0	55	142	10	0	14	11	20	0	378
16:45	5	112	8	0	6	10	4	0	47	127	9	0	17	12	30	0	387
17:00	3	99	8	0	11	6	3	0	52	135	14	0	10	9	35	0	385
17:15	2	80	4	0	12	7	4	0	39	122	6	0	14	8	28	0	326
17:30	2	95	8	0	8	8	7	0	49	135	17	0	12	7	15	0	363
17:45	1	65	4	0	10	4	6	0	44	129	8	0	12	5	17	0	305
Total	25	769	48	0	72	51	31	0	375	1053	89	0	117	74	189	0	2893
Pk Hr	4:15 PM																
Pk Vol	18	416	26	0	31	25	10	0	202	536	52	0	49	42	111	0	1518
PHF	0.643	0.929	0.813	0.000	0.705	0.625	0.625	0.000	0.918	0.944	0.684	0.000	0.721	0.875	0.793	0.000	0.981

Intersection Statistics

Per	Peak Hour	Pk Hr Vol	Peak Intvl	Pk Intvl Vol	PHF
AM	7:00 AM	1254	7:15 AM	355	0.883
MID					
PM	4:15 PM	1518	4:45 PM	387	0.981

Peak Hour Statistics by Approach

Per	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF
AM	7:00 AM	561	0.850	7:00 AM	118	0.670	8:00 AM	382	0.853	7:00 AM	246	0.904
MID												
PM	4:00 PM	471	0.942	4:45 PM	86	0.935	4:15 PM	790	0.954	4:00 PM	208	0.867


Comments

Approach & Departure Volumes (No Peds)


Per	Approach	Depart	Approach	Depart	Approach	Depart	Approach	Depart
AM	1041	631	192	145	711	1265	427	330
MID	0	0	0	0	0	0	0	0
PM	842	1201	154	188	1517	1030	380	474




Intersection TMC: 1602337
Count Date: 3/23/2016



	From North				From East				From South				From West				INTSEC
	AZ89				W RD 4 N				AZ89				W RD 4 N				
Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
7:00	0	126	9	0	6	0	6	0	2	63	1	0	5	3	18	0	239
7:15	1	140	7	0	4	1	6	0	5	77	3	0	3	3	8	0	258
7:30	3	115	5	0	8	1	4	0	7	57	3	0	5	1	8	0	217
7:45	4	104	3	0	7	1	1	0	4	67	4	0	4	1	6	0	206
8:00	1	118	3	0	4	0	3	0	0	63	3	0	8	0	11	0	214
8:15	0	103	1	0	6	0	2	0	6	59	3	0	2	1	3	0	186
8:30	1	96	3	0	6	0	1	0	2	54	0	0	4	0	8	0	175
8:45	0	80	1	0	4	2	2	0	3	70	1	0	6	0	8	0	177
Total	10	882	32	0	45	5	25	0	29	510	18	0	37	9	70	0	1672
Pk Hr																	7:00 AM
Pk Vol	8	485	24	0	25	3	17	0	18	264	11	0	17	8	40	0	920
PHF	0.500	0.866	0.667	0.000	0.781	0.750	0.708	0.000	0.643	0.857	0.688	0.000	0.850	0.667	0.556	0.000	0.891



Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Pk Hr																	
Pk Vol																	
PHF																	



Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
16:00	2	97	8	0	3	2	5	0	11	141	18	0	3	2	11	0	303
16:15	3	89	3	0	2	0	5	0	5	125	6	0	4	0	10	0	252
16:30	6	87	1	0	5	0	2	0	15	133	8	0	3	2	6	0	268
16:45	0	102	4	0	4	4	10	0	10	134	8	0	3	4	4	0	287
17:00	6	90	5	0	8	2	8	0	10	135	8	0	1	1	4	0	278
17:15	0	77	2	0	4	2	7	0	10	137	4	0	2	1	9	0	255
17:30	5	72	3	0	4	2	5	0	7	120	8	0	1	0	8	0	235
17:45	1	69	3	0	3	1	8	0	16	130	10	0	4	3	9	0	257
Total	23	683	29	0	33	13	50	0	84	1055	70	0	21	13	61	0	2135
Pk Hr	4:00 PM																
Pk Vol	11	375	16	0	14	6	22	0	41	533	40	0	13	8	31	0	1110
PHF	0.458	0.919	0.500	0.000	0.700	0.375	0.550	0.000	0.683	0.945	0.556	0.000	0.813	0.500	0.705	0.000	0.916

Intersection Statistics

Per	Peak Hour	Pk Hr Vol	Peak Intvl	Pk Intvl Vol	PHF
AM	7:00 AM	920	7:15 AM	258	0.891
MID					
PM	4:00 PM	1110	4:00 PM	303	0.916

Peak Hour Statistics by Approach

Per	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF
AM	7:00 AM	517	0.873	7:00 AM	45	0.865	7:00 AM	293	0.862	7:00 AM	65	0.625
MID												
PM	4:00 PM	402	0.939	4:45 PM	60	0.833	4:00 PM	614	0.903	4:00 PM	52	0.813


Comments

Approach & Departure Volumes (No Peds)


Per	Approach	Depart	Approach	Depart	Approach	Depart	Approach	Depart
AM	924	572	75	37	557	997	116	66
MID	0	0	0	0	0	0	0	0
PM	735	1126	96	106	1209	777	95	126




Intersection TMC: 1602338
Count Date: 3/23/2016



	From North				From East				From South				From West				INTSEC
	AZ 89				ROLLING HILLS RD				AZ 89				ROLLING HILLS RD				
Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
7:00	0	116	1	0	0	0	0	0	5	36	0	0	2	0	11	0	171
7:15	0	106	0	0	0	0	0	0	4	53	0	0	0	0	9	0	172
7:30	0	82	2	0	0	0	0	0	11	52	0	0	0	0	9	0	156
7:45	0	86	4	0	0	0	0	0	3	36	0	0	0	0	14	0	143
8:00	0	87	2	0	0	0	0	0	1	49	0	0	2	0	7	0	148
8:15	0	63	3	0	0	0	0	0	3	47	0	0	1	0	6	0	123
8:30	0	70	2	0	0	0	0	0	3	26	0	0	1	0	10	0	112
8:45	0	60	0	0	0	0	0	0	3	53	0	0	2	0	6	0	124
Total	0	670	14	0	0	0	0	0	33	352	0	0	8	0	72	0	1149
Pk Hr																	7:00 AM
Pk Vol	0	390	7	0	0	0	0	0	23	177	0	0	2	0	43	0	642
PHF	0.000	0.841	0.438	0.000	0.000	0.000	0.000	0.000	0.523	0.835	0.000	0.000	0.250	0.000	0.768	0.000	0.933



Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Pk Hr																	
Pk Vol																	
PHF																	



Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
16:00	0	79	4	0	0	0	0	0	10	116	0	0	2	0	3	0	214
16:15	0	62	1	0	0	0	0	0	6	95	0	0	0	0	5	0	169
16:30	0	79	2	0	0	0	0	0	4	114	0	0	3	0	9	0	211
16:45	0	72	1	0	0	0	0	0	6	98	0	0	4	0	9	0	190
17:00	0	54	0	0	0	0	0	0	13	112	0	0	0	0	6	0	185
17:15	0	56	2	0	0	0	0	0	11	106	0	0	1	0	3	0	179
17:30	0	66	4	0	0	0	0	0	8	101	0	0	1	0	9	0	189
17:45	0	42	1	0	0	0	0	0	7	104	0	0	2	0	1	0	157
Total	0	510	15	0	0	0	0	0	65	846	0	0	13	0	45	0	1494
Pk Hr	4:00 PM																
Pk Vol	0	292	8	0	0	0	0	0	26	423	0	0	9	0	26	0	784
PHF	0.000	0.924	0.500	0.000	0.000	0.000	0.000	0.000	0.650	0.912	0.000	0.000	0.563	0.000	0.722	0.000	0.916

Intersection Statistics

Per	Peak Hour	Pk Hr Vol	Peak Intvl	Pk Intvl Vol	PHF
AM	7:00 AM	642	7:15 AM	172	0.933
MID					
PM	4:00 PM	784	4:00 PM	214	0.916

Peak Hour Statistics by Approach

Per	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF
AM	7:00 AM	397	0.848				7:15 AM	209	0.829	7:00 AM	45	0.804
MID												
PM	4:00 PM	300	0.904				4:30 PM	464	0.928	4:15 PM	36	0.692


Comments

Approach & Departure Volumes (No Peds)


Per	Approach	Depart	Approach	Depart	Approach	Depart	Approach	Depart
AM	684	360	0	0	385	742	80	47
MID	0	0	0	0	0	0	0	0
PM	525	859	0	0	911	555	58	80




Intersection TMC: 1602339
Count Date: 3/23/2016



	From North				From East				From South				From West				INTSEC	
	AZ 89				BIG CHINO RD				AZ 89				BIG CHINO RD					
Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL	
7:00	0	67	0	0	0	0	0	0	0	11	31	0	0	1	0	54	0	164
7:15	0	44	5	0	0	0	0	0	0	13	42	0	0	4	0	48	0	156
7:30	0	40	2	0	0	0	0	0	0	16	38	0	0	2	0	34	0	132
7:45	0	52	4	0	0	0	0	0	0	11	25	0	0	5	0	43	0	140
8:00	0	39	1	0	0	0	0	0	0	8	40	0	0	2	0	38	0	128
8:15	0	31	2	0	0	0	0	0	0	12	36	0	0	1	0	23	0	105
8:30	0	46	4	0	0	0	0	0	0	10	26	0	0	0	0	19	0	105
8:45	0	41	2	0	0	0	0	0	0	14	32	0	0	5	0	22	0	116
Total	0	360	20	0	0	0	0	0	0	95	270	0	0	20	0	281	0	1046
Pk Hr	7:00 AM																	
Pk Vol	0	203	11	0	0	0	0	0	0	51	136	0	0	12	0	179	0	592
PHF	0.000	0.757	0.550	0.000	0.000	0.000	0.000	0.000	0.000	0.797	0.810	0.000	0.000	0.600	0.000	0.829	0.000	0.902



Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL



Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
16:00	0	67	8	0	0	0	0	0	41	59	0	0	4	0	20	0	199
16:15	0	57	11	0	0	0	0	0	50	63	0	0	5	0	15	0	201
16:30	0	58	9	0	0	0	0	0	54	48	0	0	8	0	24	0	201
16:45	0	52	6	0	0	0	0	0	40	62	0	0	5	0	21	0	186
17:00	0	46	5	0	0	0	0	0	58	64	0	0	0	0	15	0	188
17:15	0	46	4	0	0	0	0	0	44	65	0	0	8	0	15	0	182
17:30	0	54	4	0	0	0	0	0	45	50	0	0	4	0	15	0	172
17:45	0	34	4	0	0	0	0	0	51	61	0	0	5	0	12	0	167
Total	0	414	51	0	0	0	0	0	383	472	0	0	39	0	137	0	1496
Pk Hr	4:00 PM																
Pk Vol	0	234	34	0	0	0	0	0	185	232	0	0	22	0	80	0	787
PHF	0.000	0.873	0.773	0.000	0.000	0.000	0.000	0.000	0.856	0.921	0.000	0.000	0.688	0.000	0.833	0.000	0.979

Intersection Statistics

Per	Peak Hour	Pk Hr Vol	Peak Intvl	Pk Intvl Vol	PHF
AM	7:00 AM	592	7:00 AM	164	0.902
MID					
PM	4:00 PM	787	4:15 PM	201	0.979

Peak Hour Statistics by Approach

Per	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF
AM	7:00 AM	214	0.799				7:15 AM	193	0.877	7:00 AM	191	0.868
MID												
PM	4:00 PM	268	0.893				4:15 PM	439	0.900	4:00 PM	102	0.797


Comments

Approach & Departure Volumes (No Peds)


Per	Approach	Depart	Approach	Depart	Approach	Depart	Approach	Depart
AM	380	290	0	0	365	641	301	115
MID	0	0	0	0	0	0	0	0
PM	465	511	0	0	855	551	176	434




Intersection TMC: 1602340
Count Date: 3/23/2016



	From North				From East				From South				From West				INTSEC	
	AZ 89				BRAMBLE DR				AZ 89				BRAMBLE DR					
Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL	
7:00	0	16	0	0	2	1	0	0	0	4	32	0	0	2	0	28	0	85
7:15	0	11	0	0	1	0	0	0	0	8	36	0	0	0	0	19	0	75
7:30	0	6	0	0	1	0	0	0	0	5	28	0	0	4	0	20	0	64
7:45	0	24	0	0	3	0	0	0	0	3	22	1	0	0	0	18	0	71
8:00	0	16	1	0	1	0	0	0	0	2	32	2	0	0	0	9	0	63
8:15	0	23	0	0	0	0	0	0	0	5	25	0	0	1	0	9	0	63
8:30	0	30	0	0	0	0	0	0	0	2	26	0	0	0	0	14	0	72
8:45	0	25	0	0	0	0	0	0	0	3	26	0	0	0	0	7	0	61
Total	0	151	1	0	8	1	0	0	0	32	227	3	0	7	0	124	0	554
Pk Hr	7:00 AM																	
Pk Vol	0	57	0	0	7	1	0	0	0	20	118	1	0	6	0	85	0	295
PHF	0.000	0.594	0.000	0.000	0.583	0.250	0.000	0.000	0.625	0.819	0.250	0.000	0.375	0.000	0.759	0.000		0.868



Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Pk Hr																	
Pk Vol																	
PHF																	



Time	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	LT	Thru	RT	Ped	TOTAL
16:00	0	60	5	0	1	0	0	0	20	21	1	0	0	0	12	0	120
16:15	0	43	7	0	1	0	0	0	19	37	2	0	0	0	15	0	124
16:30	1	50	6	0	0	0	0	0	21	22	0	0	1	0	14	0	115
16:45	0	47	2	0	1	0	0	0	30	26	0	0	0	2	9	0	117
17:00	0	41	0	0	1	0	0	0	21	27	3	0	2	0	8	0	103
17:15	0	39	2	0	1	0	0	0	25	32	1	0	0	0	9	0	109
17:30	0	33	2	0	1	0	0	0	21	16	2	0	0	0	10	0	85
17:45	0	24	1	0	0	0	0	0	27	23	0	0	0	0	9	0	84
Total	1	337	25	0	6	0	0	0	184	204	9	0	3	2	86	0	857
Pk Hr	4:00 PM																
Pk Vol	1	200	20	0	3	0	0	0	90	106	3	0	1	2	50	0	476
PHF	0.250	0.833	0.714	0.000	0.750	0.000	0.000	0.000	0.750	0.716	0.375	0.000	0.250	0.250	0.833	0.000	0.960

Intersection Statistics

Per	Peak Hour	Pk Hr Vol	Peak Intvl	Pk Intvl Vol	PHF
AM	7:00 AM	295	7:00 AM	85	0.868
MID					
PM	4:00 PM	476	4:15 PM	124	0.960

Peak Hour Statistics by Approach

Per	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF	Peak Hour	Vol	PHF
AM	8:00 AM	95	0.792	7:00 AM	8	0.667	7:00 AM	139	0.790	7:00 AM	91	0.758
MID												
PM	4:00 PM	221	0.850	4:45 PM	4	1.000	4:15 PM	208	0.897	4:00 PM	53	0.883

Comments

Approach & Departure Volumes (No Peds)


Per	Approach	Depart	Approach	Depart	Approach	Depart	Approach	Depart
AM	152	234	9	3	262	283	131	34
MID	0	0	0	0	0	0	0	0
PM	363	207	6	12	397	429	91	209

APPENDIX WP1-4

2016 HCS and SIDRA Results

HCS 2010 Signalized Intersection Results Summary

General Information				Intersection Information	
Agency	Burgess & Niple			Duration, h	0.25
Analyst	KMS	Analysis Date	May 6, 2016	Area Type	Other
Jurisdiction	ADOT/CYMPO	Time Period	AM Peak Hour	PHF	0.90
Urban Street	SR 89	Analysis Year	2016	Analysis Period	1 > 7:00
Intersection	SR 89 and Road 3N	File Name	01_Road 3N_AM_Existing Conditions.xus		
Project Description	SR 89 Transportation Study				



Demand Information	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Demand (v), veh/h	55	50	145	45	45	30	65	235	30	20	475	70



Signal Information											
Cycle, s	100.0	Reference Phase	2								
Offset, s	0	Reference Point	End								
Uncoordinated	No	Simult. Gap E/W	On	Green	2.8	2.4	57.2	19.7	0.0	0.0	
Force Mode	Fixed	Simult. Gap N/S	On	Yellow	4.0	0.0	4.0	4.0	0.0	0.0	
				Red	2.0	0.0	2.0	2.0	0.0	0.0	

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		25.7		25.7	11.2	65.6	8.8	63.2
Change Period, ($Y+R_c$), s		6.0		6.0	6.0	6.0	6.0	6.0
Max Allow Headway (MAH), s		4.4		4.4	4.0	0.0	4.0	0.0
Queue Clearance Time (g_s), s		14.2		18.3	3.6		2.5	
Green Extension Time (g_e), s		1.5		1.4	0.2	0.0	0.0	0.0
Phase Call Probability		1.00		1.00	0.87		0.46	
Max Out Probability		0.01		0.03	0.00		0.00	

Movement Group Results	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	61	217		50	83		72	149	146	22	309	297
Adjusted Saturation Flow Rate (s), veh/h/ln	1309	1643		1160	1738		1774	1810	1738	1774	1810	1728
Queue Service Time (g_s), s	4.1	12.2		4.2	4.0		1.6	3.6	3.7	0.5	8.8	8.9
Cycle Queue Clearance Time (g_c), s	8.1	12.2		16.3	4.0		1.6	3.6	3.7	0.5	8.8	8.9
Green Ratio (g/C)	0.20	0.20		0.20	0.20		0.62	0.60	0.60	0.60	0.57	0.57
Capacity (c), veh/h	278	323		160	342		554	1078	1035	702	1034	987
Volume-to-Capacity Ratio (X)	0.220	0.670		0.312	0.244		0.130	0.138	0.141	0.032	0.299	0.301
Back of Queue (Q), ft/ln (50 th percentile)	34.5	128		31.8	43.9		13.6	33.5	32.6	4.4	84	80.2
Back of Queue (Q), veh/ln (50 th percentile)	1.4	5.1		1.3	1.8		0.5	1.3	1.3	0.2	3.3	3.2
Queue Storage Ratio (RQ) (50 th percentile)	0.28	0.00		0.32	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Uniform Delay (d_1), s/veh	37.2	37.2		44.6	33.9		7.8	8.9	8.9	8.2	11.1	11.1
Incremental Delay (d_2), s/veh	0.4	2.4		1.1	0.4		0.1	0.3	0.3	0.0	0.7	0.8
Initial Queue Delay (d_3), s/veh	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Control Delay (d), s/veh	37.6	39.6		45.7	34.3		8.0	9.2	9.2	8.2	11.8	11.9
Level of Service (LOS)	D	D		D	C		A	A	A	A	B	B
Approach Delay, s/veh / LOS	39.1	D		38.6	D		8.9	A		11.7	B	
Intersection Delay, s/veh / LOS	19.0						B					

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.8	C	2.8	C	2.2	B	2.2	B
Bicycle LOS Score / LOS	0.9	A	0.7	A	0.8	A	1.0	A

HCS 2010 Signalized Intersection Results Summary

General Information						Intersection Information															
Agency		Burgess & Niple				Duration, h		0.25													
Analyst		KMS		Analysis Date		May 6, 2016		Area Type		Other											
Jurisdiction		ADOT/CYMPO		Time Period		PM Peak Hour		PHF		0.90											
Urban Street		SR 89		Analysis Year		2016		Analysis Period		1> 7:00											
Intersection		SR 89 and Road 3N		File Name		01_Road 3N_PM_Existing Conditions.xus															
Project Description		SR 89 Transportation Study																			
Demand Information						EB			WB			NB			SB						
Approach Movement						L	T	R	L	T	R	L	T	R	L	T	R				
Demand (v), veh/h						70	45	95	30	25	10	190	530	45	20	430	25				
Signal Information																					
Cycle, s	100.0	Reference Phase	2	Green	2.8		4.2	60.7	14.3	0.0	0.0	1	2	3	4						
Offset, s	0	Reference Point	End	Yellow	4.0		0.0	4.0	4.0	0.0	0.0	5	6	7	8						
Uncoordinated	No	Simult. Gap E/W	On	Red	2.0		0.0	2.0	2.0	0.0	0.0										
Force Mode	Fixed	Simult. Gap N/S	On																		
Timer Results						EBL		EBT		WBL		WBT		NBL		NBT		SBL		SBT	
Assigned Phase								4				8		5		2		1		6	
Case Number								6.0				6.0		1.1		4.0		1.1		4.0	
Phase Duration, s								20.3				20.3		13.0		70.9		8.8		66.7	
Change Period, ($Y+R_c$), s								6.0				6.0		6.0		6.0		6.0		6.0	
Max Allow Headway (MAH), s								4.4				4.4		4.0		0.0		4.0		0.0	
Queue Clearance Time (g_s), s								10.9				13.4		6.3				2.5			
Green Extension Time (g_e), s								1.0				0.9		0.7		0.0		0.0		0.0	
Phase Call Probability								1.00				1.00		1.00				0.46			
Max Out Probability								0.01				0.04		0.00				0.00			
Movement Group Results						EB			WB			NB			SB						
Approach Movement						L	T	R	L	T	R	L	T	R	L	T	R				
Assigned Movement						7	4	14	3	8	18	5	2	12	1	6	16				
Adjusted Flow Rate (v), veh/h						78	156		33	39		211	323	315	22	255	251				
Adjusted Saturation Flow Rate (s), veh/h/ln						1363	1660		1226	1772		1774	1810	1759	1774	1810	1774				
Queue Service Time (g_s), s						5.3	8.9		2.6	1.9		4.3	7.6	7.7	0.5	6.4	6.5				
Cycle Queue Clearance Time (g_c), s						7.2	8.9		11.4	1.9		4.3	7.6	7.7	0.5	6.4	6.5				
Green Ratio (g/C)						0.14	0.14		0.14	0.14		0.68	0.65	0.65	0.63	0.61	0.61				
Capacity (c), veh/h						242	238		140	254		678	1174	1141	555	1097	1076				
Volume-to-Capacity Ratio (X)						0.321	0.653		0.238	0.153		0.312	0.275	0.276	0.040	0.232	0.233				
Back of Queue (Q), ft/ln (50 th percentile)						46.7	95.6		21.4	21.5		33.6	66.9	64.4	3.9	59.4	57.6				
Back of Queue (Q), veh/ln (50 th percentile)						1.8	3.8		0.8	0.9		1.3	2.6	2.6	0.2	2.3	2.3				
Queue Storage Ratio (RQ) (50 th percentile)						0.37	0.00		0.21	0.00		0.00	0.00	0.00	0.00	0.00	0.00				
Uniform Delay (d_1), s/veh						40.6	40.5		45.8	37.5		6.2	7.5	7.5	6.9	9.0	9.0				
Incremental Delay (d_2), s/veh						0.8	3.0		0.9	0.3		0.3	0.6	0.6	0.0	0.5	0.5				
Initial Queue Delay (d_3), s/veh						0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0				
Control Delay (d), s/veh						41.4	43.5		46.7	37.8		6.4	8.1	8.1	7.0	9.5	9.5				
Level of Service (LOS)						D	D		D	D		A	A	A	A	A	A				
Approach Delay, s/veh / LOS						42.8		D	41.9		D	7.7		A	9.4		A				
Intersection Delay, s/veh / LOS						14.6						B									
Multimodal Results						EB			WB			NB			SB						
Pedestrian LOS Score / LOS						2.9		C	2.9		C	2.2		B	2.2		B				
Bicycle LOS Score / LOS						0.9		A	0.6		A	1.2		A	0.9		A				

MOVEMENT SUMMARY

Site: SR 89 & Rd 4N Existing
Conditions - AM

SR 89 & Rd 4N
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	22	3.0	0.159	4.9	LOS A	0.6	15.5	0.15	0.87	27.5
8	T	294	5.0	0.159	5.0	LOS A	0.6	15.5	0.15	0.42	30.9
18	R	11	3.0	0.159	5.0	LOS A	0.6	15.5	0.15	0.55	30.1
Approach		328	4.8	0.159	5.0	LOS A	0.6	15.5	0.15	0.46	30.6
East: Rd 4N											
1	L	28	3.0	0.065	4.8	LOS A	0.2	4.1	0.30	0.79	27.5
6	T	6	3.0	0.065	4.8	LOS A	0.2	4.1	0.30	0.50	30.7
16	R	22	3.0	0.065	4.8	LOS A	0.2	4.1	0.30	0.57	30.2
Approach		56	3.0	0.065	4.8	LOS A	0.2	4.1	0.30	0.68	28.8
North: SR 89											
7	L	11	3.0	0.284	6.4	LOS A	1.2	31.7	0.19	0.89	26.8
4	T	539	5.0	0.284	6.4	LOS A	1.2	31.7	0.19	0.44	30.0
14	R	28	3.0	0.284	6.4	LOS A	1.2	31.7	0.19	0.55	29.3
Approach		578	4.9	0.284	6.4	LOS A	1.2	31.7	0.19	0.45	29.9
West: Rd 4N											
5	L	22	3.0	0.048	5.7	LOS A	0.1	3.2	0.41	0.84	27.1
2	T	11	3.0	0.048	5.7	LOS A	0.1	3.2	0.41	0.60	30.0
12	R	44	3.0	0.062	5.7	LOS A	0.2	3.9	0.40	0.68	29.6
Approach		78	3.0	0.062	5.7	LOS A	0.2	3.9	0.40	0.71	28.8
All Vehicles		1039	4.6	0.284	5.8	LOS A	1.2	31.7	0.20	0.48	29.9

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Thursday, May 12, 2016 5:11:16 PM

SIDRA INTERSECTION 5.1.13.2093

Project: U:\popovich\NewBusiness\Phoenix Office\Chino Valley - SR 89\Task 02 Current and Future Conditions

Figures\HCS Analysis\SR 89 & Rd 4N.sip

8001273, BURGESS & NIPLE, INC., SINGLE

Copyright © 2000-2011 Akcelik and Associates Pty Ltd

www.sidrasolutions.com

SIDRA
INTERSECTION

MOVEMENT SUMMARY

Site: SR 89 & Rd 4N Existing
Conditions - PM

SR 89 & Rd 4N
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	44	3.0	0.329	6.8	LOS A	1.5	39.2	0.17	0.87	26.6
8	T	592	5.0	0.329	6.8	LOS A	1.5	39.2	0.17	0.42	29.7
18	R	44	3.0	0.329	6.8	LOS A	1.5	39.2	0.17	0.54	28.9
Approach		681	4.7	0.329	6.8	LOS A	1.5	39.2	0.17	0.46	29.4
East: Rd 4N											
1	L	17	3.0	0.065	6.0	LOS A	0.2	4.1	0.42	0.88	27.0
6	T	6	3.0	0.065	6.0	LOS A	0.2	4.1	0.42	0.63	29.8
16	R	22	3.0	0.065	6.0	LOS A	0.2	4.1	0.42	0.69	29.4
Approach		44	3.0	0.065	6.0	LOS A	0.2	4.1	0.42	0.75	28.5
North: SR 89											
7	L	11	3.0	0.221	5.7	LOS A	0.9	22.9	0.20	0.88	27.2
4	T	417	5.0	0.221	5.7	LOS A	0.9	22.9	0.20	0.44	30.4
14	R	17	3.0	0.221	5.7	LOS A	0.9	22.9	0.20	0.56	29.7
Approach		444	4.9	0.221	5.7	LOS A	0.9	22.9	0.20	0.46	30.3
West: Rd 4N											
5	L	17	3.0	0.036	5.0	LOS A	0.1	2.4	0.36	0.81	27.4
2	T	11	3.0	0.036	5.0	LOS A	0.1	2.4	0.36	0.54	30.5
12	R	33	3.0	0.042	5.0	LOS A	0.1	2.6	0.34	0.62	30.0
Approach		61	3.0	0.042	5.0	LOS A	0.1	2.6	0.35	0.66	29.3
All Vehicles		1231	4.6	0.329	6.3	LOS A	1.5	39.2	0.20	0.48	29.7

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Thursday, May 12, 2016 5:12:29 PM

SIDRA INTERSECTION 5.1.13.2093

Project: U:\popovich\NewBusiness\Phoenix Office\Chino Valley - SR 89\Task 02 Current and Future Conditions

Figures\HCS Analysis\SR 89 & Rd 4N.sip

8001273, BURGESS & NIPLE, INC., SINGLE

Copyright © 2000-2011 Akcelik and Associates Pty Ltd


www.sidrasolutions.com

SIDRA
INTERSECTION

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Rolling Hills Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/6/2016	East/West Street	Rolling Hills Road
Analysis Year	2016	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	0	1		0	0	0	0	1	1	0	0	0	1	1
Configuration		L		R						L	T				T	R
Volume (veh/h)		5		45						25	180				390	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		6		53						29						
Capacity		378		600						1084						
v/c Ratio		0.02		0.09						0.03						
95% Queue Length		0.0		0.3						0.1						
Control Delay (s/veh)		14.7		11.6						8.4						
Level of Service (LOS)		B		B						A						
Approach Delay (s/veh)	11.9								1.0							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Rolling Hills Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/6/2016	East/West Street	Rolling Hills Road
Analysis Year	2016	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	0	1		0	0	0	0	1	1	0	0	0	1	1
Configuration		L		R						L	T				T	R
Volume (veh/h)		10		25						25	425				290	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		11		28						28						
Capacity		322		716						1219						
v/c Ratio		0.03		0.04						0.02						
95% Queue Length		0.1		0.1						0.1						
Control Delay (s/veh)		16.6		10.2						8.0						
Level of Service (LOS)		C		B						A						
Approach Delay (s/veh)	12.0								0.4							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Big Chino Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/6/2016	East/West Street	Big Chino Rd
Analysis Year	2016	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	0	0		0	0	0	0	1	1	0	0	0	1	1
Configuration			LR							L	T				T	R
Volume (veh/h)		10		180						50	135				205	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)			224							59						
Capacity			770							1305						
v/c Ratio			0.29							0.05						
95% Queue Length			1.2							0.1						
Control Delay (s/veh)			11.6							7.9						
Level of Service (LOS)			B							A						
Approach Delay (s/veh)	11.6								2.1							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Big Chino Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/6/2016	East/West Street	Big Chino Rd
Analysis Year	2016	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	0	0		0	0	0	0	1	1	0	0	0	1	1
Configuration			LR							L	T				T	R
Volume (veh/h)		20		80						185	230				235	35
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)			111							206						
Capacity			544							1254						
v/c Ratio			0.20							0.16						
95% Queue Length			0.8							0.6						
Control Delay (s/veh)			13.3							8.4						
Level of Service (LOS)			B							A						
Approach Delay (s/veh)	13.3								3.8							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Bramble Dr
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/6/2016	East/West Street	Bramble/San Francisco
Analysis Year	2016	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	1	0		1	1	0	0	1	1	1	0	1	1	1
Configuration		L		TR		L		TR		L	T	R		L	T	R
Volume (veh/h)		5	0	85		10	5	0		20	120	5		0	55	0
Percent Heavy Vehicles		3	3	3		3	3	3		3				3		
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		6		100		12		6		24						
Capacity		680		996		574		637		1529				1427		
v/c Ratio		0.01		0.10		0.02		0.01		0.02						
95% Queue Length		0.0		0.3		0.1		0.0		0.0						
Control Delay (s/veh)		10.3		9.0		11.4		10.7		7.4				7.5		
Level of Service (LOS)		B		A		B		B		A				A		
Approach Delay (s/veh)	9.1				11.2				1.0							
Approach LOS	A				B											

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Bramble Dr
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/6/2016	East/West Street	Bramble/San Francisco
Analysis Year	2016	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	1	0		1	1	0	0	1	1	1	0	1	1	1
Configuration		L		TR		L		TR		L	T	R		L	T	R
Volume (veh/h)		5	5	50		5	0	0		90	105	5		5	200	20
Percent Heavy Vehicles		3	3	3		3	3	3		3				3		
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																



Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		6		62		6				100				6		
Capacity		416		742		365				1315				1456		
v/c Ratio		0.01		0.08		0.02				0.08				0.00		
95% Queue Length		0.0		0.3		0.1				0.2				0.0		
Control Delay (s/veh)		13.8		10.3		15.0				8.0				7.5		
Level of Service (LOS)		B		B		C				A				A		
Approach Delay (s/veh)	10.6				15.0				3.6				0.2			
Approach LOS	B				C											


APPENDIX WP1-5

2021 HCS and SIDRA Results


HCS 2010 Signalized Intersection Results Summary

General Information						Intersection Information															
Agency		Burgess & Niple				Duration, h		0.25													
Analyst		KMS		Analysis Date		May 6, 2016		Area Type		Other											
Jurisdiction		ADOT/CYMPO		Time Period		AM Peak Hour		PHF		0.90											
Urban Street		SR 89		Analysis Year		2021		Analysis Period		1> 7:00											
Intersection		SR 89 and Road 3N		File Name		01_Road 3N_AM_5 Year Horizon.xus															
Project Description		SR 89 Transportation Study																			
Demand Information						EB			WB			NB			SB						
Approach Movement						L	T	R	L	T	R	L	T	R	L	T	R				
Demand (v), veh/h						60	60	180	50	50	40	80	290	40	20	580	80				
Signal Information																					
Cycle, s	100.0	Reference Phase	2																		
Offset, s	0	Reference Point	End																		
Uncoordinated	No	Simult. Gap E/W	On																		
Force Mode	Fixed	Simult. Gap N/S	On																		
Green						2.8	2.7	53.4	23.1	0.0	0.0										
Yellow						4.0	0.0	4.0	4.0	0.0	0.0										
Red						2.0	0.0	2.0	2.0	0.0	0.0										
Timer Results						EBL		EBT		WBL		WBT		NBL		NBT		SBL		SBT	
Assigned Phase								4				8		5		2		1		6	
Case Number								6.0				6.0		1.1		4.0		1.1		4.0	
Phase Duration, s								29.1				29.1		11.5		62.1		8.8		59.4	
Change Period, (Y+R c), s								6.0				6.0		6.0		6.0		6.0		6.0	
Max Allow Headway (MAH), s								4.5				4.5		4.0		0.0		4.0		0.0	
Queue Clearance Time (g s), s								16.9				21.7		4.2				2.6			
Green Extension Time (g e), s								1.8				1.5		0.2		0.0		0.0		0.0	
Phase Call Probability								1.00				1.00		0.92				0.46			
Max Out Probability								0.03				0.18		0.00				0.00			
Movement Group Results						EB			WB			NB			SB						
Approach Movement						L	T	R	L	T	R	L	T	R	L	T	R				
Assigned Movement						7	4	14	3	8	18	5	2	12	1	6	16				
Adjusted Flow Rate (v), veh/h						67	267		56	100		89	186	181	22	374	359				
Adjusted Saturation Flow Rate (s), veh/h/ln						1290	1641		1108	1725		1774	1810	1733	1774	1810	1732				
Queue Service Time (g s), s						4.4	14.9		4.8	4.7		2.2	5.0	5.1	0.6	12.1	12.2				
Cycle Queue Clearance Time (g c), s						9.1	14.9		19.7	4.7		2.2	5.0	5.1	0.6	12.1	12.2				
Green Ratio (g/C)						0.23	0.23		0.23	0.23		0.59	0.56	0.56	0.56	0.53	0.53				
Capacity (c), veh/h						310	379		164	399		465	1016	973	616	966	925				
Volume-to-Capacity Ratio (X)						0.215	0.703		0.339	0.251		0.191	0.183	0.186	0.036	0.387	0.388				
Back of Queue (Q), ft/ln (50 th percentile)						36.5	156.1		35.3	50.5		19.3	48.2	46.4	5	120.5	114.4				
Back of Queue (Q), veh/ln (50 th percentile)						1.4	6.2		1.4	2.0		0.8	1.9	1.9	0.2	4.7	4.6				
Queue Storage Ratio (RQ) (50 th percentile)						0.29	0.00		0.35	0.00		0.00	0.00	0.00	0.00	0.00	0.00				
Uniform Delay (d 1), s/veh						35.1	35.3		44.3	31.4		9.8	10.7	10.7	9.8	13.7	13.7				
Incremental Delay (d 2), s/veh						0.3	2.8		1.2	0.3		0.2	0.4	0.4	0.0	1.2	1.2				
Initial Queue Delay (d 3), s/veh						0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0				
Control Delay (d), s/veh						35.4	38.1		45.5	31.7		10.0	11.1	11.2	9.9	14.9	14.9				
Level of Service (LOS)						D	D		D	C		A	B	B	A	B	B				
Approach Delay, s/veh / LOS						37.6		D		36.6		D		10.9		B		14.7		B	
Intersection Delay, s/veh / LOS						20.2						C									
Multimodal Results						EB			WB			NB			SB						
Pedestrian LOS Score / LOS						2.8		C		2.8		C		2.2		B		2.3		B	
Bicycle LOS Score / LOS						1.0		A		0.7		A		0.9		A		1.1		A	

HCS 2010 Signalized Intersection Results Summary

General Information				Intersection Information		
Agency	Burgess & Niple			Duration, h	0.25	
Analyst	KMS	Analysis Date	May 6, 2016	Area Type	Other	
Jurisdiction	ADOT/CYMPO	Time Period	PM Peak Hour	PHF	0.90	
Urban Street	SR 89	Analysis Year	2021	Analysis Period	1> 7:00	
Intersection	SR 89 and Road 3N	File Name	01_Road 3N_PM_5 Year Horizon.xus			
Project Description	SR 89 Transportation Study					

Demand Information	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Demand (v), veh/h	80	50	110	40	30	10	230	650	50	20	530	30

Signal Information											
Cycle, s	100.0	Reference Phase	2								
Offset, s	0	Reference Point	End								
Uncoordinated	No	Simult. Gap E/W	On								
Force Mode	Fixed	Simult. Gap N/S	On								
											

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		22.5		22.5	14.4	68.8	8.8	63.2
Change Period, ($Y+R_c$), s		6.0		6.0	6.0	6.0	6.0	6.0
Max Allow Headway (MAH), s		4.4		4.4	4.0	0.0	4.0	0.0
Queue Clearance Time (g_s), s		12.0		15.6	7.5		2.5	
Green Extension Time (g_e), s		1.1		0.9	0.8	0.0	0.0	0.0
Phase Call Probability		1.00		1.00	1.00		0.46	
Max Out Probability		0.03		0.15	0.00		0.00	

Movement Group Results	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	89	178		44	44		256	394	384	22	314	309
Adjusted Saturation Flow Rate (s), veh/h/ln	1356	1658		1202	1783		1774	1810	1764	1774	1810	1775
Queue Service Time (g_s), s	6.0	10.0		3.6	2.1		5.5	10.4	10.4	0.5	9.0	9.0
Cycle Queue Clearance Time (g_c), s	8.1	10.0		13.6	2.1		5.5	10.4	10.4	0.5	9.0	9.0
Green Ratio (g/C)	0.16	0.16		0.16	0.16		0.67	0.63	0.63	0.60	0.57	0.57
Capacity (c), veh/h	268	274		151	294		604	1135	1106	468	1034	1014
Volume-to-Capacity Ratio (X)	0.332	0.650		0.295	0.151		0.423	0.347	0.347	0.047	0.303	0.304
Back of Queue (Q), ft/ln (50 th percentile)	52.3	107.2		28.5	23.9		44	93.4	90.1	4.4	86.1	83.4
Back of Queue (Q), veh/ln (50 th percentile)	2.1	4.3		1.1	1.0		1.7	3.7	3.6	0.2	3.4	3.3
Queue Storage Ratio (RQ) (50 th percentile)	0.42	0.00		0.28	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Uniform Delay (d_1), s/veh	39.2	39.0		45.4	35.8		7.2	8.9	8.9	8.4	11.1	11.1
Incremental Delay (d_2), s/veh	0.7	2.6		1.1	0.2		0.5	0.8	0.9	0.0	0.8	0.8
Initial Queue Delay (d_3), s/veh	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Control Delay (d), s/veh	39.9	41.6		46.4	36.0		7.6	9.7	9.7	8.4	11.9	11.9
Level of Service (LOS)	D	D		D	D		A	A	A	A	B	B
Approach Delay, s/veh / LOS	41.1	D		41.2	D		9.2	A		11.8	B	
Intersection Delay, s/veh / LOS	15.6						B					

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.8	C	2.8	C	2.2	B	2.2	B
Bicycle LOS Score / LOS	0.9	A	0.6	A	1.3	A	1.0	A

MOVEMENT SUMMARY

Site: SR 89 & Rd 4N 5 Year Horizon
- AM

SR 89 & Rd 4N
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	22	3.0	0.189	5.2	LOS A	0.7	19.0	0.15	0.88	27.3
8	T	356	5.0	0.189	5.3	LOS A	0.7	19.0	0.15	0.42	30.7
18	R	11	3.0	0.189	5.3	LOS A	0.7	19.0	0.15	0.55	29.9
Approach		389	4.8	0.189	5.3	LOS A	0.7	19.0	0.15	0.45	30.4
East: Rd 4N											
1	L	33	3.0	0.081	5.2	LOS A	0.2	5.2	0.34	0.82	27.3
6	T	11	3.0	0.081	5.2	LOS A	0.2	5.2	0.34	0.54	30.4
16	R	22	3.0	0.081	5.2	LOS A	0.2	5.2	0.34	0.60	29.9
Approach		67	3.0	0.081	5.2	LOS A	0.2	5.2	0.34	0.70	28.6
North: SR 89											
7	L	11	3.0	0.348	7.2	LOS A	1.6	41.9	0.23	0.88	26.5
4	T	656	5.0	0.348	7.2	LOS A	1.6	41.9	0.23	0.45	29.4
14	R	33	3.0	0.348	7.2	LOS A	1.6	41.9	0.23	0.56	28.7
Approach		700	4.9	0.348	7.2	LOS A	1.6	41.9	0.23	0.46	29.3
West: Rd 4N											
5	L	22	3.0	0.053	6.3	LOS A	0.1	3.5	0.45	0.87	26.8
2	T	11	3.0	0.053	6.3	LOS A	0.1	3.5	0.45	0.65	29.6
12	R	56	3.0	0.085	6.4	LOS A	0.2	5.4	0.44	0.73	29.1
Approach		89	3.0	0.085	6.4	LOS A	0.2	5.4	0.44	0.76	28.5
All Vehicles		1244	4.6	0.348	6.4	LOS A	1.6	41.9	0.23	0.49	29.6

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

MOVEMENT SUMMARY

Site: SR 89 & Rd 4N 5 Year Horizon
- PM

SR 89 & Rd 4N
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	56	3.0	0.404	7.9	LOS A	2.1	53.3	0.20	0.85	26.1
8	T	722	5.0	0.404	7.9	LOS A	2.1	53.3	0.20	0.43	29.0
18	R	56	3.0	0.404	7.9	LOS A	2.1	53.3	0.20	0.54	28.3
Approach		833	4.7	0.404	7.9	LOS A	2.1	53.3	0.20	0.46	28.7
East: Rd 4N											
1	L	22	3.0	0.109	7.2	LOS A	0.3	7.1	0.47	0.91	26.5
6	T	11	3.0	0.109	7.2	LOS A	0.3	7.1	0.47	0.68	29.1
16	R	33	3.0	0.109	7.2	LOS A	0.3	7.1	0.47	0.73	28.7
Approach		67	3.0	0.109	7.2	LOS A	0.3	7.1	0.47	0.78	27.9
North: SR 89											
7	L	11	3.0	0.277	6.4	LOS A	1.2	30.3	0.25	0.88	26.8
4	T	511	5.0	0.277	6.4	LOS A	1.2	30.3	0.25	0.46	29.9
14	R	22	3.0	0.277	6.4	LOS A	1.2	30.3	0.25	0.57	29.2
Approach		544	4.9	0.277	6.4	LOS A	1.2	30.3	0.25	0.47	29.8
West: Rd 4N											
5	L	22	3.0	0.047	5.5	LOS A	0.1	3.1	0.40	0.83	27.2
2	T	11	3.0	0.047	5.5	LOS A	0.1	3.1	0.40	0.58	30.1
12	R	44	3.0	0.060	5.5	LOS A	0.1	3.8	0.38	0.67	29.7
Approach		78	3.0	0.060	5.5	LOS A	0.1	3.8	0.39	0.70	28.9
All Vehicles		1522	4.6	0.404	7.2	LOS A	2.1	53.3	0.24	0.49	29.1

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Friday, May 13, 2016 11:42:57 AM
SIDRA INTERSECTION 5.1.13.2093
Project: P:\PR54679\Traffic\SR 89 & Rd 4N.sip
8001273, BURGESS & NIPLE, INC., SINGLE


Copyright © 2000-2011 Akcelik and Associates Pty Ltd
www.sidrasolutions.com

SIDRA
INTERSECTION

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Rolling Hills Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Rolling Hills Road
Analysis Year	2021	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	0	1		0	0	0	0	1	1	0	0	0	1	1
Configuration		L		R						L	T				T	R
Volume (veh/h)		10		50						30	210				470	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		12		59						35						
Capacity		309		530						1001						
v/c Ratio		0.04		0.11						0.03						
95% Queue Length		0.1		0.4						0.1						
Control Delay (s/veh)		17.1		12.6						8.7						
Level of Service (LOS)		C		B						A						
Approach Delay (s/veh)	13.4								1.1							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Rolling Hills Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Rolling Hills Road
Analysis Year	2021	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	0	1		0	0	0	0	1	1	0	0	0	1	1
Configuration		L		R						L	T				T	R
Volume (veh/h)		10		30						30	510				350	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		11		33						33						
Capacity		253		657						1152						
v/c Ratio		0.04		0.05						0.03						
95% Queue Length		0.1		0.2						0.1						
Control Delay (s/veh)		19.9		10.8						8.2						
Level of Service (LOS)		C		B						A						
Approach Delay (s/veh)	13.1								0.5							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Big Chino Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Big Chino Rd
Analysis Year	2021	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	0	0		0	0	0	0	1	1	0	0	0	1	1
Configuration			LR							L	T				T	R
Volume (veh/h)		20		220						60	160				240	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)			283							71						
Capacity			709							1260						
v/c Ratio			0.40							0.06						
95% Queue Length			1.9							0.2						
Control Delay (s/veh)			13.4							8.0						
Level of Service (LOS)			B							A						
Approach Delay (s/veh)	13.4								2.2							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Big Chino Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Big Chino Rd
Analysis Year	2021	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	0	0		0	0	0	0	1	1	0	0	0	1	1
Configuration			LR							L	T				T	R
Volume (veh/h)		30		100						220	280				280	40
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)			144							244						
Capacity			433							1197						
v/c Ratio			0.33							0.20						
95% Queue Length			1.4							0.8						
Control Delay (s/veh)			17.4							8.8						
Level of Service (LOS)			C							A						
Approach Delay (s/veh)	17.4								3.9							
Approach LOS	C															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Bramble Dr
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Bramble/San Francisco
Analysis Year	2021	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	1	0		1	1	0	0	1	1	1	0	1	1	1
Configuration		L		TR		L		TR		L	T	R		L	T	R
Volume (veh/h)		10	0	100		10	10	0		20	140	10		0	70	0
Percent Heavy Vehicles		3	3	3		3	3	3		3				3		
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		12		118		12		12		24						
Capacity		631		974		520		605		1507				1391		
v/c Ratio		0.02		0.12		0.02		0.02		0.02						
95% Queue Length		0.1		0.4		0.1		0.1		0.0						
Control Delay (s/veh)		10.8		9.2		12.1		11.1		7.4				7.6		
Level of Service (LOS)		B		A		B		B		A				A		
Approach Delay (s/veh)	9.4				11.6				0.9							
Approach LOS	A				B											

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Bramble Dr
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Bramble/San Francisco
Analysis Year	2021	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	1	0		1	1	0	0	1	1	1	0	1	1	1
Configuration		L		TR		L		TR		L	T	R		L	T	R
Volume (veh/h)		10	10	60		10	0	0		110	130	10		10	250	20
Percent Heavy Vehicles		3	3	3		3	3	3		3				3		
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		11		78		11				122				11		
Capacity		330		640		276				1254				1417		
v/c Ratio		0.03		0.12		0.04				0.10				0.01		
95% Queue Length		0.1		0.4		0.1				0.3				0.0		
Control Delay (s/veh)		16.3		11.4		18.6				8.2				7.6		
Level of Service (LOS)		C		B		C				A				A		
Approach Delay (s/veh)	12.0				18.6				3.6				0.3			
Approach LOS	B				C											

APPENDIX WP1-6

2026 HCS and SIDRA Results

HCS 2010 Signalized Intersection Results Summary

General Information				Intersection Information		
Agency	Burgess & Niple			Duration, h	0.25	
Analyst	KMS	Analysis Date	May 6, 2016	Area Type	Other	
Jurisdiction	ADOT/CYMPO	Time Period	AM Peak Hour	PHF	0.90	
Urban Street	SR 89	Analysis Year	2026	Analysis Period	1> 7:00	
Intersection	SR 89 and Road 3N	File Name	01_Road 3N_AM_10 Year Horizon.xus			
Project Description	SR 89 Transportation Study					

Demand Information	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Demand (v), veh/h	70	60	180	60	60	40	80	310	40	20	610	90

Signal Information											
Cycle, s	100.0	Reference Phase	2								
Offset, s	0	Reference Point	End								
Uncoordinated	No	Simult. Gap E/W	On	Green	2.8	2.7	52.5	24.0	0.0	0.0	
Force Mode	Fixed	Simult. Gap N/S	On	Yellow	4.0	0.0	4.0	4.0	0.0	0.0	
				Red	2.0	0.0	2.0	2.0	0.0	0.0	

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		30.0		30.0	11.5	61.3	8.8	58.5
Change Period, ($Y+R_c$), s		6.0		6.0	6.0	6.0	6.0	6.0
Max Allow Headway (MAH), s		4.5		4.5	4.0	0.0	4.0	0.0
Queue Clearance Time (g_s), s		16.8		22.5	4.2		2.6	
Green Extension Time (g_e), s		1.9		1.5	0.2	0.0	0.0	0.0
Phase Call Probability		1.00		1.00	0.92		0.46	
Max Out Probability		0.04		0.26	0.00		0.00	

Movement Group Results	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	78	267		67	111		89	197	192	22	398	380
Adjusted Saturation Flow Rate (s), veh/h/ln	1277	1641		1108	1738		1774	1810	1737	1774	1810	1728
Queue Service Time (g_s), s	5.3	14.8		5.8	5.2		2.2	5.5	5.6	0.6	13.4	13.4
Cycle Queue Clearance Time (g_c), s	10.4	14.8		20.5	5.2		2.2	5.5	5.6	0.6	13.4	13.4
Green Ratio (g/C)	0.24	0.24		0.24	0.24		0.58	0.55	0.55	0.55	0.53	0.53
Capacity (c), veh/h	312	393		175	416		439	1000	960	593	951	908
Volume-to-Capacity Ratio (X)	0.249	0.678		0.381	0.267		0.202	0.197	0.200	0.037	0.418	0.419
Back of Queue (Q), ft/ln (50 th percentile)	42.7	153.6		42.3	55.8		19.9	53	51	5.2	133.3	126.2
Back of Queue (Q), veh/ln (50 th percentile)	1.7	6.1		1.7	2.2		0.8	2.1	2.0	0.2	5.2	5.0
Queue Storage Ratio (RQ) (50 th percentile)	0.34	0.00		0.42	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Uniform Delay (d_1), s/veh	35.1	34.5		43.8	30.9		10.3	11.2	11.2	10.2	14.4	14.4
Incremental Delay (d_2), s/veh	0.4	2.4		1.4	0.3		0.2	0.4	0.5	0.0	1.4	1.4
Initial Queue Delay (d_3), s/veh	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Control Delay (d), s/veh	35.5	36.9		45.1	31.2		10.5	11.7	11.7	10.3	15.8	15.9
Level of Service (LOS)	D	D		D	C		B	B	B	B	B	B
Approach Delay, s/veh / LOS	36.6	D		36.4	D		11.5	B		15.7	B	
Intersection Delay, s/veh / LOS	20.6						C					


Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.8	C	2.8	C	2.2	B	2.3	B
Bicycle LOS Score / LOS	1.1	A	0.8	A	0.9	A	1.1	A

HCS 2010 Signalized Intersection Results Summary

General Information

Agency	Burgess & Niple		
Analyst	KMS	Analysis Date	May 6, 2016
Jurisdiction	ADOT/CYMPO	Time Period	PM Peak Hour
Urban Street	SR 89	Analysis Year	2026
Intersection	SR 89 and Road 3N	File Name	01_Road 3N_PM_
Project Description	SR 89 Transportation Study		

Intersection Information



Demand Information

	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Demand (v), veh/h	90	60	120	40	30	10	250	690	60	20	560	30

Signal Information

Cycle, s	100.0	Reference Phase	2									
Offset, s	0	Reference Point	End									
Uncoordinated	No	Simult. Gap E/W	On	Green	2.8	0.4	55.1	17.8	0.0	0.0		
Force Mode	Fixed	Simult. Gap N/S	On	Yellow	4.0	4.0	4.0	4.0	0.0	0.0		
				Red	2.0	2.0	2.0	2.0	0.0	0.0		

Timer Results

	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		23.8		23.8	15.2	67.5	8.8	61.1
Change Period, ($Y+R_c$), s		6.0		6.0	6.0	6.0	6.0	6.0
Max Allow Headway (MAH), s		4.4		4.4	4.0	0.0	4.0	0.0
Queue Clearance Time (g_s), s		13.2		16.8	8.3		2.5	
Green Extension Time (g_e), s		1.2		0.9	0.9	0.0	0.0	0.0
Phase Call Probability		1.00		1.00	1.00		0.46	
Max Out Probability		0.06		0.30	0.00		0.00	

Movement Group Results

	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	100	200		44	44		278	423	411	22	330	325
Adjusted Saturation Flow Rate (s), veh/h/ln	1356	1663		1178	1783		1774	1810	1758	1774	1810	1777
Queue Service Time (g_s), s	6.7	11.2		3.7	2.1		6.3	11.7	11.8	0.5	10.0	10.1
Cycle Queue Clearance Time (g_c), s	8.8	11.2		14.8	2.1		6.3	11.7	11.8	0.5	10.0	10.1
Green Ratio (g/C)	0.18	0.18		0.18	0.18		0.66	0.61	0.61	0.58	0.55	0.55
Capacity (c), veh/h	285	296		150	317		582	1112	1081	433	996	978
Volume-to-Capacity Ratio (X)	0.350	0.676		0.297	0.140		0.477	0.380	0.380	0.051	0.332	0.332
Back of Queue (Q), ft/ln (50 th percentile)	58.3	120.3		28.4	23.4		50.9	107.6	103.5	4.8	97.7	95.2
Back of Queue (Q), veh/ln (50 th percentile)	2.3	4.8		1.1	0.9		2.0	4.2	4.1	0.2	3.8	3.8
Queue Storage Ratio (RQ) (50 th percentile)	0.47	0.00		0.28	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Uniform Delay (d_1), s/veh	38.3	38.4		45.3	34.7		7.9	9.7	9.7	9.3	12.4	12.4
Incremental Delay (d_2), s/veh	0.7	2.7		1.1	0.2		0.6	1.0	1.0	0.0	0.9	0.9
Initial Queue Delay (d_3), s/veh	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Control Delay (d), s/veh	39.1	41.1		46.4	34.9		8.5	10.7	10.7	9.3	13.3	13.3
Level of Service (LOS)	D	D		D	C		A	B	B	A	B	B
Approach Delay, s/veh / LOS	40.4	D		40.6	D		10.2	B		13.1	B	
Intersection Delay, s/veh / LOS	16.5						B					

Multimodal Results

	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.8	C	2.8	C	2.2	B	2.2	B
Bicycle LOS Score / LOS	1.0	A	0.6	A	1.4	A	1.0	A

MOVEMENT SUMMARY

Site: SR 89 & Rd 4N 10 Year
Horizon - AM

SR 89 & Rd 4N
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	22	3.0	0.200	5.4	LOS A	0.8	20.3	0.16	0.88	27.3
8	T	378	5.0	0.200	5.4	LOS A	0.8	20.3	0.16	0.42	30.6
18	R	11	3.0	0.200	5.4	LOS A	0.8	20.3	0.16	0.55	29.9
Approach		411	4.8	0.200	5.4	LOS A	0.8	20.3	0.16	0.45	30.4
East: Rd 4N											
1	L	33	3.0	0.083	5.3	LOS A	0.2	5.3	0.35	0.83	27.3
6	T	11	3.0	0.083	5.3	LOS A	0.2	5.3	0.35	0.55	30.3
16	R	22	3.0	0.083	5.3	LOS A	0.2	5.3	0.35	0.61	29.8
Approach		67	3.0	0.083	5.3	LOS A	0.2	5.3	0.35	0.71	28.5
North: SR 89											
7	L	11	3.0	0.370	7.5	LOS A	1.8	45.8	0.24	0.88	26.3
4	T	700	5.0	0.370	7.5	LOS A	1.8	45.9	0.24	0.45	29.2
14	R	33	3.0	0.370	7.5	LOS A	1.8	45.9	0.24	0.56	28.6
Approach		744	4.9	0.370	7.5	LOS A	1.8	45.9	0.24	0.46	29.1
West: Rd 4N											
5	L	22	3.0	0.055	6.5	LOS A	0.1	3.6	0.47	0.89	26.7
2	T	11	3.0	0.055	6.5	LOS A	0.1	3.6	0.47	0.66	29.4
12	R	56	3.0	0.087	6.6	LOS A	0.2	5.6	0.45	0.74	28.9
Approach		89	3.0	0.087	6.6	LOS A	0.2	5.6	0.46	0.77	28.4
All Vehicles		1311	4.6	0.370	6.7	LOS A	1.8	45.9	0.23	0.49	29.4

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

MOVEMENT SUMMARY

Site: SR 89 & Rd 4N 10 Year
Horizon - PM

SR 89 & Rd 4N
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	56	3.0	0.426	8.2	LOS A	2.2	58.0	0.21	0.85	26.0
8	T	767	5.0	0.426	8.2	LOS A	2.2	58.0	0.21	0.43	28.8
18	R	56	3.0	0.426	8.2	LOS A	2.2	58.0	0.21	0.54	28.1
Approach		878	4.7	0.426	8.2	LOS A	2.2	58.0	0.21	0.46	28.5
East: Rd 4N											
1	L	22	3.0	0.113	7.4	LOS A	0.3	7.3	0.49	0.92	26.4
6	T	11	3.0	0.113	7.4	LOS A	0.3	7.3	0.49	0.69	28.9
16	R	33	3.0	0.113	7.4	LOS A	0.3	7.3	0.49	0.74	28.5
Approach		67	3.0	0.113	7.4	LOS A	0.3	7.3	0.49	0.79	27.8
North: SR 89											
7	L	11	3.0	0.294	6.6	LOS A	1.3	32.8	0.25	0.88	26.8
4	T	544	5.0	0.294	6.6	LOS A	1.3	32.8	0.25	0.46	29.8
14	R	22	3.0	0.294	6.6	LOS A	1.3	32.8	0.25	0.57	29.1
Approach		578	4.9	0.294	6.6	LOS A	1.3	32.8	0.25	0.47	29.7
West: Rd 4N											
5	L	22	3.0	0.048	5.7	LOS A	0.1	3.2	0.41	0.84	27.1
2	T	11	3.0	0.048	5.7	LOS A	0.1	3.2	0.41	0.60	30.0
12	R	44	3.0	0.062	5.7	LOS A	0.2	3.9	0.40	0.68	29.6
Approach		78	3.0	0.062	5.7	LOS A	0.2	3.9	0.40	0.71	28.8
All Vehicles		1600	4.6	0.426	7.5	LOS A	2.2	58.0	0.25	0.49	28.9

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Friday, May 13, 2016 11:39:19 AM
SIDRA INTERSECTION 5.1.13.2093
Project: P:\PR54679\Traffic\SR 89 & Rd 4N.sip
8001273, BURGESS & NIPLE, INC., SINGLE


Copyright © 2000-2011 Akcelik and Associates Pty Ltd
www.sidrasolutions.com

SIDRA
INTERSECTION

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Rolling Hills Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Rolling Hills Road
Analysis Year	2026	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	0	1		0	0	0	0	1	1	0	0	0	1	1
Configuration		L		R						L	T				T	R
Volume (veh/h)		10		50						30	220				490	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		12		59						35						
Capacity		295		515						981						
v/c Ratio		0.04		0.11						0.04						
95% Queue Length		0.1		0.4						0.1						
Control Delay (s/veh)		17.7		12.9						8.8						
Level of Service (LOS)		C		B						A						
Approach Delay (s/veh)	13.7								1.0							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Rolling Hills Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Rolling Hills Road
Analysis Year	2026	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	0	1		0	0	0	0	1	1	0	0	0	1	1
Configuration		L		R						L	T				T	R
Volume (veh/h)		10		30						30	540				370	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		11		33						33						
Capacity		234		638						1131						
v/c Ratio		0.05		0.05						0.03						
95% Queue Length		0.1		0.2						0.1						
Control Delay (s/veh)		21.1		10.9						8.3						
Level of Service (LOS)		C		B						A						
Approach Delay (s/veh)	13.5								0.4							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Big Chino Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Big Chino Rd
Analysis Year	2026	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	0	0		0	0	0	0	1	1	0	0	0	1	1
Configuration			LR							L	T				T	R
Volume (veh/h)		20		220						60	170				250	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)			283							71						
Capacity			696							1248						
v/c Ratio			0.41							0.06						
95% Queue Length			2.0							0.2						
Control Delay (s/veh)			13.7							8.1						
Level of Service (LOS)			B							A						
Approach Delay (s/veh)	13.7								2.1							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Big Chino Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Big Chino Rd
Analysis Year	2026	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	0	0		0	0	0	0	1	1	0	0	0	1	1
Configuration			LR							L	T				T	R
Volume (veh/h)		30		100						230	290				290	40
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)			144							256						
Capacity			412							1186						
v/c Ratio			0.35							0.22						
95% Queue Length			1.5							0.8						
Control Delay (s/veh)			18.4							8.9						
Level of Service (LOS)			C							A						
Approach Delay (s/veh)	18.4								3.9							
Approach LOS	C															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Bramble Dr
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Bramble/San Francisco
Analysis Year	2026	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	1	0		1	1	0	0	1	1	1	0	1	1	1
Configuration		L		TR		L		TR		L	T	R		L	T	R
Volume (veh/h)		10	0	100		10	10	0		30	150	10		0	80	0
Percent Heavy Vehicles		3	3	3		3	3	3		3				3		
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		12		118		12		12		35						
Capacity		586		959		482		566		1492				1379		
v/c Ratio		0.02		0.12		0.02		0.02		0.02						
95% Queue Length		0.1		0.4		0.1		0.1		0.1						
Control Delay (s/veh)		11.3		9.3		12.7		11.5		7.5				7.6		
Level of Service (LOS)		B		A		B		B		A				A		
Approach Delay (s/veh)	9.5				12.1				1.2							
Approach LOS	A				B											

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Bramble Dr
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Bramble/San Francisco
Analysis Year	2026	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	1	0		1	1	0	0	1	1	1	0	1	1	1
Configuration		L		TR		L		TR		L	T	R		L	T	R
Volume (veh/h)		10	10	60		10	0	0		110	130	10		10	260	30
Percent Heavy Vehicles		3	3	3		3	3	3		3				3		
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																

Delay, Queue Length, and Level of Service


Flow Rate (veh/h)		11		78		11				122				11		
Capacity		324		631		271				1231				1417		
v/c Ratio		0.03		0.12		0.04				0.10				0.01		
95% Queue Length		0.1		0.4		0.1				0.3				0.0		
Control Delay (s/veh)		16.5		11.5		18.9				8.2				7.6		
Level of Service (LOS)		C		B		C				A				A		
Approach Delay (s/veh)	12.1				18.9				3.6				0.2			
Approach LOS	B				C											

APPENDIX WP1-7

2036 HCS and SIDRA Results

HCS 2010 Signalized Intersection Results Summary

General Information				Intersection Information	
Agency	Burgess & Niple			Duration, h	0.25
Analyst	KMS	Analysis Date	May 6, 2016	Area Type	Other
Jurisdiction	ADOT/CYMPO	Time Period	AM Peak Hour	PHF	0.90
Urban Street	SR 89	Analysis Year	2036	Analysis Period	1 > 7:00
Intersection	SR 89 and Road 3N	File Name	01_Road 3N_AM_20 Year Horizon.xus		
Project Description	SR 89 Transportation Study				



Demand Information	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Demand (v), veh/h	70	70	200	60	60	40	90	340	40	20	680	100


Signal Information											
Cycle, s	100.0	Reference Phase	2								
Offset, s	0	Reference Point	End								
Uncoordinated	No	Simult. Gap E/W	On	Green	2.8	2.9	50.5	25.8	0.0	0.0	
Force Mode	Fixed	Simult. Gap N/S	On	Yellow	4.0	0.0	4.0	4.0	0.0	0.0	
				Red	2.0	0.0	2.0	2.0	0.0	0.0	

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		31.8		31.8	11.6	59.4	8.8	56.5
Change Period, ($Y+R_c$), s		6.0		6.0	6.0	6.0	6.0	6.0
Max Allow Headway (MAH), s		4.5		4.5	4.0	0.0	4.0	0.0
Queue Clearance Time (g_s), s		18.6		24.5	4.6		2.6	
Green Extension Time (g_e), s		2.0		1.4	0.2	0.0	0.0	0.0
Phase Call Probability		1.00		1.00	0.94		0.46	
Max Out Probability		0.08		0.53	0.00		0.00	

Movement Group Results	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	78	300		67	111		100	214	208	22	443	423
Adjusted Saturation Flow Rate (s), veh/h/ln	1277	1644		1075	1738		1774	1810	1743	1774	1810	1728
Queue Service Time (g_s), s	5.1	16.6		6.0	5.1		2.6	6.2	6.3	0.6	16.0	16.1
Cycle Queue Clearance Time (g_c), s	10.2	16.6		22.5	5.1		2.6	6.2	6.3	0.6	16.0	16.1
Green Ratio (g/C)	0.26	0.26		0.26	0.26		0.56	0.53	0.53	0.53	0.51	0.51
Capacity (c), veh/h	338	425		172	449		391	966	931	554	915	873
Volume-to-Capacity Ratio (X)	0.230	0.707		0.387	0.248		0.256	0.221	0.224	0.040	0.485	0.485
Back of Queue (Q), ft/ln (50 th percentile)	41.5	175		42.4	54.1		24	61.4	59	5.5	163.5	154.6
Back of Queue (Q), veh/ln (50 th percentile)	1.6	7.0		1.7	2.2		0.9	2.4	2.4	0.2	6.4	6.2
Queue Storage Ratio (RQ) (50 th percentile)	0.33	0.00		0.42	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Uniform Delay (d_1), s/veh	33.4	33.6		43.8	29.4		11.7	12.3	12.3	11.2	16.2	16.2
Incremental Delay (d_2), s/veh	0.3	3.5		1.4	0.3		0.3	0.5	0.6	0.0	1.8	1.9
Initial Queue Delay (d_3), s/veh	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Control Delay (d), s/veh	33.7	37.2		45.2	29.7		12.1	12.8	12.9	11.2	18.0	18.1
Level of Service (LOS)	C	D		D	C		B	B	B	B	B	B
Approach Delay, s/veh / LOS	36.5		D	35.5		D	12.7		B	17.9		B
Intersection Delay, s/veh / LOS	21.7						C					

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.8	C	2.8	C	2.3	B	2.3	B
Bicycle LOS Score / LOS	1.1	A	0.8	A	0.9	A	1.2	A

HCS 2010 Signalized Intersection Results Summary

General Information				Intersection Information		
Agency	Burgess & Niple			Duration, h	0.25	
Analyst	KMS	Analysis Date	May 6, 2016	Area Type	Other	
Jurisdiction	ADOT/CYMPO	Time Period	PM Peak Hour	PHF	0.90	
Urban Street	SR 89	Analysis Year	2036	Analysis Period	1> 7:00	
Intersection	SR 89 and Road 3N	File Name	01_Road 3N_PM_20 Year Horizon.xus			
Project Description	SR 89 Transportation Study					

Demand Information	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Demand (v), veh/h	100	60	130	40	40	20	280	770	60	20	620	40

Signal Information											
Cycle, s	100.0	Reference Phase	2								
Offset, s	0	Reference Point	End								
Uncoordinated	No	Simult. Gap E/W	On	Green	2.8	1.6	53.1	18.5	0.0	0.0	
Force Mode	Fixed	Simult. Gap N/S	On	Yellow	4.0	4.0	4.0	4.0	0.0	0.0	
				Red	2.0	2.0	2.0	2.0	0.0	0.0	

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		24.5		24.5	16.4	66.7	8.8	59.1
Change Period, ($Y+R_c$), s		6.0		6.0	6.0	6.0	6.0	6.0
Max Allow Headway (MAH), s		4.4		4.4	4.0	0.0	4.0	0.0
Queue Clearance Time (g_s), s		13.9		17.5	9.3		2.6	
Green Extension Time (g_e), s		1.3		1.0	1.0	0.0	0.0	0.0
Phase Call Probability		1.00		1.00	1.00		0.46	
Max Out Probability		0.10		0.44	0.00		0.00	

Movement Group Results	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	111	211		44	67		311	467	455	22	370	363
Adjusted Saturation Flow Rate (s), veh/h/ln	1329	1658		1166	1757		1774	1810	1763	1774	1810	1770
Queue Service Time (g_s), s	7.7	11.9		3.7	3.2		7.3	13.7	13.7	0.6	12.1	12.1
Cycle Queue Clearance Time (g_c), s	10.9	11.9		15.5	3.2		7.3	13.7	13.7	0.6	12.1	12.1
Green Ratio (g/C)	0.19	0.19		0.19	0.19		0.65	0.61	0.61	0.56	0.53	0.53
Capacity (c), veh/h	276	307		150	326		551	1099	1070	392	961	940
Volume-to-Capacity Ratio (X)	0.402	0.687		0.296	0.205		0.565	0.425	0.425	0.057	0.385	0.386
Back of Queue (Q), ft/ln (50 th percentile)	66	127.7		28.4	35.3		60.8	127	122	5.1	119.5	115.7
Back of Queue (Q), veh/ln (50 th percentile)	2.6	5.1		1.1	1.4		2.4	5.0	4.9	0.2	4.7	4.6
Queue Storage Ratio (RQ) (50 th percentile)	0.53	0.00		0.28	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Uniform Delay (d_1), s/veh	39.1	38.0		45.2	34.5		9.0	10.4	10.4	10.2	13.8	13.8
Incremental Delay (d_2), s/veh	0.9	3.3		1.1	0.3		0.9	1.2	1.2	0.1	1.2	1.2
Initial Queue Delay (d_3), s/veh	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Control Delay (d), s/veh	40.0	41.3		46.3	34.8		9.9	11.6	11.6	10.3	15.0	15.0
Level of Service (LOS)	D	D		D	C		A	B	B	B	B	B
Approach Delay, s/veh / LOS	40.9	D		39.4	D		11.2	B		14.9	B	
Intersection Delay, s/veh / LOS	17.6						B					

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.8	C	2.8	C	2.2	B	2.3	B
Bicycle LOS Score / LOS	1.0	A	0.7	A	1.5	A	1.1	A

MOVEMENT SUMMARY

Site: SR 89 & Rd 4N 20 Year
Horizon - AM

SR 89 & Rd 4N
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	33	3.0	0.232	5.7	LOS A	0.9	24.5	0.16	0.87	27.1
8	T	422	5.0	0.232	5.7	LOS A	0.9	24.5	0.16	0.42	30.4
18	R	22	3.0	0.232	5.7	LOS A	0.9	24.5	0.16	0.55	29.6
Approach		478	4.8	0.232	5.7	LOS A	0.9	24.5	0.16	0.46	30.1
East: Rd 4N											
1	L	44	3.0	0.115	5.8	LOS A	0.3	7.5	0.38	0.86	27.0
6	T	22	3.0	0.115	5.8	LOS A	0.3	7.5	0.38	0.59	30.0
16	R	22	3.0	0.115	5.8	LOS A	0.3	7.5	0.38	0.65	29.5
Approach		89	3.0	0.115	5.8	LOS A	0.3	7.5	0.38	0.74	28.3
North: SR 89											
7	L	11	3.0	0.429	8.6	LOS A	2.2	56.3	0.32	0.87	25.9
4	T	778	5.0	0.429	8.6	LOS A	2.2	56.3	0.32	0.48	28.6
14	R	44	3.0	0.429	8.6	LOS A	2.2	56.3	0.32	0.58	28.0
Approach		833	4.9	0.429	8.6	LOS A	2.2	56.3	0.32	0.49	28.5
West: Rd 4N											
5	L	22	3.0	0.059	7.0	LOS A	0.2	3.9	0.50	0.90	26.5
2	T	11	3.0	0.059	7.0	LOS A	0.2	3.9	0.50	0.69	29.1
12	R	67	3.0	0.112	7.4	LOS A	0.3	7.2	0.49	0.75	28.5
Approach		100	3.0	0.112	7.2	LOS A	0.3	7.2	0.49	0.78	28.1
All Vehicles		1500	4.6	0.429	7.4	LOS A	2.2	56.3	0.28	0.52	28.9

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Friday, May 13, 2016 4:02:15 PM
SIDRA INTERSECTION 5.1.13.2093
Project: P:\PR54679\Traffic\SR 89 & Rd 4N.sip
8001273, BURGESS & NIPLE, INC., SINGLE

Copyright © 2000-2011 Akcelik and Associates Pty Ltd
www.sidrasolutions.com

SIDRA
INTERSECTION

MOVEMENT SUMMARY

Site: SR 89 & Rd 4N 20 Year
Horizon - PM

SR 89 & Rd 4N
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	67	3.0	0.485	9.2	LOS A	2.8	71.8	0.26	0.84	25.5
8	T	856	5.0	0.485	9.2	LOS A	2.8	71.8	0.26	0.44	28.2
18	R	67	3.0	0.485	9.2	LOS A	2.8	71.8	0.26	0.55	27.6
Approach		989	4.7	0.485	9.2	LOS A	2.8	71.8	0.26	0.47	27.9
East: Rd 4N											
1	L	22	3.0	0.122	8.1	LOS A	0.3	7.9	0.53	0.92	26.1
6	T	11	3.0	0.122	8.1	LOS A	0.3	7.9	0.53	0.71	28.5
16	R	33	3.0	0.122	8.1	LOS A	0.3	7.9	0.53	0.76	28.1
Approach		67	3.0	0.122	8.1	LOS A	0.3	7.9	0.53	0.81	27.4
North: SR 89											
7	L	22	3.0	0.331	7.2	LOS A	1.5	38.5	0.28	0.87	26.5
4	T	600	5.0	0.331	7.2	LOS A	1.5	38.5	0.28	0.47	29.4
14	R	22	3.0	0.331	7.2	LOS A	1.5	38.5	0.28	0.58	28.8
Approach		644	4.9	0.331	7.2	LOS A	1.5	38.5	0.28	0.49	29.3
West: Rd 4N											
5	L	22	3.0	0.050	6.0	LOS A	0.1	3.3	0.44	0.86	27.0
2	T	11	3.0	0.050	6.0	LOS A	0.1	3.3	0.44	0.62	29.8
12	R	44	3.0	0.065	6.0	LOS A	0.2	4.1	0.42	0.70	29.4
Approach		78	3.0	0.065	6.0	LOS A	0.2	4.1	0.43	0.74	28.6
All Vehicles		1778	4.6	0.485	8.3	LOS A	2.8	71.8	0.28	0.50	28.4

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).


Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Rolling Hills Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Rolling Hills Road
Analysis Year	2036	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	0	1		0	0	0	0	1	1	0	0	0	1	1
Configuration		L		R						L	T				T	R
Volume (veh/h)		10		60						30	240				520	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		12		71						35						
Capacity		272		491						951						
v/c Ratio		0.04		0.14						0.04						
95% Queue Length		0.1		0.5						0.1						
Control Delay (s/veh)		18.9		13.6						8.9						
Level of Service (LOS)		C		B						A						
Approach Delay (s/veh)	14.3								1.0							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Rolling Hills Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Rolling Hills Road
Analysis Year	2036	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	0	1		0	0	0	0	1	1	0	0	0	1	1
Configuration		L		R						L	T				T	R
Volume (veh/h)		10		30						40	580				390	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		11		33						44						
Capacity		205		620						1110						
v/c Ratio		0.05		0.05						0.04						
95% Queue Length		0.2		0.2						0.1						
Control Delay (s/veh)		23.5		11.1						8.4						
Level of Service (LOS)		C		B						A						
Approach Delay (s/veh)	14.2								0.5							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Big Chino Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Big Chino Rd
Analysis Year	2036	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	0	0		0	0	0	0	1	1	0	0	0	1	1
Configuration			LR							L	T				T	R
Volume (veh/h)		20		240						70	180				270	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)			306							82						
Capacity			673							1223						
v/c Ratio			0.45							0.07						
95% Queue Length			2.4							0.2						
Control Delay (s/veh)			14.7							8.2						
Level of Service (LOS)			B							A						
Approach Delay (s/veh)	14.7								2.3							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Big Chino Rd
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Big Chino Rd
Analysis Year	2036	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	0	0		0	0	0	0	1	1	0	0	0	1	1
Configuration			LR							L	T				T	R
Volume (veh/h)		30		110						250	310				320	50
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)			155							278						
Capacity			378							1140						
v/c Ratio			0.41							0.24						
95% Queue Length			1.9							1.0						
Control Delay (s/veh)			21.0							9.2						
Level of Service (LOS)			C							A						
Approach Delay (s/veh)	21.0								4.1							
Approach LOS	C															

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Bramble Dr
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Bramble/San Francisco
Analysis Year	2036	North/South Street	SR 89
Time Analyzed	AM Peak Hour	Peak Hour Factor	0.85
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	1	0		1	1	0	0	1	1	1	0	1	1	1
Configuration		L		TR		L		TR		L	T	R		L	T	R
Volume (veh/h)		10	0	110		10	10	0		30	160	10		0	80	0
Percent Heavy Vehicles		3	3	3		3	3	3		3				3		
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																


Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		12		129		12		12		35						
Capacity		575		959		463		557		1492				1365		
v/c Ratio		0.02		0.13		0.03		0.02		0.02						
95% Queue Length		0.1		0.5		0.1		0.1		0.1						
Control Delay (s/veh)		11.4		9.3		13.0		11.6		7.5				7.6		
Level of Service (LOS)		B		A		B		B		A				A		
Approach Delay (s/veh)	9.5				12.3				1.1							
Approach LOS	A				B											

HCS 2010 Two-Way Stop Control Summary Report

General Information		Site Information	
Analyst	KMS	Intersection	SR 89 & Bramble Dr
Agency/Co.	Burgess & Niple	Jurisdiction	ADOT/CYMPO
Date Performed	5/2016	East/West Street	Bramble/San Francisco
Analysis Year	2036	North/South Street	SR 89
Time Analyzed	PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	SR 89 Transportation Study		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	1	0		1	1	0	0	1	1	1	0	1	1	1
Configuration		L		TR		L		TR		L	T	R		L	T	R
Volume (veh/h)		10	10	60		10	0	0		120	140	20		10	290	30
Percent Heavy Vehicles		3	3	3		3	3	3		3				3		
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																

Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		11		78		11				133				11		
Capacity		289		595		240				1197				1390		
v/c Ratio		0.04		0.13		0.05				0.11				0.01		
95% Queue Length		0.1		0.4		0.1				0.4				0.0		
Control Delay (s/veh)		17.9		12.0		20.7				8.4				7.6		
Level of Service (LOS)		C		B		C				A				A		
Approach Delay (s/veh)	12.7				20.7				3.6				0.2			
Approach LOS	B				C											

APPENDIX WP2-1
Recommendations Map Book

**State Route 89 Chino Valley to Forest Boundary
Transportation Study**

ADOT Task Assignment MPD 0034-16

Appendix WP2-1 Recommendations Map Book

Prepared for:




AND



Prepared by:

BURGESS & NIPLE


- Legend**
- ADOT Mile Posts
 - Municipal Boundary
 - Right of Way
 - Parcels
- Project Horizons**
- Near-Term
 - Mid-Term
 - Long-Term



Project:	P1A - Install Raised Median from Butterfield Road to Road 3N and Retime Signal at Road 3N
Location:	Butterfield Road to Road 3N
Description:	Convert TWLTL to 8-foot raised median and construct 5-foot sidewalk on both sides, from Butterfield Road to Road 3N. Mill and overlay existing asphaltic concrete pavement; existing curb and gutter to remain. Retime the existing signal at Road 3N with a 100 second cycle for both peaks, with a protected-permitted southbound left-turn, protected only northbound left-turn, and permitted only eastbound and westbound left-turns.
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$490,000

Project:	P1B: Install Raised Median from Perkinsville Road to Road 3N with Roundabout at Road 3N
Location:	Perkinsville Road to Road 3N
Description:	Convert TWLTL to 8-foot raised median and construct 5-foot sidewalk on both sides, from Perkinsville Road to Road 3N. Construct a two-lane roundabout at Road 3N.
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$2,010,000


Urban Highway Typical Section UA
Figure 306.4A in ADOT RDG Modified
w/ Narrowed Median & Sidewalk



Project:	P2: Widen to Four-Lane Section with Raised Median from Road 3N to Road 4N
Location:	Road 3N to Road 4N
Description:	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 3N to Road 4N roundabout (under construction).
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$5,890,000


- Legend
- ADOT Mile Posts
-
- Municipal Boundary

Project Horizons


Near-TermMid-TermLong-Term

Project:	P2: Widen to Four-Lane Section with Raised Median from Road 3N to Road 4N
Location:	Road 3N to Road 4N
Description:	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 3N to Road 4N roundabout (under construction).
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$5,890,000

Urban Highway Typical Section UA
Figure 306.4A in ADOT RDG
Modified w/ Narrowed Median & Sidewalk




- Legend**
- ADOT Mile Posts
 - ▬ Municipal Boundary
 - ▬ Right of Way
 - ▬ Parcels
- Project Horizons**
- Near-Term
 - Mid-Term
 - Long-Term




Project:	P2: Widen to Four-Lane Section with Raised Median from Road 3N to Road 4N
Location:	Road 3N to Road 4N
Description:	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 3N to Road 4N roundabout (under construction).
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$5,890,000

Project:	P3 - Widen to Four-Lane Section with Raised Median from Road 4N to Road 5N and Construct Roundabout at Road 5N
Location:	Road 4N to Road 5N
Description:	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 4N roundabout (under construction) to proposed Road 5N Roundabout. This project could be constructed in phases, with the roundabout at Road 5N as the first phase .
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$8,370,000


Urban Highway Typical Section UA
Figure 306.4A in ADOT RDG
Modified w/ Narrowed Median & Sidewalk






Project:	P3 - Widen to Four-Lane Section with Raised Median from Road 4N to Road 5N and Construct Roundabout at Road 5N
Location:	Road 4N to Road 5N
Description:	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 4N roundabout (under construction) to proposed Road 5N Roundabout. This project could be constructed in phases, with the roundabout at Road 5N as the first phase .
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$8,370,000


Urban Highway Typical Section UA
Figure 306.4A in ADOT RDG
Modified w/ Narrowed Median & Sidewalk





Project:	P3 - Widen to Four-Lane Section with Raised Median from Road 4N to Road 5N and Construct Roundabout at Road 5N
Location:	Road 4N to Road 5N
Description:	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 4N roundabout (under construction) to proposed Road 5N Roundabout. This project could be constructed in phases, with the roundabout at Road 5N as the first phase .
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$8,370,000

Urban Highway Typical Section UA
Figure 306.4A in ADOT RDG
Modified w/ Narrowed Median & Sidewalk






Project:	P3 - Widen to Four-Lane Section with Raised Median from Road 4N to Road 5N and Construct Roundabout at Road 5N
Location:	Road 4N to Road 5N
Description:	Widen to four-lane typical urban section, modified to have an 8-foot raised median and 5-foot sidewalk on both sides, from Road 4N roundabout (under construction) to proposed Road 5N Roundabout. This project could be constructed in phases, with the roundabout at Road 5N as the first phase .
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$8,370,000

- Legend**
- ADOT Mile Posts
 - Municipal Boundary
 - Right of Way
 - Parcels


- Project Horizons**
- Near-Term
 - Mid-Term
 - Long-Term



Project:	P4 - Align Approaches at Road 6N
Description:	Reconstruct the east and westbound approaches at the Road 6N intersection so that they align (offset approximately 70 feet).
Primary Purpose(s):	Access Management
Cost:	\$480,000




Project:	P5 - Widen to Four-Lane Section with Graded Median from Old Highway 89 to Frontier Road and Construct Roundabouts at Old Highway 89 and Frontier Road
Description:	Widen to a four-lane facility conforming to ADOT’s fringe urban typical section, with no curb and a standard width, graded median between Old Highway 89 and Frontier Road. Construct two-lane roundabouts at Old Highway 89 and Frontier Road. This project could be constructed in phases, with either/both roundabouts constructed as the first phase.
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$13,190,000



Project:	P5 - Widen to Four-Lane Section with Graded Median from Old Highway 89 to Frontier Road and Construct Roundabouts at Old Highway 89 and Frontier Road
Description:	Widen to a four-lane facility conforming to ADOT’s fringe urban typical section, with no curb and a standard width, graded median between Old Highway 89 and Frontier Road. Construct two-lane roundabouts at Old Highway 89 and Frontier Road. This project could be constructed in phases, with either/both roundabouts constructed as the first phase.
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$13,190,000

Fringe-Urban Highway Typical Section
Figure 306.3 in ADOT RDG







Project:	P5 - Widen to Four-Lane Section with Graded Median from Old Highway 89 to Frontier Road and Construct Roundabouts at Old Highway 89 and Frontier Road
Description:	Widen to a four-lane facility conforming to ADOT’s fringe urban typical section, with no curb and a standard width, graded median between Old Highway 89 and Frontier Road. Construct two-lane roundabouts at Old Highway 89 and Frontier Road. This project could be constructed in phases, with either/both roundabouts constructed as the first phase.
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$13,190,000

Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

Fringe-Urban Highway Typical Section
Figure 306.3 in ADOT RDG






Project:	P5 - Widen to Four-Lane Section with Graded Median from Old Highway 89 to Frontier Road and Construct Roundabouts at Old Highway 89 and Frontier Road
Description:	Widen to a four-lane facility conforming to ADOT’s fringe urban typical section, with no curb and a standard width, graded median between Old Highway 89 and Frontier Road. Construct two-lane roundabouts at Old Highway 89 and Frontier Road. This project could be constructed in phases, with either/both roundabouts constructed as the first phase.
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$13,190,000


Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

Fringe-Urban Highway Typical Section
Figure 306.3 in ADOT RDG



- Legend
- ADOT Mile Posts
-
- Municipal Boundary

Project Horizons

 Near-Term Mid-Term Long-Term

Project:	P5 - Widen to Four-Lane Section with Graded Median from Old Highway 89 to Frontier Road and Construct Roundabouts at Old Highway 89 and Frontier Road
Description:	Widen to a four-lane facility conforming to ADOT’s fringe urban typical section, with no curb and a standard width, graded median between Old Highway 89 and Frontier Road. Construct two-lane roundabouts at Old Highway 89 and Frontier Road. This project could be constructed in phases, with either/both roundabouts constructed as the first phase.
Primary Purpose(s):	Access Management, Safety, Accommodate Future Development
Cost:	\$13,190,000

Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Project Horizons

Near-Term

Mid-Term


Long-Term



Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

Project:	P6 - Construct Left- and Right-Turn Lanes at Little Ranch Road
Description:	Construct left- and right-turn lanes at Little Ranch Road.
Primary Purpose(s):	Access Management and Safety
Cost:	\$1,410,000

- Legend**
- ADOT Mile Posts
 - Municipal Boundary
 - Right of Way
 - Parcels
- Project Horizons**
- Near-Term
 - Mid-Term
 - Long-Term




Project:	P6 - Construct Left- and Right-Turn Lanes at Little Ranch Road
Description:	Construct left- and right-turn lanes at Little Ranch Road.
Primary Purpose(s):	Access Management and Safety
Cost:	\$1,410,000

Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

- Legend**
- ADOT Mile Posts
 - Municipal Boundary
 - Right of Way
 - Parcels

- Project Horizons**
- Near-Term
 - Mid-Term
 - Long-Term



Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Project Horizons

Near-Term

Mid-Term

Long-Term


The map displays an aerial view of a section of State Route 89. A red dashed line indicates the right-of-way. Sweet Valley Rd runs vertically on the left. Old Highway 89 is shown as a curved road on the left side. Two project locations are marked: P10, a circular black sign with 'P10' and a yellow diamond wildlife warning sign, and P7, a circular pink sign with 'P7'. A callout box points to a section of the road with the text 'STIP FY 2018: Design and construct improvements (underway)'. A scale bar at the bottom left shows distances in feet (0 to 400) and miles (0 to 0.1). A north arrow is also present. Shaded areas indicate 'State Trust Land Shaded Blue' and 'Proposed Future Chino Valley Corridor Shaded Purple'.

Page 16 of 25

Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

Project:	P7 - Install Lighting
Description:	Install street lighting at the Paulden post office. Cost and CMF assume spot lighting with four poles. Bundling this project with the currently programmed project should be considered.
Primary Purpose(s):	Safety
Cost:	\$90,000

- Legend**
- ADOT Mile Posts
 - Municipal Boundary
 - Right of Way
 - Parcels
- Project Horizons**
- Near-Term
 - Mid-Term
 - Long-Term




Project:	P8 - Big Chino Road Roundabout
Description:	Construct a two-lane roundabout. This project could be bundled with the roundabout at Bramble Drive or constructed sequentially as needed.
Primary Purpose(s):	Safety, Access Management, Accommodate Future Development
Cost:	\$4,540,000

Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

- Legend
- ADOT Mile Posts
-
- Municipal Boundary

Project Horizons

Near-TermMid-TermLong-Term

Project:	P8 - Big Chino Road Roundabout
Description:	Construct a two-lane roundabout. This project could be bundled with the roundabout at Bramble Drive or constructed sequentially as needed.
Primary Purpose(s):	Safety, Access Management, Accommodate Future Development
Cost:	\$4,540,000

Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000



Legend

ADOT Mile Posts

Municipal Boundary

Right of Way

Parcels

Project Horizons

Near-Term


Mid-Term

Long-Term


Page 20 of 25

Project:	P9 - Bramble Drive Roundabout
Description:	Construct a two-lane roundabout. This project could be bundled with the roundabout at Big Chino Road or constructed sequentially as needed.
Primary Purpose(s):	Safety and Access Management
Cost:	\$5,100,000


Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000



Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000



Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000



Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

● ADOT Mile Posts

▭ Municipal Boundary


▬ Right of Way

▭ Parcels

■ Near-Term

■ Mid-Term

□ Long-Term



Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

● ADOT Mile Posts

▭ Municipal Boundary


▬ Right of Way

▭ Parcels

■ Near-Term

■ Mid-Term

□ Long-Term



Prescott National Forest Shaded Green
Proposed Future Chino Valley Corridor Shaded Purple

Project:	P10 - Install Wildlife Warning Signage
Description:	Install wildlife warning signage from MP 334 to 348.
Primary Purpose(s):	Safety
Cost:	\$3,000

APPENDIX WP2-2
Project Probable Cost Derivation

Butterfield Road to Road 3N	MP	329.00	to MP	329.20
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	6,653	\$2.00	\$13,400
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	739	\$8.00	\$6,000
SAW CUTTING	L.FT.	1,130	\$1.50	\$1,700
EARTHWORK	L.SUM	1	\$3,856.00	\$3,900
ASPHALT SURFACE COURSE	SQ.YD.	6,653	\$6.00	\$40,000
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	277	\$50.00	\$13,900
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	6,864	\$0.50	\$3,500
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$20,000.00	\$20,000
CONCRETE CURB	L.FT.	1,219	\$20.00	\$24,400
CONCRETE CURB AND GUTTER	L.FT.	0	\$15.00	\$0
CONCRETE SIDEWALK	SQ.FT.	10,129	\$3.00	\$30,400
CONCRETE SIDEWALK RAMP	EACH	12	\$2,000.00	\$24,000
CONCRETE DRIVEWAY	SQ.FT.	815	\$15.00	\$12,300
MEDIAN PAVING	SQ.YD.	553	\$60.00	\$33,200
STORM SEWER ALLOWANCE	L.SUM	0	\$0.00	\$0
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL **\$226,700**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$18,200.00	\$18,200
Quality Control (1%)	COST	1.00%	\$2,300.00	\$2,300
Construction Surveying (1.5%)	COST	1.50%	\$3,500.00	\$3,500
Erosion Control (1%)	COST	1.00%	\$2,300.00	\$2,300
Mobilization (12%)	COST	12.00%	\$27,300.00	\$27,300

PROJECTWIDE SUBTOTAL **\$53,600**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$84,100.00	\$84,100
---	------	--------	-------------	----------

PROJECTWIDE TOTAL **\$137,700**

Construction Engineering (9%)	COST	9.00%	\$32,800.00	\$32,800
Construction Contingencies (5%)	COST	5.00%	\$18,300.00	\$18,300
Engineering Design (10%)	COST	10.00%	\$36,500.00	\$36,500
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$87,600**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$37,800.00	\$37,800
---	------	-------	-------------	----------

SUMMARY

ITEM TOTAL	\$226,700
PROJECTWIDE TOTAL	\$137,700
OTHER COST TOTAL	\$87,600
ICAP	\$37,800
TOTAL	\$490,000

Road 3N Roundabout	MP	329.20	to MP	329.20
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	2,600	\$5.00	\$13,000
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	7,200	\$8.00	\$57,600
SAW CUTTING	L.FT.	288	\$1.50	\$500
EARTHWORK	L.SUM	1	\$19,424.00	\$19,500
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	6,899	\$50.00	\$345,000
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	3,000	\$0.50	\$1,500
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$15,000.00	\$15,000
CONCRETE CURB	L.FT.	1,905	\$20.00	\$38,100
CONCRETE CURB AND GUTTER	L.FT.	2,400	\$15.00	\$36,000
CONCRETE SIDEWALK	SQ.FT.	10,685	\$3.00	\$32,100
CONCRETE SIDEWALK RAMP	EACH	16	\$2,000.00	\$32,000
CONCRETE DRIVEWAY	SQ.FT.	2,746	\$15.00	\$41,200
MEDIAN PAVING	SQ.YD.	948	\$60.00	\$56,900
STORM SEWER ALLOWANCE	L.SUM	1	\$200,000.00	\$200,000
TRUCK APRON	SQ.YD.	317	\$135.00	\$42,800

ITEM TOTAL **\$931,200**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$74,500.00	\$74,500
Quality Control (1%)	COST	1.00%	\$9,400.00	\$9,400
Construction Surveying (1.5%)	COST	1.50%	\$14,000.00	\$14,000
Erosion Control (1%)	COST	1.00%	\$9,400.00	\$9,400
Mobilization (12%)	COST	12.00%	\$111,800.00	\$111,800

PROJECTWIDE SUBTOTAL **\$219,100**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$345,100.00	\$345,100
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL **\$564,200**

Construction Engineering (9%)	COST	9.00%	\$134,600.00	\$134,600
Construction Contingencies (5%)	COST	5.00%	\$74,800.00	\$74,800
Engineering Design (10%)	COST	10.00%	\$149,600.00	\$149,600
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$359,000**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$155,100.00	\$155,100
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	\$931,200
PROJECTWIDE TOTAL	\$564,200
OTHER COST TOTAL	\$359,000
ICAP	\$155,100
TOTAL	\$2,010,000

Road 3N to Road 4N	MP	329.20	to MP	330.16
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	2,800	\$5.00	\$14,000
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	27,314	\$8.00	\$218,600
SAW CUTTING	L.FT.	301	\$1.50	\$500
EARTHWORK	L.SUM	1	\$87,100.00	\$87,100
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	32,820	\$50.00	\$1,641,000
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	30,413	\$0.50	\$15,300
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$25,000.00	\$25,000
CONCRETE CURB	L.FT.	10,000	\$20.00	\$200,000
CONCRETE CURB AND GUTTER	L.FT.	9,551	\$15.00	\$143,300
CONCRETE SIDEWALK	SQ.FT.	44,388	\$3.00	\$133,200
CONCRETE SIDEWALK RAMP	EACH	10	\$2,000.00	\$20,000
CONCRETE DRIVEWAY	SQ.FT.	9,268	\$15.00	\$139,100
MEDIAN PAVING	SQ.YD.	118	\$60.00	\$7,100
STORM SEWER ALLOWANCE	L.SUM	1	\$82,000.00	\$82,000
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL **\$2,726,200**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$218,100.00	\$218,100
Quality Control (1%)	COST	1.00%	\$27,300.00	\$27,300
Construction Surveying (1.5%)	COST	1.50%	\$40,900.00	\$40,900
Erosion Control (1%)	COST	1.00%	\$27,300.00	\$27,300
Mobilization (12%)	COST	12.00%	\$327,200.00	\$327,200

PROJECTWIDE SUBTOTAL **\$640,800**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$1,010,100.00	\$1,010,100
---	------	--------	----------------	-------------

PROJECTWIDE TOTAL **\$1,650,900**

Construction Engineering (9%)	COST	9.00%	\$394,000.00	\$394,000
Construction Contingencies (5%)	COST	5.00%	\$218,900.00	\$218,900
Engineering Design (10%)	COST	10.00%	\$437,800.00	\$437,800
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$1,050,700**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$453,800.00	\$453,800
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	<u>\$2,726,200</u>
PROJECTWIDE TOTAL	<u>\$1,650,900</u>
OTHER COST TOTAL	<u>\$1,050,700</u>
ICAP	<u>\$453,800</u>
TOTAL	<u>\$5,890,000</u>

Road 4N to Road 5N	MP	330.24	to MP	331.22
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	1,400	\$5.00	\$7,000
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	25,297	\$8.00	\$202,400
SAW CUTTING	L.FT.	230	\$1.50	\$400
EARTHWORK	L.SUM	1	\$101,000.00	\$101,000
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	31,908	\$50.00	\$1,595,500
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	31,046	\$0.50	\$15,600
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$25,000.00	\$25,000
CONCRETE CURB	L.FT.	10,035	\$20.00	\$200,800
CONCRETE CURB AND GUTTER	L.FT.	9,915	\$15.00	\$148,800
CONCRETE SIDEWALK	SQ.FT.	44,942	\$3.00	\$134,900
CONCRETE SIDEWALK RAMP	EACH	6	\$2,000.00	\$12,000
CONCRETE DRIVEWAY	SQ.FT.	11,463	\$15.00	\$172,000
MEDIAN PAVING	SQ.YD.	0	\$60.00	\$0
STORM SEWER ALLOWANCE	L.SUM	0	\$0.00	\$0
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL **\$2,615,400**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$209,300.00	\$209,300
Quality Control (1%)	COST	1.00%	\$26,200.00	\$26,200
Construction Surveying (1.5%)	COST	1.50%	\$39,300.00	\$39,300
Erosion Control (1%)	COST	1.00%	\$26,200.00	\$26,200
Mobilization (12%)	COST	12.00%	\$313,900.00	\$313,900

PROJECTWIDE SUBTOTAL **\$614,900**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$969,100.00	\$969,100
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL **\$1,584,000**

Construction Engineering (9%)	COST	9.00%	\$378,000.00	\$378,000
Construction Contingencies (5%)	COST	5.00%	\$210,000.00	\$210,000
Engineering Design (10%)	COST	10.00%	\$420,000.00	\$420,000
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$1,008,000**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$435,400.00	\$435,400
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	\$2,615,400
PROJECTWIDE TOTAL	\$1,584,000
OTHER COST TOTAL	\$1,008,000
ICAP	\$435,400
TOTAL	\$5,650,000

Road 5N Roundabout	MP	331.28	to MP	331.28
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	12,149	\$8.00	\$97,200
SAW CUTTING	L.FT.	176	\$1.50	\$300
EARTHWORK	L.SUM	1	\$51,180.00	\$51,200
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	11,719	\$50.00	\$586,000
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	9,233	\$0.50	\$4,700
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$15,000.00	\$15,000
CONCRETE CURB	L.FT.	2,779	\$20.00	\$55,600
CONCRETE CURB AND GUTTER	L.FT.	4,634	\$15.00	\$69,600
CONCRETE SIDEWALK	SQ.FT.	5,000	\$3.00	\$15,000
CONCRETE SIDEWALK RAMP	EACH	16	\$2,000.00	\$32,000
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	1,426	\$60.00	\$85,600
STORM SEWER ALLOWANCE	L.SUM	1	\$200,000.00	\$200,000
TRUCK APRON	SQ.YD.	384	\$135.00	\$51,900

ITEM TOTAL **\$1,264,100**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$101,200.00	\$101,200
Quality Control (1%)	COST	1.00%	\$12,700.00	\$12,700
Construction Surveying (1.5%)	COST	1.50%	\$19,000.00	\$19,000
Erosion Control (1%)	COST	1.00%	\$12,700.00	\$12,700
Mobilization (12%)	COST	12.00%	\$151,700.00	\$151,700

PROJECTWIDE SUBTOTAL **\$297,300**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$468,500.00	\$468,500
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL **\$765,800**

Construction Engineering (9%)	COST	9.00%	\$182,700.00	\$182,700
Construction Contingencies (5%)	COST	5.00%	\$101,500.00	\$101,500
Engineering Design (10%)	COST	10.00%	\$203,000.00	\$203,000
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$487,200**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$210,500.00	\$210,500
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	\$1,264,100
PROJECTWIDE TOTAL	\$765,800
OTHER COST TOTAL	\$487,200
ICAP	\$210,500
TOTAL	\$2,730,000

Road 6N Intersection Realignment	MP	332.35	to MP	332.35
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	1,691	\$8.00	\$13,600
SAW CUTTING	L.FT.	100	\$1.50	\$200
EARTHWORK	L.SUM	1	\$20,400.00	\$20,400
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	3,592	\$50.00	\$179,700
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	500	\$0.50	\$300
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$5,000.00	\$5,000
CONCRETE CURB	L.FT.	0	\$20.00	\$0
CONCRETE CURB AND GUTTER	L.FT.	0	\$15.00	\$0
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	0	\$60.00	\$0
STORM SEWER ALLOWANCE	L.SUM	0	\$0.00	\$0
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL **\$219,200**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$17,600.00	\$17,600
`	COST	1.00%	\$2,200.00	\$2,200
Construction Surveying (1.5%)	COST	1.50%	\$3,300.00	\$3,300
Erosion Control (1%)	COST	1.00%	\$2,200.00	\$2,200
Mobilization (12%)	COST	12.00%	\$26,400.00	\$26,400

PROJECTWIDE SUBTOTAL **\$51,700**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$81,300.00	\$81,300
---	------	--------	-------------	----------

PROJECTWIDE TOTAL **\$133,000**

Construction Engineering (9%)	COST	9.00%	\$31,700.00	\$31,700
Construction Contingencies (5%)	COST	5.00%	\$17,700.00	\$17,700
Engineering Design (10%)	COST	10.00%	\$35,300.00	\$35,300
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$84,700**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$36,600.00	\$36,600
---	------	-------	-------------	----------

SUMMARY

ITEM TOTAL	\$219,200
PROJECTWIDE TOTAL	\$133,000
OTHER COST TOTAL	\$84,700
ICAP	\$36,600
TOTAL	\$480,000

Old Highway 89 Roundabout	MP	333.41	to MP	333.41
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	20,000	\$8.00	\$160,000
SAW CUTTING	L.FT.	136	\$1.50	\$300
EARTHWORK	L.SUM	1	\$30,088.00	\$30,100
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	28,204	\$50.00	\$1,410,300
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	16,000	\$0.50	\$8,000
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$15,000.00	\$15,000
CONCRETE CURB	L.FT.	1,403	\$20.00	\$28,100
CONCRETE CURB AND GUTTER	L.FT.	1,797	\$15.00	\$27,000
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	1,533	\$60.00	\$92,000
STORM SEWER ALLOWANCE	L.SUM	1	\$200,000.00	\$200,000
TRUCK APRON	SQ.YD.	363	\$135.00	\$49,100

ITEM TOTAL **\$2,019,900**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$161,600.00	\$161,600
Quality Control (1%)	COST	1.00%	\$20,200.00	\$20,200
Construction Surveying (1.5%)	COST	1.50%	\$30,300.00	\$30,300
Erosion Control (1%)	COST	1.00%	\$20,200.00	\$20,200
Mobilization (12%)	COST	12.00%	\$242,400.00	\$242,400

PROJECTWIDE SUBTOTAL **\$474,700**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$748,400.00	\$748,400
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL **\$1,223,100**

Construction Engineering (9%)	COST	9.00%	\$291,900.00	\$291,900
Construction Contingencies (5%)	COST	5.00%	\$162,200.00	\$162,200
Engineering Design (10%)	COST	10.00%	\$324,300.00	\$324,300
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$778,400**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$336,200.00	\$336,200
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	<u>\$2,019,900</u>
PROJECTWIDE TOTAL	<u>\$1,223,100</u>
OTHER COST TOTAL	<u>\$778,400</u>
ICAP	<u>\$336,200</u>
TOTAL	<u>\$4,360,000</u>

Old Highway 89 to Frontier Road

	MP	333.41	to MP	334.50
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	25,911	\$8.00	\$207,300
SAW CUTTING	L.FT.	176	\$1.50	\$300
EARTHWORK	L.SUM	1	\$131,504.00	\$131,600
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	39,091	\$50.00	\$1,954,600
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	31,800	\$0.50	\$15,900
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$40,000.00	\$40,000
CONCRETE CURB	L.FT.	0	\$20.00	\$0
CONCRETE CURB AND GUTTER	L.FT.	0	\$15.00	\$0
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	0	\$60.00	\$0
STORM SEWER ALLOWANCE	L.SUM	0	\$0.00	\$0
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL **\$2,349,700**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$188,000.00	\$188,000
Quality Control (1%)	COST	1.00%	\$23,500.00	\$23,500
Construction Surveying (1.5%)	COST	1.50%	\$35,300.00	\$35,300
Erosion Control (1%)	COST	1.00%	\$23,500.00	\$23,500
Mobilization (12%)	COST	12.00%	\$282,000.00	\$282,000

PROJECTWIDE SUBTOTAL **\$552,300**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$870,600.00	\$870,600
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL **\$1,422,900**

Construction Engineering (9%)	COST	9.00%	\$339,600.00	\$339,600
Construction Contingencies (5%)	COST	5.00%	\$188,700.00	\$188,700
Engineering Design (10%)	COST	10.00%	\$377,300.00	\$377,300
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$905,600**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$391,100.00	\$391,100
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	\$2,349,700
PROJECTWIDE TOTAL	\$1,422,900
OTHER COST TOTAL	\$905,600
ICAP	\$391,100
TOTAL	\$5,070,000

Frontier Road Roundabout	MP	334.50	to MP	334.50
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	17,600	\$8.00	\$140,800
SAW CUTTING	L.FT.	172	\$1.50	\$300
EARTHWORK	L.SUM	1	\$55,200.00	\$55,200
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	22,416	\$50.00	\$1,120,800
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	20,000	\$0.50	\$10,000
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$15,000.00	\$15,000
CONCRETE CURB	L.FT.	1,300	\$20.00	\$26,000
CONCRETE CURB AND GUTTER	L.FT.	1,520	\$15.00	\$22,800
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	1,691	\$60.00	\$101,500
STORM SEWER ALLOWANCE	L.SUM	1	\$200,000.00	\$200,000
TRUCK APRON	SQ.YD.	363	\$135.00	\$49,100

ITEM TOTAL **\$1,741,500**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$139,400.00	\$139,400
Quality Control (1%)	COST	1.00%	\$17,500.00	\$17,500
Construction Surveying (1.5%)	COST	1.50%	\$26,200.00	\$26,200
Erosion Control (1%)	COST	1.00%	\$17,500.00	\$17,500
Mobilization (12%)	COST	12.00%	\$209,000.00	\$209,000

PROJECTWIDE SUBTOTAL **\$409,600**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$645,400.00	\$645,400
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL **\$1,055,000**

Construction Engineering (9%)	COST	9.00%	\$251,700.00	\$251,700
Construction Contingencies (5%)	COST	5.00%	\$139,900.00	\$139,900
Engineering Design (10%)	COST	10.00%	\$279,700.00	\$279,700
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$671,300**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$290,000.00	\$290,000
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	<u>\$1,741,500</u>
PROJECTWIDE TOTAL	<u>\$1,055,000</u>
OTHER COST TOTAL	<u>\$671,300</u>
ICAP	<u>\$290,000</u>
TOTAL	<u>\$3,760,000</u>

Little Ranch Road Left-Turn Installation	MP	335.58	to MP	335.92
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	8,311	\$8.00	\$66,500
SAW CUTTING	L.FT.	118	\$1.50	\$200
EARTHWORK	L.SUM	1	\$26,481.48	\$26,500
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	9,766	\$50.00	\$488,300
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	8,800	\$0.50	\$4,400
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	0	\$0.00	\$0
CONCRETE CURB	L.FT.	0	\$20.00	\$0
CONCRETE CURB AND GUTTER	L.FT.	0	\$15.00	\$0
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	0	\$60.00	\$0
STORM SEWER ALLOWANCE	L.SUM	0	\$0.00	\$0
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL **\$585,900**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$46,900.00	\$46,900
Quality Control (1%)	COST	1.00%	\$5,900.00	\$5,900
Construction Surveying (1.5%)	COST	1.50%	\$8,800.00	\$8,800
Erosion Control (1%)	COST	1.00%	\$5,900.00	\$5,900
Mobilization (12%)	COST	12.00%	\$70,400.00	\$70,400

PROJECTWIDE SUBTOTAL **\$137,900**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$217,200.00	\$217,200
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL **\$355,100**

Construction Engineering (9%)	COST	9.00%	\$84,700.00	\$84,700
Construction Contingencies (5%)	COST	5.00%	\$47,100.00	\$47,100
Engineering Design (10%)	COST	10.00%	\$94,100.00	\$94,100
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$225,900**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$97,600.00	\$97,600
---	------	-------	-------------	----------

SUMMARY

ITEM TOTAL	\$585,900
PROJECTWIDE TOTAL	\$355,100
OTHER COST TOTAL	\$225,900
ICAP	\$97,600
TOTAL	\$1,270,000

Little Ranch Road Right-Turn Installation

	MP	335.78	to MP	335.92
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	148	\$8.00	\$1,200
SAW CUTTING	L.FT.	665	\$1.50	\$1,000
EARTHWORK	L.SUM	1	\$29,296.30	\$29,300
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	685	\$50.00	\$34,300
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	1,330	\$0.50	\$700
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	0	\$0.00	\$0
CONCRETE CURB	L.FT.	0	\$20.00	\$0
CONCRETE CURB AND GUTTER	L.FT.	0	\$15.00	\$0
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	0	\$60.00	\$0
STORM SEWER ALLOWANCE	L.SUM	0	\$0.00	\$0
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL **\$66,500**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$5,400.00	\$5,400
Quality Control (1%)	COST	1.00%	\$700.00	\$700
Construction Surveying (1.5%)	COST	1.50%	\$1,000.00	\$1,000
Erosion Control (1%)	COST	1.00%	\$700.00	\$700
Mobilization (12%)	COST	12.00%	\$8,000.00	\$8,000

PROJECTWIDE SUBTOTAL **\$15,800**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$24,700.00	\$24,700
---	------	--------	-------------	----------

PROJECTWIDE TOTAL **\$40,500**

Construction Engineering (9%)	COST	9.00%	\$9,700.00	\$9,700
Construction Contingencies (5%)	COST	5.00%	\$5,400.00	\$5,400
Engineering Design (10%)	COST	10.00%	\$10,700.00	\$10,700
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$25,800**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$11,200.00	\$11,200
---	------	-------	-------------	----------

SUMMARY

ITEM TOTAL	\$66,500
PROJECTWIDE TOTAL	\$40,500
OTHER COST TOTAL	\$25,800
ICAP	\$11,200
TOTAL	\$150,000

Lighting	MP	337.00	to MP	337.10
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	0	\$8.00	\$0
SAW CUTTING	L.FT.	0	\$1.50	\$0
EARTHWORK	L.SUM	0	\$0.00	\$0
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	0	\$50.00	\$0
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	0	\$0.50	\$0
ROADWAY LIGHTING	L.SUM	1	\$40,000.00	\$40,000
LANDSCAPING ALLOWANCE	L.SUM	0	\$0.00	\$0
CONCRETE CURB	L.FT.	0	\$20.00	\$0
CONCRETE CURB AND GUTTER	L.FT.	0	\$15.00	\$0
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	0	\$60.00	\$0
STORM SEWER ALLOWANCE	L.SUM	0	\$0.00	\$0
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL **\$40,000**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$3,200.00	\$3,200
Quality Control (1%)	COST	1.00%	\$400.00	\$400
Construction Surveying (1.5%)	COST	1.50%	\$600.00	\$600
Erosion Control (1%)	COST	1.00%	\$400.00	\$400
Mobilization (12%)	COST	12.00%	\$4,800.00	\$4,800

PROJECTWIDE SUBTOTAL **\$9,400**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$14,900.00	\$14,900
---	------	--------	-------------	----------

PROJECTWIDE TOTAL **\$24,300**

Construction Engineering (9%)	COST	9.00%	\$5,800.00	\$5,800
Construction Contingencies (5%)	COST	5.00%	\$3,300.00	\$3,300
Engineering Design (10%)	COST	10.00%	\$6,500.00	\$6,500
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$15,600**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$6,700.00	\$6,700
---	------	-------	------------	---------

SUMMARY

ITEM TOTAL	\$40,000
PROJECTWIDE TOTAL	\$24,300
OTHER COST TOTAL	\$15,600
ICAP	\$6,700
TOTAL	\$90,000

Big Chino Road Roundabout	MP	337.70	to MP	337.70
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	20,178	\$8.00	\$161,500
SAW CUTTING	L.FT.	124	\$1.50	\$200
EARTHWORK	L.SUM	1	\$56,480.00	\$56,500
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	29,198	\$50.00	\$1,459,900
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	24,400	\$0.50	\$12,200
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$15,000.00	\$15,000
CONCRETE CURB	L.FT.	3,723	\$20.00	\$74,500
CONCRETE CURB AND GUTTER	L.FT.	1,563	\$15.00	\$23,500
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	808	\$60.00	\$48,500
STORM SEWER ALLOWANCE	L.SUM	1	\$200,000.00	\$200,000
TRUCK APRON	SQ.YD.	363	\$135.00	\$49,100

ITEM TOTAL **\$2,100,900**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$168,100.00	\$168,100
Quality Control (1%)	COST	1.00%	\$21,100.00	\$21,100
Construction Surveying (1.5%)	COST	1.50%	\$31,600.00	\$31,600
Erosion Control (1%)	COST	1.00%	\$21,100.00	\$21,100
Mobilization (12%)	COST	12.00%	\$252,200.00	\$252,200

PROJECTWIDE SUBTOTAL **\$494,100**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$778,500.00	\$778,500
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL **\$1,272,600**

Construction Engineering (9%)	COST	9.00%	\$303,700.00	\$303,700
Construction Contingencies (5%)	COST	5.00%	\$168,700.00	\$168,700
Engineering Design (10%)	COST	10.00%	\$337,400.00	\$337,400
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$809,800**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$349,800.00	\$349,800
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	<u>\$2,100,900</u>
PROJECTWIDE TOTAL	<u>\$1,272,600</u>
OTHER COST TOTAL	<u>\$809,800</u>
ICAP	<u>\$349,800</u>
TOTAL	<u>\$4,540,000</u>

Bramble Drive Roundabout	MP	338.81	to MP	338.81
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	24,000	\$8.00	\$192,000
SAW CUTTING	L.FT.	160	\$1.50	\$300
EARTHWORK	L.SUM	1	\$48,960.00	\$49,000
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	33,383	\$50.00	\$1,669,200
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	25,900	\$0.50	\$13,000
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$15,000.00	\$15,000
CONCRETE CURB	L.FT.	4,115	\$20.00	\$82,300
CONCRETE CURB AND GUTTER	L.FT.	1,627	\$15.00	\$24,400
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	1,124	\$60.00	\$67,500
STORM SEWER ALLOWANCE	L.SUM	1	\$200,000.00	\$200,000
TRUCK APRON	SQ.YD.	363	\$135.00	\$49,100

ITEM TOTAL **\$2,361,800**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$189,000.00	\$189,000
Quality Control (1%)	COST	1.00%	\$23,700.00	\$23,700
Construction Surveying (1.5%)	COST	1.50%	\$35,500.00	\$35,500
Erosion Control (1%)	COST	1.00%	\$23,700.00	\$23,700
Mobilization (12%)	COST	12.00%	\$283,500.00	\$283,500

PROJECTWIDE SUBTOTAL **\$555,400**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$875,200.00	\$875,200
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL **\$1,430,600**

Construction Engineering (9%)	COST	9.00%	\$341,400.00	\$341,400
Construction Contingencies (5%)	COST	5.00%	\$189,700.00	\$189,700
Engineering Design (10%)	COST	10.00%	\$379,300.00	\$379,300
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$910,400**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$393,200.00	\$393,200
---	------	-------	--------------	-----------

SUMMARY


ITEM TOTAL	<u>\$2,361,800</u>
PROJECTWIDE TOTAL	<u>\$1,430,600</u>
OTHER COST TOTAL	<u>\$910,400</u>
ICAP	<u>\$393,200</u>
TOTAL	<u>\$5,100,000</u>

APPENDIX WP2-3

2036 Capacity Analysis

HCS 2010 Signalized Intersection Results Summary

General Information				Intersection Information	
Agency	Burgess & Niple			Duration, h	0.25
Analyst	KMS	Analysis Date	May 6, 2016	Area Type	Other
Jurisdiction	ADOT/CYMPO	Time Period	AM Peak Hour - Build Condition	PHF	0.90
Urban Street	SR 89	Analysis Year	2036	Analysis Period	1 > 7:00
Intersection	SR 89 and Road 3N	File Name	01_Road 3N_AM_Build Condition.xus		
Project Description	SR 89 Transportation Study				



Demand Information	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Demand (v), veh/h	70	70	200	60	60	40	90	340	40	20	680	100

Signal Information											
Cycle, s	100.0	Reference Phase	2								
Offset, s	0	Reference Point	End								
Uncoordinated	No	Simult. Gap E/W	On	Green	2.8	4.6	48.6	26.1	0.0	0.0	
Force Mode	Fixed	Simult. Gap N/S	On	Yellow	4.0	0.0	4.0	4.0	0.0	0.0	
				Red	2.0	0.0	2.0	2.0	0.0	0.0	


Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	2.0	4.0	1.1	4.0
Phase Duration, s		32.1		32.1	13.3	59.1	8.8	54.6
Change Period, ($Y+R_c$), s		6.0		6.0	6.0	6.0	6.0	6.0
Max Allow Headway (MAH), s		4.5		4.5	4.0	0.0	4.0	0.0
Queue Clearance Time (g_s), s		18.5		24.4	7.5		2.6	
Green Extension Time (g_e), s		2.1		1.7	0.3	0.0	0.0	0.0
Phase Call Probability		1.00		1.00	0.94		0.46	
Max Out Probability		0.03		0.20	0.00		0.00	

Movement Group Results	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	78	300		67	111		100	214	208	22	443	423
Adjusted Saturation Flow Rate (s), veh/h/ln	1277	1644		1075	1738		1774	1810	1743	1774	1810	1728
Queue Service Time (g_s), s	5.1	16.5		6.0	5.1		5.5	6.3	6.4	0.6	16.7	16.7
Cycle Queue Clearance Time (g_c), s	10.1	16.5		22.4	5.1		5.5	6.3	6.4	0.6	16.7	16.7
Green Ratio (g/C)	0.26	0.26		0.26	0.26		0.07	0.53	0.53	0.51	0.49	0.49
Capacity (c), veh/h	341	428		176	453		130	962	927	551	880	840
Volume-to-Capacity Ratio (X)	0.228	0.700		0.379	0.245		0.770	0.222	0.225	0.040	0.504	0.504
Back of Queue (Q), ft/ln (50 th percentile)	41.4	171.8		42.2	53.9		68.1	61.9	59.6	5.8	172.3	162.8
Back of Queue (Q), veh/ln (50 th percentile)	1.6	6.9		1.7	2.2		2.7	2.4	2.4	0.2	6.8	6.5
Queue Storage Ratio (RQ) (50 th percentile)	0.33	0.00		0.42	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Uniform Delay (d_1), s/veh	33.2	33.4		43.5	29.2		45.5	12.4	12.5	12.0	17.5	17.5
Incremental Delay (d_2), s/veh	0.3	2.6		1.3	0.3		9.2	0.5	0.6	0.0	2.1	2.2
Initial Queue Delay (d_3), s/veh	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Control Delay (d), s/veh	33.5	36.1		44.9	29.5		54.7	13.0	13.0	12.1	19.5	19.6
Level of Service (LOS)	C	D		D	C		D	B	B	B	B	B
Approach Delay, s/veh / LOS	35.5	D		35.2	D		21.0	C		19.4	B	
Intersection Delay, s/veh / LOS	24.4						C					

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.8	C	2.8	C	2.3	B	2.3	B
Bicycle LOS Score / LOS	1.1	A	0.8	A	0.9	A	1.2	A

HCS 2010 Signalized Intersection Results Summary

General Information				Intersection Information	
Agency	Burgess & Niple			Duration, h	0.25
Analyst	KMS	Analysis Date	May 6, 2016	Area Type	Other
Jurisdiction	ADOT/CYMPO	Time Period	PM Peak Hour - Build Condition	PHF	0.90
Urban Street	SR 89	Analysis Year	2036	Analysis Period	1 > 7:00
Intersection	SR 89 and Road 3N	File Name	01_Road 3N_PM_Build Condition.xus		
Project Description	SR 89 Transportation Study				




Demand Information	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Demand (v), veh/h	100	60	130	40	40	20	280	770	60	20	620	40

Signal Information											
Cycle, s	100.0	Reference Phase	2								
Offset, s	0	Reference Point	End								
Uncoordinated	No	Simult. Gap E/W	On	Green	2.8	11.1	43.9	18.2	0.0	0.0	
Force Mode	Fixed	Simult. Gap N/S	On	Yellow	4.0	4.0	4.0	4.0	0.0	0.0	
				Red	2.0	2.0	2.0	2.0	0.0	0.0	

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	2.0	4.0	1.1	4.0
Phase Duration, s		24.2		24.2	25.9	67.0	8.8	49.9
Change Period, (Y+R _c), s		6.0		6.0	6.0	6.0	6.0	6.0
Max Allow Headway (MAH), s		4.4		4.4	4.0	0.0	4.0	0.0
Queue Clearance Time (g _s), s		13.9		17.6	19.0		2.7	
Green Extension Time (g _e), s		1.0		0.6	0.9	0.0	0.0	0.0
Phase Call Probability		1.00		1.00	1.00		0.46	
Max Out Probability		0.35		1.00	0.00		0.04	

Movement Group Results	EB			WB			NB			SB		
Approach Movement	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	111	211		44	67		311	467	455	22	370	363
Adjusted Saturation Flow Rate (s), veh/h/ln	1329	1658		1166	1757		1774	1810	1763	1774	1810	1770
Queue Service Time (g_s), s	7.8	11.9		3.7	3.2		17.0	13.6	13.6	0.7	14.4	14.5
Cycle Queue Clearance Time (g_c), s	11.0	11.9		15.6	3.2		17.0	13.6	13.6	0.7	14.4	14.5
Green Ratio (g/C)	0.18	0.18		0.18	0.18		0.20	0.61	0.61	0.47	0.44	0.44
Capacity (c), veh/h	272	302		146	320		353	1104	1076	386	794	777
Volume-to-Capacity Ratio (X)	0.409	0.698		0.305	0.208		0.881	0.423	0.423	0.058	0.467	0.467
Back of Queue (Q), ft/ln (50 th percentile)	66.3	131.9		28.6	35.4		200.8	125.6	120.7	6.6	153.2	148.2
Back of Queue (Q), veh/ln (50 th percentile)	2.6	5.3		1.1	1.4		7.9	4.9	4.8	0.3	6.0	5.9
Queue Storage Ratio (RQ) (50 th percentile)	0.53	0.00		0.29	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Uniform Delay (d_1), s/veh	39.4	38.3		45.6	34.8		38.9	10.2	10.2	14.4	19.8	19.8
Incremental Delay (d_2), s/veh	1.0	5.1		1.2	0.3		8.8	1.2	1.2	0.1	2.0	2.0
Initial Queue Delay (d_3), s/veh	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Control Delay (d), s/veh	40.4	43.4		46.8	35.1		47.7	11.4	11.5	14.5	21.8	21.8
Level of Service (LOS)	D	D		D	D		D	B	B	B	C	C
Approach Delay, s/veh / LOS	42.4	D		39.8	D		20.6	C		21.6	C	
Intersection Delay, s/veh / LOS	24.7						C					

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.8	C	2.8	C	2.2	B	2.3	B
Bicycle LOS Score / LOS	1.0	A	0.7	A	1.5	A	1.1	A



MOVEMENT SUMMARY

Site: SR 89 & Rd 4N Build - AM

SR 89 & Rd 4N
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	33	3.0	0.232	5.7	LOS A	0.9	24.5	0.16	0.87	27.1
8	T	422	5.0	0.232	5.7	LOS A	0.9	24.5	0.16	0.42	30.4
18	R	22	3.0	0.232	5.7	LOS A	0.9	24.5	0.16	0.55	29.6
Approach		478	4.8	0.232	5.7	LOS A	0.9	24.5	0.16	0.46	30.1
East: Rd 4N											
1	L	44	3.0	0.115	5.8	LOS A	0.3	7.5	0.38	0.86	27.0
6	T	22	3.0	0.115	5.8	LOS A	0.3	7.5	0.38	0.59	30.0
16	R	22	3.0	0.115	5.8	LOS A	0.3	7.5	0.38	0.65	29.5
Approach		89	3.0	0.115	5.8	LOS A	0.3	7.5	0.38	0.74	28.3
North: SR 89											
7	L	11	3.0	0.429	8.6	LOS A	2.2	56.3	0.32	0.87	25.9
4	T	778	5.0	0.429	8.6	LOS A	2.2	56.3	0.32	0.48	28.6
14	R	44	3.0	0.429	8.6	LOS A	2.2	56.3	0.32	0.58	28.0
Approach		833	4.9	0.429	8.6	LOS A	2.2	56.3	0.32	0.49	28.5
West: Rd 4N											
5	L	22	3.0	0.059	7.0	LOS A	0.2	3.9	0.50	0.90	26.5
2	T	11	3.0	0.059	7.0	LOS A	0.2	3.9	0.50	0.69	29.1
12	R	67	3.0	0.112	7.4	LOS A	0.3	7.2	0.49	0.75	28.5
Approach		100	3.0	0.112	7.2	LOS A	0.3	7.2	0.49	0.78	28.1
All Vehicles		1500	4.6	0.429	7.4	LOS A	2.2	56.3	0.28	0.52	28.9

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Thursday, October 20, 2016 8:42:25 AM
SIDRA INTERSECTION 5.1.13.2093
Project: P:\PR54679\Traffic\SR 89 & Rd 4N.sip
8001273, BURGESS & NIPLE, INC., SINGLE

Copyright © 2000-2011 Akcelik and Associates Pty Ltd
www.sidrasolutions.com

SIDRA
INTERSECTION

MOVEMENT SUMMARY

Site: SR 89 & Rd 4N Build - PM

SR 89 & Rd 4N
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	67	3.0	0.485	9.2	LOS A	2.8	71.8	0.26	0.84	25.5
8	T	856	5.0	0.485	9.2	LOS A	2.8	71.8	0.26	0.44	28.2
18	R	67	3.0	0.485	9.2	LOS A	2.8	71.8	0.26	0.55	27.6
Approach		989	4.7	0.485	9.2	LOS A	2.8	71.8	0.26	0.47	27.9
East: Rd 4N											
1	L	22	3.0	0.122	8.1	LOS A	0.3	7.9	0.53	0.92	26.1
6	T	11	3.0	0.122	8.1	LOS A	0.3	7.9	0.53	0.71	28.5
16	R	33	3.0	0.122	8.1	LOS A	0.3	7.9	0.53	0.76	28.1
Approach		67	3.0	0.122	8.1	LOS A	0.3	7.9	0.53	0.81	27.4
North: SR 89											
7	L	22	3.0	0.331	7.2	LOS A	1.5	38.5	0.28	0.87	26.5
4	T	600	5.0	0.331	7.2	LOS A	1.5	38.5	0.28	0.47	29.4
14	R	22	3.0	0.331	7.2	LOS A	1.5	38.5	0.28	0.58	28.8
Approach		644	4.9	0.331	7.2	LOS A	1.5	38.5	0.28	0.49	29.3
West: Rd 4N											
5	L	22	3.0	0.050	6.0	LOS A	0.1	3.3	0.44	0.86	27.0
2	T	11	3.0	0.050	6.0	LOS A	0.1	3.3	0.44	0.62	29.8
12	R	44	3.0	0.065	6.0	LOS A	0.2	4.1	0.42	0.70	29.4
Approach		78	3.0	0.065	6.0	LOS A	0.2	4.1	0.43	0.74	28.6
All Vehicles		1778	4.6	0.485	8.3	LOS A	2.8	71.8	0.28	0.50	28.4

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Thursday, October 20, 2016 8:42:27 AM
SIDRA INTERSECTION 5.1.13.2093
Project: P:\PR54679\Traffic\SR 89 & Rd 4N.sip
8001273, BURGESS & NIPLE, INC., SINGLE

Copyright © 2000-2011 Akcelik and Associates Pty Ltd
www.sidrasolutions.com

SIDRA
INTERSECTION

HCS 2010 Two-Way Stop Control Summary Report


General Information

Analyst	KMS
Agency/Co.	Burgess & Niple
Date Performed	5/2016
Analysis Year	2036
Time Analyzed	AM Peak Hour
Intersection Orientation	North-South
Project Description	SR 89 Transportation Study

Site Information

Intersection	SR 89 & Rolling Hills Rd
Jurisdiction	ADOT/CYMPO
East/West Street	Rolling Hills Road
North/South Street	SR 89
Peak Hour Factor	0.85
Analysis Time Period (hrs)	0.25

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	0	1		0	0	0	0	1	1	0	0	0	1	1
Configuration		L		R						L	T				T	R
Volume (veh/h)		10		60						30	240				520	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																

Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		12		71						35						
Capacity		272		491						951						
v/c Ratio		0.04		0.14						0.04						
95% Queue Length		0.1		0.5						0.1						
Control Delay (s/veh)		18.9		13.6						8.9						
Level of Service (LOS)		C		B						A						
Approach Delay (s/veh)	14.3								1.0							
Approach LOS	B															

HCS 2010 Two-Way Stop Control Summary Report


General Information

Analyst	KMS
Agency/Co.	Burgess & Niple
Date Performed	5/2016
Analysis Year	2036
Time Analyzed	PM Peak Hour
Intersection Orientation	North-South
Project Description	SR 89 Transportation Study

Site Information

Intersection	SR 89 & Rolling Hills Rd
Jurisdiction	ADOT/CYMPO
East/West Street	Rolling Hills Road
North/South Street	SR 89
Peak Hour Factor	0.90
Analysis Time Period (hrs)	0.25

Lanes




Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		1	0	1		0	0	0	0	1	1	0	0	0	1	1
Configuration		L		R						L	T				T	R
Volume (veh/h)		10		30						40	580				390	10
Percent Heavy Vehicles		3		3						3						
Proportion Time Blocked																
Right Turn Channelized	No				No				No				No			
Median Type	Undivided															
Median Storage																

Delay, Queue Length, and Level of Service

Flow Rate (veh/h)		11		33						44						
Capacity		205		620						1110						
v/c Ratio		0.05		0.05						0.04						
95% Queue Length		0.2		0.2						0.1						
Control Delay (s/veh)		23.5		11.1						8.4						
Level of Service (LOS)		C		B						A						
Approach Delay (s/veh)	14.2								0.5							
Approach LOS	B															



MOVEMENT SUMMARY

Site: SR 89 & Big Chino Road -
Build - AM Peak Hour

SR 89 and Big Chino Road
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	76	3.0	0.253	5.8	LOS A	1.1	27.9	0.11	0.85	27.0
8	T	196	3.0	0.253	5.8	LOS A	1.1	27.9	0.11	0.40	30.3
Approach		272	3.0	0.253	5.8	LOS A	1.1	27.9	0.11	0.52	29.3
North: SR 89											
4	T	293	3.0	0.311	6.7	LOS A	1.4	35.9	0.24	0.45	29.7
14	R	22	3.0	0.311	6.7	LOS A	1.4	35.9	0.24	0.54	29.2
Approach		315	3.0	0.311	6.7	LOS A	1.4	35.9	0.24	0.46	29.7
West: Big Chino Road											
5	L	22	3.0	0.349	8.5	LOS A	1.5	38.1	0.48	0.86	25.9
12	R	261	3.0	0.349	8.5	LOS A	1.5	38.1	0.48	0.68	27.9
Approach		283	3.0	0.349	8.5	LOS A	1.5	38.1	0.48	0.69	27.8
All Vehicles		870	3.0	0.349	7.0	LOS A	1.5	38.1	0.28	0.56	28.9

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Thursday, October 20, 2016 8:56:43 AM

SIDRA INTERSECTION 5.1.13.2093

Project: P:\PR54679\Traffic\Proposed Conditions\SR 89 & Big Chino Road.sip

8001273, BURGESS & NIPLE, INC., SINGLE

Copyright © 2000-2011 Akcelik and Associates Pty Ltd

www.sidrasolutions.com

SIDRA
INTERSECTION

MOVEMENT SUMMARY

Site: SR 89 & Big Chino Road -
Build - PM Peak Hour

SR 89 and Big Chino Road
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	272	3.0	0.574	10.7	LOS B	4.1	104.0	0.23	0.76	24.8
8	T	337	3.0	0.574	10.7	LOS B	4.1	104.0	0.23	0.40	27.2
Approach		609	3.0	0.574	10.7	LOS B	4.1	104.0	0.23	0.56	26.0
North: SR 89											
4	T	348	3.0	0.485	10.8	LOS B	2.5	64.4	0.54	0.68	27.3
14	R	54	3.0	0.485	10.8	LOS B	2.5	64.4	0.54	0.73	27.0
Approach		402	3.0	0.485	10.8	LOS B	2.5	64.4	0.54	0.69	27.2
West: Big Chino Road											
5	L	33	3.0	0.198	6.8	LOS A	0.7	18.7	0.46	0.85	26.6
12	R	120	3.0	0.198	6.8	LOS A	0.7	18.7	0.46	0.67	28.9
Approach		152	3.0	0.198	6.8	LOS A	0.7	18.7	0.46	0.71	28.3
All Vehicles		1163	3.0	0.574	10.2	LOS B	4.1	104.0	0.37	0.62	26.7

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Thursday, October 20, 2016 8:56:57 AM

SIDRA INTERSECTION 5.1.13.2093


Project: P:\PR54679\Traffic\Proposed Conditions\SR 89 & Big Chino Road.sip

8001273, BURGESS & NIPLE, INC., SINGLE

Copyright © 2000-2011 Akcelik and Associates Pty Ltd

www.sidrasolutions.com

SIDRA
INTERSECTION



MOVEMENT SUMMARY

Site: SR 89 & Bramble Drive - Build
- AM Peak Hour

SR 89 & Bramble Drive
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	33	3.0	0.201	5.2	LOS A	0.8	20.8	0.08	0.89	27.3
8	T	174	3.0	0.201	5.2	LOS A	0.8	20.8	0.08	0.41	30.8
18	R	11	3.0	0.201	5.2	LOS A	0.8	20.8	0.08	0.51	30.1
Approach		217	3.0	0.201	5.2	LOS A	0.8	20.8	0.08	0.48	30.1
East: Bramble Drive											
1	L	11	3.0	0.026	4.3	LOS A	0.1	2.2	0.32	0.77	27.8
6	T	11	3.0	0.026	4.3	LOS A	0.1	2.2	0.32	0.46	31.1
16	R	1	3.0	0.026	4.3	LOS A	0.1	2.2	0.32	0.53	30.6
Approach		23	3.0	0.026	4.3	LOS A	0.1	2.2	0.32	0.61	29.4
North: SR 89											
7	L	1	3.0	0.086	4.2	LOS A	0.3	7.8	0.15	0.91	27.9
4	T	87	3.0	0.086	4.2	LOS A	0.3	7.8	0.15	0.43	31.4
14	R	1	3.0	0.086	4.2	LOS A	0.3	7.8	0.15	0.52	30.8
Approach		89	3.0	0.086	4.2	LOS A	0.3	7.8	0.15	0.44	31.4
West: Bramble Drive											
5	L	11	3.0	0.133	4.9	LOS A	0.5	12.5	0.23	0.79	27.5
2	T	1	3.0	0.133	4.9	LOS A	0.5	12.5	0.23	0.43	30.8
12	R	120	3.0	0.133	4.9	LOS A	0.5	12.5	0.23	0.51	30.2
Approach		132	3.0	0.133	4.9	LOS A	0.5	12.5	0.23	0.53	30.0
All Vehicles		461	3.0	0.201	4.9	LOS A	0.8	20.8	0.15	0.49	30.3

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Thursday, October 20, 2016 9:01:36 AM

SIDRA INTERSECTION 5.1.13.2093

Project: P:\PR54679\Traffic\Proposed Conditions\SR 89 & Bramble Drive.sip

8001273, BURGESS & NIPLE, INC., SINGLE

Copyright © 2000-2011 Akcelik and Associates Pty Ltd

www.sidrasolutions.com

SIDRA
INTERSECTION

MOVEMENT SUMMARY

Site: SR 89 & Bramble Drive - Build
- PM Peak Hour

SR 89 & Bramble Drive
Roundabout

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: SR 89											
3	L	130	3.0	0.287	6.2	LOS A	1.3	32.8	0.14	0.79	26.8
8	T	152	3.0	0.287	6.2	LOS A	1.3	32.8	0.14	0.39	30.0
18	R	22	3.0	0.287	6.2	LOS A	1.3	32.8	0.14	0.48	29.4
Approach		304	3.0	0.287	6.2	LOS A	1.3	32.8	0.14	0.57	28.4
East: Bramble Drive											
1	L	11	3.0	0.016	4.6	LOS A	0.1	1.3	0.37	0.71	27.6
6	T	1	3.0	0.016	4.6	LOS A	0.1	1.3	0.37	0.47	30.7
16	R	1	3.0	0.016	4.6	LOS A	0.1	1.3	0.37	0.53	30.2
Approach		13	3.0	0.016	4.6	LOS A	0.1	1.3	0.37	0.67	28.0
North: SR 89											
7	L	11	3.0	0.379	8.0	LOS A	1.8	46.0	0.36	0.87	26.2
4	T	315	3.0	0.379	8.0	LOS A	1.8	46.0	0.36	0.52	28.9
14	R	33	3.0	0.379	8.0	LOS A	1.8	46.0	0.36	0.59	28.5
Approach		359	3.0	0.379	8.0	LOS A	1.8	46.0	0.36	0.53	28.8
West: Bramble Drive											
5	L	11	3.0	0.112	5.8	LOS A	0.4	9.9	0.42	0.85	27.2
2	T	11	3.0	0.112	5.8	LOS A	0.4	9.9	0.42	0.57	30.1
12	R	65	3.0	0.112	5.8	LOS A	0.4	9.9	0.42	0.63	29.6
Approach		87	3.0	0.112	5.8	LOS A	0.4	9.9	0.42	0.65	29.3
All Vehicles		763	3.0	0.379	7.0	LOS A	1.8	46.0	0.28	0.56	28.7

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

Processed: Thursday, October 20, 2016 9:03:29 AM

SIDRA INTERSECTION 5.1.13.2093

Project: P:\PR54679\Traffic\Proposed Conditions\SR 89 & Bramble Drive.sip

8001273, BURGESS & NIPLE, INC., SINGLE

Copyright © 2000-2011 Akcelik and Associates Pty Ltd

www.sidrasolutions.com

SIDRA
INTERSECTION

APPENDIX WP2-4

Crash Modification Factors



CMF / CRF Details

CMF ID: 4576

Change left-turn phase to protected phasing on one or more approaches

Description: Change from permissive, permissive/protected, or protected/permissive to protected phasing on one or more approaches at urban signalized intersection

Prior Condition: Permissive, permissive/protected, or protected/permissive phasing.

Category: Intersection traffic control

Study: [*Highway Safety Manual, 1st Edition, Various, 2010*](#)

Star Quality Rating:



Crash Modification Factor (CMF)

Value:

0.01

Adjusted Standard Error:

Unadjusted Standard Error:

0.01

Crash Reduction Factor (CRF)	
Value:	99 (This value indicates a decrease in crashes)
Adjusted Standard Error:	
Unadjusted Standard Error:	1

Applicability	
Crash Type:	Left turn
Crash Severity:	All
Roadway Types:	Not specified
Number of Lanes:	
Road Division Type:	
Speed Limit:	
Area Type:	Urban
Traffic Volume:	
Time of Day:	
<i>If countermeasure is intersection-based</i>	
Intersection Type:	Roadway/roadway (not interchange related)
Intersection Geometry:	3-leg,4-leg
Traffic Control:	Signalized

Major Road Traffic Volume:	
Minor Road Traffic Volume:	

Development Details	
Date Range of Data Used:	
Municipality:	
State:	
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	

Other Details	
Included in Highway Safety Manual?	
Date Added to Clearinghouse:	
Comments:	Crash type is for left-turn crashes on treated approaches.

The information contained in the Crash Modification Factors (CMF) Clearinghouse is disseminated under the sponsorship of the U.S. Department of Transportation in the interest of information exchange. The U.S. Government assumes no liability for the use of the information contained in the CMF Clearinghouse. The information contained in the CMF Clearinghouse does not constitute a standard, specification, or regulation, nor is it a substitute for sound engineering judgment.



CMF / CRF Details

CMF ID: 4194

Conversion of signalized intersection into single- or multi-lane roundabout

Description:

Prior Condition: Signalized intersection

Category: Intersection geometry

Study: [Safety Effectiveness of Converting Signalized Intersections to Roundabouts, Gross et al., 2012](#)

Star Quality Rating:



[\[View score details\]](#)

Crash Modification Factor (CMF)

Value: 0.81

Adjusted Standard Error:

Unadjusted Standard Error:

0.06

Crash Reduction Factor (CRF)

Value:	19 (<i>This value indicates a decrease in crashes</i>)
Adjusted Standard Error:	
Unadjusted Standard Error:	6

Applicability	
Crash Type:	All
Crash Severity:	All
Roadway Types:	Not Specified
Number of Lanes:	2
Road Division Type:	
Speed Limit:	15-35 mph
Area Type:	Urban and suburban
Traffic Volume:	
Time of Day:	All
<i>If countermeasure is intersection-based</i>	
Intersection Type:	Roadway/roadway (not interchange related)
Intersection Geometry:	3-leg,4-leg
Traffic Control:	Roundabout
Major Road Traffic Volume:	5300 to 52500 Annual Average Daily Traffic (AADT)

Minor Road Traffic Volume:	
-----------------------------------	--

Development Details	
Date Range of Data Used:	2000 to 2009
Municipality:	
State:	CO, FL, IN, MD, MI, NY, NC, SC, VT, WA
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	Sites
Before Sample Size Used:	16 Sites
After Sample Size Used:	16 Sites

Other Details	
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	Conversion to 2-lane roundabout

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Carolina Highway Safety Research Center

The information contained in the Crash Modification Factors (CMF) Clearinghouse is disseminated under the sponsorship of the U.S. Department of Transportation in the interest of information exchange. The U.S. Government assumes no liability for the use of the information contained in the CMF Clearinghouse. The information contained in the CMF Clearinghouse does not constitute a standard, specification, or regulation, nor is it a substitute for sound engineering judgment.



CMF / CRF Details

CMF ID: 4695

Convert high-speed rural intersection to roundabout

Description: Convert high-speed rural intersection to roundabout

Prior Condition: Stop controlled intersection (3 or 4 leg)

Category: Intersection geometry

Study: [*A Statistical Analysis and Development of a Crash Prediction Model for Roundabouts on High-Speed Rural Roadways, Isebrands, 2012*](#)

Star Quality Rating:



[\[View score details\]](#)

Crash Modification Factor (CMF)

Value: 0.33

Adjusted Standard Error:

Unadjusted Standard Error:

Crash Reduction Factor (CRF)

Value:	67 (This value indicates a decrease in crashes)
Adjusted Standard Error:	
Unadjusted Standard Error:	

Applicability	
Crash Type:	All
Crash Severity:	All
Roadway Types:	Not specified
Number of Lanes:	1 to 2
Road Division Type:	
Speed Limit:	40-65 mph
Area Type:	Rural
Traffic Volume:	
Time of Day:	
<i>If countermeasure is intersection-based</i>	
Intersection Type:	Roadway/roadway (not interchange related)
Intersection Geometry:	3-leg,4-leg
Traffic Control:	Roundabout
Major Road Traffic Volume:	

Minor Road Traffic Volume:	
-----------------------------------	--

Development Details	
Date Range of Data Used:	
Municipality:	
State:	KS, MD, MN, OR, WA, WI
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	Site-years
Before Sample Size Used:	98 Site-years
After Sample Size Used:	98 Site-years

Other Details	
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Carolina Highway Safety Research Center

The information contained in the Crash Modification Factors (CMF) Clearinghouse is disseminated under the sponsorship of the U.S. Department of Transportation in the interest of information exchange. The U.S. Government assumes no liability for the use of the information contained in the CMF Clearinghouse. The information contained in the CMF Clearinghouse does not constitute a standard, specification, or regulation, nor is it a substitute for sound engineering judgment.



CMF / CRF Details

CMF ID: 285

Provide a right-turn lane on one major-road approach

Description:

Prior Condition: *No Prior Condition(s)*

Category: Intersection geometry

Study: [*Safety Effectiveness of Intersection Left- and Right-Turn Lanes, Harwood et al., 2002*](#)

Star Quality Rating:



Crash Modification Factor (CMF)

Value: 0.86

Adjusted Standard Error: 0.06

Unadjusted Standard Error: 0.05

Crash Reduction Factor (CRF)

Value:	14 (<i>This value indicates a decrease in crashes</i>)
Adjusted Standard Error:	6
Unadjusted Standard Error:	5

Applicability	
Crash Type:	All
Crash Severity:	All
Roadway Types:	Not Specified
Number of Lanes:	
Road Division Type:	
Speed Limit:	
Area Type:	All
Traffic Volume:	
Time of Day:	
<i>If countermeasure is intersection-based</i>	
Intersection Type:	Roadway/roadway (not interchange related)
Intersection Geometry:	3-leg,4-leg
Traffic Control:	Stop-controlled
Major Road Traffic Volume:	1500 to 40600 Average Daily Traffic (ADT)

Minor Road Traffic Volume:

25 to 26000 Average Daily Traffic (ADT)

Development Details**Date Range of Data Used:****Municipality:****State:****Country:****Type of Methodology Used:**

Before/after using empirical Bayes or full Bayes

Sample Size Used:**Other Details****Included in Highway Safety Manual?**

Yes. HSM lists this CMF in **bold** font to indicate that it has the highest reliability since it has an adjusted standard error of 0.1 or less.

Date Added to Clearinghouse:**Comments:**

Countermeasure name changed to match HSM

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Carolina Highway Safety Research Center

The information contained in the Crash Modification Factors (CMF) Clearinghouse is disseminated under the sponsorship of the U.S. Department of Transportation in the interest of information exchange. The U.S. Government assumes no liability for the

use of the information contained in the CMF Clearinghouse. The information contained in the CMF Clearinghouse does not constitute a standard, specification, or regulation, nor is it a substitute for sound engineering judgment.



CMF / CRF Details

CMF ID: 7774

Install lighting

Description:

Prior Condition: Roadways without street lighting

Category: Highway lighting

Study: [*Validation and Application of Highway Safety Manual \(Part D\) in Florida, Abdel-Aty et al., 2014*](#)

Star Quality Rating:



[\[View score details\]](#)

Crash Modification Factor (CMF)

Value:	0.63
Adjusted Standard Error:	
Unadjusted Standard Error:	0.12

Crash Reduction Factor (CRF)

Value:	37 (This value indicates a decrease in crashes)
Adjusted Standard Error:	
Unadjusted Standard Error:	12

Applicability	
Crash Type:	All
Crash Severity:	Fatal,Serious injury,Minor injury
Roadway Types:	All
Number of Lanes:	
Road Division Type:	All
Speed Limit:	
Area Type:	All
Traffic Volume:	
Time of Day:	Night
<i>If countermeasure is intersection-based</i>	
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	

**Minor Road Traffic
Volume:**

Development Details

**Date Range of Data
Used:**

2006 to 2010

Municipality:

State:

FL

Country:

USA

**Type of Methodology
Used:**

Before/after using empirical Bayes or full Bayes

Sample Size Used:

Other Details

**Included in Highway
Safety Manual?**

No

**Date Added to
Clearinghouse:**

Mar-08-2016

Comments:

CMFs of adding lighting on all roads types with all number of lanes.

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Carolina Highway Safety Research Center

The information contained in the Crash Modification Factors (CMF) Clearinghouse is disseminated under the sponsorship of the U.S. Department of Transportation in the interest of information exchange. The U.S. Government assumes no liability for the

use of the information contained in the CMF Clearinghouse. The information contained in the CMF Clearinghouse does not constitute a standard, specification, or regulation, nor is it a substitute for sound engineering judgment.



CMF / CRF Details

CMF ID: 7775

Install lighting

Description:

Prior Condition: Roadways without street lighting

Category: Highway lighting

Study: [*Validation and Application of Highway Safety Manual \(Part D\) in Florida, Abdel-Aty et al., 2014*](#)

Star Quality Rating:



[\[View score details\]](#)

Crash Modification Factor (CMF)

Value: 0.84

Adjusted Standard Error:

Unadjusted Standard Error:

0.18

Crash Reduction Factor (CRF)

Value:	16 (<i>This value indicates a decrease in crashes</i>)
Adjusted Standard Error:	
Unadjusted Standard Error:	18

Applicability	
Crash Type:	All
Crash Severity:	Property damage only (PDO)
Roadway Types:	All
Number of Lanes:	
Road Division Type:	All
Speed Limit:	
Area Type:	All
Traffic Volume:	
Time of Day:	Night
<i>If countermeasure is intersection-based</i>	
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	

**Minor Road Traffic
Volume:**

Development Details

**Date Range of Data
Used:**

2006 to 2010

Municipality:

State:

FL

Country:

USA

**Type of Methodology
Used:**

Before/after using empirical Bayes or full Bayes

Sample Size Used:

Other Details

**Included in Highway
Safety Manual?**

No

**Date Added to
Clearinghouse:**

Mar-08-2016

Comments:

CMFs of adding lighting on all roads types with all number of lanes.

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Carolina Highway Safety Research Center

The information contained in the Crash Modification Factors (CMF) Clearinghouse is disseminated under the sponsorship of the U.S. Department of Transportation in the interest of information exchange. The U.S. Government assumes no liability for the

use of the information contained in the CMF Clearinghouse. The information contained in the CMF Clearinghouse does not constitute a standard, specification, or regulation, nor is it a substitute for sound engineering judgment.



CMF / CRF Details

CMF ID: 2514

Replace TWLTL with raised median

Description:

Prior Condition: Two way left turn lane (TWLTL)

Category: Access management

Study: [Modeling and Evaluating the Safety Impacts of Access Management \(AM\) Features in the Las Vegas Valley, Mauga and Kaseko, 2010](#)

Star Quality Rating:



[\[View score details\]](#)

Crash Modification Factor (CMF)

Value: 0.77

Adjusted Standard Error:

Unadjusted Standard Error:

0.0616

Crash Reduction Factor (CRF)

Value:	23 (This value indicates a decrease in crashes)
Adjusted Standard Error:	
Unadjusted Standard Error:	6.16

Applicability	
Crash Type:	Angle,Fixed object,Head on,Rear end,Run off road,Sideswipe,Single vehicle
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	
Road Division Type:	All
Speed Limit:	30-45
Area Type:	Urban
Traffic Volume:	4883 to 96080
Time of Day:	Not specified
<i>If countermeasure is intersection-based</i>	
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	

**Minor Road Traffic
Volume:**

Development Details

**Date Range of Data
Used:**

2002 to 2006

Municipality:

State:

NV

Country:

**Type of Methodology
Used:**

Regression cross-section

Sample Size Used:

Crashes

Other Details

**Included in Highway
Safety Manual?**

No

**Date Added to
Clearinghouse:**

Comments:

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Carolina Highway Safety Research Center

The information contained in the Crash Modification Factors (CMF) Clearinghouse is disseminated under the sponsorship of the U.S. Department of Transportation in the interest of information exchange. The U.S. Government assumes no liability for the use of the information contained in the CMF Clearinghouse. The information contained

in the CMF Clearinghouse does not constitute a standard, specification, or regulation, nor is it a substitute for sound engineering judgment.



CMF / CRF Details

CMF ID: 7569

Convert 2 lane roadway to 4 lane divided roadway

Description: Conversion of urban and rural two-lane roadways to four-lane divided roadways

Prior Condition: 2 lane roadway

Category: Roadway

Study: [*Evaluation of the Safety Effectiveness of the Conversion of Two-Lane Roadways to Four-Lane Divided Roadways: Bayesian vs. Empirical Bayes, Ahmed et al., 2015*](#)

Star Quality Rating:



[\[View score details\]](#)

Crash Modification Factor (CMF)

Value:

0.712

Adjusted Standard Error:

Unadjusted Standard Error:

0.076

Crash Reduction Factor (CRF)	
Value:	28.79 (<i>This value indicates a decrease in crashes</i>)
Adjusted Standard Error:	
Unadjusted Standard Error:	7.65

Applicability	
Crash Type:	All
Crash Severity:	All
Roadway Types:	Not specified
Number of Lanes:	2
Road Division Type:	Undivided
Speed Limit:	
Area Type:	Rural
Traffic Volume:	
Time of Day:	All
<i>If countermeasure is intersection-based</i>	
Intersection Type:	
Intersection Geometry:	
Traffic Control:	

Major Road Traffic Volume:	
Minor Road Traffic Volume:	

Development Details	
Date Range of Data Used:	2002 to 2012
Municipality:	
State:	FL
Country:	USA
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	

Other Details	
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Carolina Highway Safety Research Center

The information contained in the Crash Modification Factors (CMF) Clearinghouse is

disseminated under the sponsorship of the U.S. Department of Transportation in the interest of information exchange. The U.S. Government assumes no liability for the use of the information contained in the CMF Clearinghouse. The information contained in the CMF Clearinghouse does not constitute a standard, specification, or regulation, nor is it a substitute for sound engineering judgment.

APPENDIX WP2-5
Public Involvement Summary

State Route 89 Chino Valley to Forest Boundary Transportation Study

(Perkinsville Road to two miles north of Bramble Drive in Paulden)

February 2017

Prepared by
Arizona Department of Transportation
206 S. 17th Ave.
Phoenix, AZ 85007

Contents

1.0	Introduction	3
2.0	Public Information Meetings	3
2.1	Outreach	3
2.2	Notifications	4
2.3	Outreach Meetings	4
2.4	Title VI	4
3.0	Public Comment Summary.....	4
3.1	Summary of Comments	5
4.0	Appendix.....	6

Stakeholder Outreach Plan

Meeting notifications, newspaper ad and mailer/postcard

Title VI reports and public meeting summaries for each meeting, including written comments received at the meeting, sign-in sheets

Media clips about the study

Public Information Meeting Summary

1.0 Introduction

The Arizona Department of Transportation (ADOT) in association with the Central Yavapai Metropolitan Planning Organization (CYMPO), Yavapai County, the Town of Chino Valley, and Federal Highway Administration (FHWA), issued a study to develop a vision for safety and performance improvements on a 13-mile segment of State Route 89 between Perkinsville Road in Chino Valley to two miles north of Bramble Drive in Paulden.

In order to improve safety and operational efficiency along SR 89, the study's purpose was to identify access, mobility, safety and expansion needs for the corridor. The recommendations were then prioritized for the short-term (five-year), mid-term (ten-year) and long-term (twenty-year) time periods.

The study began in May of 2016 and was complete by March 2017. Extensive outreach was done throughout the study. Initially, a public outreach plan was prepared and followed throughout the study process.

Study outreach included the following:

- Newspaper ad published in the Chino Valley Review on Wednesday, Dec. 7 and Dec. 21
- Postcard mailed to 2,500 residents, business owners along the corridor that were within ¼ mile of the project
- Gov Delivery email blast about the meeting to over 3,881 stakeholders was sent out on 1-4-17 as a reminder of the four scheduled meetings
- Study webpage was created: azdot.gov/pauldenstudy
- Information through the Paulden Post Office, Family Dollar store, local gas stations, McDonald's in Chino Valley, Town of Chino Valley, Urgent Care in Chino Valley

2.0 Public Information Meetings

ADOT held four meetings to provide study information and answer questions with the general public. The four outreach meetings were held on Thursday, Jan. 5 at the Paulden Christian Fellowship Church at 165 Aspen Road, Paulden, AZ 86334; Tuesday, Jan. 10 at council chambers at the Town of Chino Valley, 202 N. SR 89, Chino Valley, AZ 86332; Wednesday, Feb. 1 at the Yavapai County Board of Supervisors meeting, 1015 Fair Street, Prescott, AZ 86305 and Wednesday, Feb. 15 at the Central Yavapai Metropolitan Planning Organization (CYMPO) board meeting at 1015 Fair Street, Prescott, AZ 86305. The biggest attendance was at the first meeting in Paulden at the PACO meeting. A full summary of each of the meetings is detailed in the Title VI report.

2.1 Outreach

The study team prepared an extensive outreach schedule to ensure all Title VI requirements were met and that proper notifications were provided for the upcoming meetings.

Public Information Meeting Summary

The study mailer was mailed out on Dec. 1 to 2,500 addresses within a ¼ mile radius along the study corridor. This flier introduced the study and invited residents and businesses to attend one of the upcoming public information meetings.

2.2 Notifications

- Newspaper ad published in the Chino Valley Review on Wednesday, Dec. 7 and Dec. 21
- Postcard mailed to 2,500 residents, business owners along the corridor that were within ¼ mile of the project
- Gov Delivery email blast about the meeting to over 3,881 stakeholders on January 4, 2017
- Project webpage was created: azdot.gov/pauldenstudy
- Study and meeting notifications were hand-delivered in Paulden and Chino Valley. Locations include the Paulden Post Office, Family Dollar store, local gas stations, McDonald's in Chino Valley, Town of Chino Valley, Urgent Care, Pharmacy, ShopCo and Ace Valley hardware
- Local media outlets covered the meeting announcements such as the Daily Courier, KYCA AM 1490, Yavapai Broadcasting and eNews of Prescott/Chino Valley
- The Daily Courier and Chino Valley Review announced the meetings on January 5, 2017
- The Chino Valley Review and the Daily Courier ran a follow up story on January 11, 2017 about the Paulden meeting

2.3 Outreach Meetings

The purpose of the four meetings was to inform the local community about the transportation study. The intent behind each of the four meetings was to partner with the local jurisdictions (CYMPO, the Town of Chino Valley and Yavapai County) who were also working along-side ADOT during the study. Feedback was encouraged to help offer suggestions for necessary improvements that address safety, access, mobility, and capacity issues.

2.4 Title VI

Title VI information was presented at the beginning of the slide show. Mentions were made of information and survey cards that were made available at each meeting (photos attached). This included an English and Spanish brochure as well as self-identification surveys. A Title VI Summary was prepared for each the four meetings (attached).

3.0 Public Comment Summary

Written questions and concerns were presented and addressed during each meeting. Many concerns were from residents who want to see intersection improvements throughout the corridor, some were of the lack of acceptance of roundabouts and other comments were made about the timing for the widening of SR 89.

Public Information Meeting Summary

Written comments received during the meetings are located as part of the documents received from each meeting. Each meeting has a public meeting summary, Title VI summary, written comments (if received) and sign-in sheets.

Comments were classified into the following categories:

- Roundabouts & Locations
- Timing of widening project/s
- Concern for need for turn lanes along the corridor
- Safety concerns
- Concern for wildlife corridors

3.1 Summary of Comments

- Roundabouts and Location
 - Many questions were about roundabout locations and why couldn't a signal be placed instead?
 - Roundabouts are not safe, signals are better
 - Where will the new roundabouts be located
 - Some of the public expressed operational concerns with roundabouts, but most appeared to accept the safety benefits after receiving explanation from the Study Team
- Timing of widening project
 - ADOT was informative and up front about the lack of current funding for this study
 - ADOT reminded the public that this is a high-level planning study
 - ADOT would look at doing a few improvement projects now, based on the need and dependent upon funding availability
- Concerns for turn-lanes along the corridor
 - Many residents voiced concerns for the need for turn lanes at Buffalo Run and South end of Old Hwy 89 and at Little Ranch Road
- Wildlife Corridors
 - A few people were vocal about the desire for wildlife corridors to help with keeping the antelope population strong

APPENDIX

Stakeholder outreach plan

Meeting notifications: Newspaper ad, postcard/mailer

Title VI reports and summaries for each meeting

Written comments

Sign-in sheets

Media clips

**SR89 Chino Valley to Forest Boundary Transportation Study
Public and Stakeholder Outreach Plan**

Task	Responsible Parties	Description	Start	Finish
Create / Update Study Website	Tricia / Jason	-Jason to provide Tricia with approved deliverables (content). -Tricia to work with WebTeam to create/update.	May 2016	February 2017
Study Notification	Tricia / Core Study Team	-Tricia to provide notification to direct interested public/ stakeholders to the Study Website and sign up for the GovDelivery study email list. -Core Study Team to review message.	September 2016	February 2017
Public / Stakeholder Review of Draft Alternatives and Access Management	Tricia / Core Study Team	-Tricia to prepare Newspaper Ads and GovDelivery email blasts to notify public/stakeholders to review the draft alternatives, draft access management plan, and notify of upcoming meetings. -Core Study Team to review ad/email messages.	September 2016	December 2016
Draft Alternatives and Access Management Plan Presentations	Jason / Tricia / District / Dan	-Jason to provide draft Plan of Improvements (Working Paper 2). -Tricia to prepare presentation. -District and Dan to present to PACO, County Board, and Chino Council. -Tricia to document public feedback.	October 2016	December 2016
Public/Stakeholder Outreach Summary Report	Tricia / Core Study Team	-Tricia to prepare a Public/Stakeholder Outreach Summary Report based on input received. -Core Study Team to review.	January 2017	March 2017
Draft/Final Report Outreach	Dan / Tricia / Core Study Team	-Dan to prepare email blast when the Draft Report (for review) and Final Report (for record) are available. -Core Study Team to review message. -Tricia to distribute to Stakeholder list.	February 2017	March 2017



Invoice No.	Quote
Invoice Date:	October 27, 2016
Bill To:	ADOT Tricia Lewis
Address:	
Phone:	928-606-2420
E-mail:	Tlewis@azdot.gov
Fax:	

Make all checks payable to Prescott Newspapers Inc.
Total due upon receipt. Overdue accounts subject to a service charge of 2% per month.

Thank you for your business!



SR 89 Chino Valley to Forest Boundary Transportation Study

Perkinsville Road to two miles north of Bramble Drive in Paulden

The Arizona Department of Transportation is studying a 13-mile segment of State Route 89, between Perkinsville in Chino Valley and two miles north of Bramble Drive in Paulden. The purpose of this long-range planning study is to help identify future roadway improvements as funding becomes available.

Your input is needed! You can learn more about the study and provide comments at the following meetings:

- **Paulden Area Community Organization (PACO):** 7 p.m. Thursday, Jan. 5, 2017, at the Paulden Christian Fellowship Church, 165 Aspen Road, Paulden 86334
- **Town of Chino Valley Council Meeting:** 6 p.m. Tuesday, Jan. 10, at council chambers, 202 N. State Route 89, Chino Valley, 86332
- **Yavapai County Board of Supervisors Meeting:** 9 a.m. Wednesday, Feb. 1, 1015 Fair Street, Prescott, 86305
- **Central Yavapai Metropolitan Planning Organization (CYMPO) Board Meeting:** 4 p.m., Wednesday, Feb. 15, at 1015 Fair Street, Prescott, 86305


(Note: Each meeting will cover the same information)

For additional study details, or to sign up to receive study emails, please visit:

azdot.gov/PauldenStudy

Pursuant to Title VI of the Civil Rights Act of 1964, and the Americans with Disabilities Act (ADA), ADOT does not discriminate on the basis of race, color, national origin, age, sex or disability. Persons who require a reasonable accommodation based on language or disability should contact Tricia Lewis at 928.606.2420 or email TLewis@azdot.gov. Requests should be made as early as possible to ensure the state has an opportunity to address the accommodation.

De acuerdo con el título VI de la Ley de Derechos Civiles de 1964 y la Ley de Estadounidenses con Discapacidades (ADA por sus siglas en inglés), el Departamento de Transporte de Arizona (ADOT por sus siglas en inglés) no discrimina por raza, color, nacionalidad, edad, género o discapacidad. Personas que requieren asistencia (dentro de lo razonable) ya sea por el idioma o por discapacidad deben ponerse en contacto con Tricia Lewis al 928.606.2420 o por correo electrónico al TLewis@azdot.gov. Las solicitudes deben hacerse lo más pronto posible para asegurar que el equipo encargado del proyecto tenga la oportunidad de hacer los arreglos necesarios.



FOR MORE INFORMATION, CONTACT:
Tricia Lewis, senior community relations officer,
ADOT Northwest District
TLewis@azdot.gov or 928.606.2420

Appendix A – Study Mailer



SR 89 Chino Valley to Forest Boundary Transportation Study Perkinsville Road to two miles north of Bramble Drive in Paulden

The Arizona Department of Transportation is studying a 13-mile segment of State Route 89, between Perkinsville in Chino Valley and two miles north of Bramble Drive in Paulden. The purpose of this long-range planning study is to help identify future roadway improvements as funding becomes available.

Your input is needed! You can learn more about the study and provide comments at the following meetings:

- Paulden Area Community Organization (PACO): 7 p.m., Thursday, Jan. 5, 2017, at the Paulden Christian Fellowship Church, 165 Aspen Road, Paulden 86334
- Town of Chino Valley Council Meeting: 6 p.m., Tuesday, Jan. 10, at council chambers, 202 N. State Route 89, Chino Valley, 86332
- Yavapai County Board of Supervisors Meeting: 9 a.m., Wednesday, Feb. 1, 1015 Fair Street, Prescott, 86305
- Central Yavapai Metropolitan Planning Organization (CYMPO) Board Meeting: 4 p.m., Wednesday, Feb. 15, at 1015 Fair Street, Prescott, 86305

(Note: Each meeting will cover the same information)

For additional study details, or to sign up to receive study emails, please visit our website at:
azdot.gov/PauldenStudy



FOR MORE INFORMATION, CONTACT:
Tricia Lewis, senior community relations officer, ADOT Northwest District
TLewis@azdot.gov or 928.606.2420



16-313 Postcard SR 89 Paulden Study.indd 1

11/18/2016 11:55:45 AM



ADOT Communications
1655 W. Jackson St., MD 126F
Phoenix, AZ 85007

**Your input is needed! SR 89 Chino Valley to
Forest Boundary Transportation Study**

Pursuant to Title VI of the Civil Rights Act of 1964, and the Americans with Disabilities Act (ADA), ADOT does not discriminate on the basis of race, color, national origin, age, sex or disability. Persons who require a reasonable accommodation based on language or disability should contact Tricia Lewis at 928.606.2420 or email TLewis@azdot.gov. Requests should be made as early as possible to ensure the state has an opportunity to address the accommodation.

De acuerdo con el Título VI de la Ley de Derechos Civiles de 1964 y la Ley de Estadounidenses con Discapacidades (ADA por sus siglas en inglés), el Departamento de Transporte de Arizona (ADOT por sus siglas en inglés) no discrimina por raza, color, nacionalidad, edad, género o discapacidad. Personas que requieren asistencia (dentro de lo razonable) ya sea por el idioma o por discapacidad deben ponerse en contacto con Tricia Lewis al 928.606.2420 o por correo electrónico al TLewis@azdot.gov. Las solicitudes deben hacerse lo más pronto posible para asegurar que el equipo encargado del proyecto tenga la oportunidad de hacer los arreglos necesarios.

16-313 Postcard SR 89 Paulden Study.indd 2

11/18/2016 11:55:45 AM



MPD0034-16
ADOT Project No. P8600 70P

**State Route 89 Chino Valley to Forest Boundary Transportation Study
Road 3 North to two miles north of Bramble Drive in Paulden**

The Arizona Department of Transportation is studying a 13-mile segment of State Route 89, between Road 3 North in Chino Valley and two miles north of Bramble Drive in Paulden. The purpose of this long-range planning study is to help identify future roadway improvements as funding becomes available.

Your input is needed! You can learn more about the study and provide comments at the following meetings:

- Paulden Area Community Organization (PACO): 7 p.m., Thursday, Jan. 5, at the Paulden Christian Fellowship Church, 165 Aspen Road, Paulden 86334
- Town of Chino Valley Council Meeting: 6 p.m., Tuesday, Jan. 10, at council chambers, 202 N. State Route 89, Chino Valley, 86332
- Yavapai County Board of Supervisors Meeting: 9 a.m., Wednesday, Feb. 1, 1015 Fair Street, Prescott, 86305
- Central Yavapai Metropolitan Planning Organization (CYMPO) Board Meeting: 4 p.m., Wednesday, Feb. 15, at 1015 Fair Street, Prescott, 86305

(Note: Each meeting will cover the same information)

For additional study details, or to sign up to receive study emails, please visit our website at:
www.azdot.gov/Pauldenstudy

Pursuant to Title VI of the Civil Rights Act of 1964, and the Americans with Disabilities Act (ADA), ADOT does not discriminate on the basis of race, color, national origin, age, sex or disability. Persons who require a reasonable accommodation based on language or disability should contact Tricia Lewis at 928.606.2420 or email tlewis@azdot.gov. Requests should be made as early as possible to ensure the state has an opportunity to address the accommodation.

De acuerdo con el título VI de la Ley de Derechos Civiles de 1964 y la Ley de Estadounidenses con Discapacidades (ADA por sus siglas en inglés), el Departamento de Transporte de Arizona (ADOT por sus siglas en inglés) no discrimina por raza, color, nacionalidad, edad, género o discapacidad. Personas que requieren asistencia (dentro de lo razonable) ya sea por el idioma o por discapacidad deben ponerse en contacto con Tricia Lewis al 928.606.2420 o por correo electrónico al tlewis@azdot.gov. Las solicitudes deben hacerse lo más pronto posible para asegurar que el equipo encargado del proyecto tenga la oportunidad de hacer los arreglos necesarios.

**CONTACT: Tricia Lewis, senior community relations officer
ADOT-Northwest District
928-606-2420 or tlewis@azdot.gov**

**State Route 89 Chino Valley to Forest Boundary Transportation Study
Road 3 North to two miles north of Bramble Drive in Paulden**

**Public Information Meeting Overview –
Paulden Area Community Organization (PACO) Paulden Meeting**

TRACS: P8600 70P

Overview

Project: State Route 89 Chino Valley to Forest Boundary Transportation Study Road 3 North to two miles north of Bramble Drive in Paulden

Meeting Type: Public Information Meeting – Part of the PACO monthly meeting

Intention: To introduce the transportation study to the local area, including residents and business owners. Explain the need, timeframe and intent behind the study.

Meeting Date and Location

Date/Time: Thursday, Jan. 5, 2017 | 7 p.m. to 9 p.m.

Location: Paulden Christian Fellowship Church | 165 Aspen Rd. Paulden, 86334

Intention: To engage the local community in a study that would eventually impact them greatly. To explain and highlight the areas ADOT feels need attention along the corridor. ADOT wants to explain how this study identifies several necessary improvements to address safety, access, mobility, and capacity issues.

Public Meeting

Format and Meeting Site Layout

Format: The Office of Community Relations coordinated with the local community organization (PACO) at a monthly meeting which actually consumed the entire agenda. Tricia Lewis reserved the site and worked with the PACO president several months prior to the meeting. The meeting site layout was rows of chairs with a podium at the front of the room. Alvin Stump, the NW District Engineer did a presentation/slide show and then opened up the meeting to questions and answer session.

Meeting layout

- Chairs: 100 set up theater style with podium and head table at the front of the room
- Tables: No tables were set up, there was not room for tables in the small venue (church)
 - Registration and Title VI – setup in the front of the room (photos provided)
- A/V: One microphone
- Sign-in/orientation
 - Materials: Sign-in sheets; Title VI information was provided and mentioned during beginning of presentation

Presentation:

The PACO meeting had a small agenda prior to opening the floor up to ADOT. At approximately 7:15, Tricia Lewis and Alvin Stump stood up and did introductions of the team that was present: Tricia Lewis, senior community relations office, Alvin Stump, NW district engineer, Dan Gabiou, MPD project manager, Andy Roth, NW assistant district engineer. Alvin began with the study overview but before the presentation got into detail, he highlighted the Title VI materials. A detailed slide show was presented and then a Q&A session (that included 26 questions). Alvin answered all the questions during the meeting.

- Presented by Tricia Lewis (welcome, introduction of study team, purpose of the meeting and Title VI information)
- Presented by Alvin Stump (study overview)

Questions:

- Written comments/questions were answered during the presentation
- Open house style after presentation
- Q&A discussion with project members after the presentation and written questions were answered

Meeting Schedule:

7:00 p.m.: Set-up (Communications, Project Team)

- Registration table
- Screen at the front of the room, A/V equipment provided

7:15 p.m. – Meeting began with PACO agenda, interaction with project team members

Answered written questions once presentation was done

9 p.m. – The church started to clear about 9:15 and meeting was complete

Notifications:

- Newspaper ad published in the Chino Valley Review on Wednesday, Dec. 7 and Dec. 21 (both Wednesday since that is production day)
- Postcard mailed to 2,500 residents, business owners along the corridor that were within ¼ mile of the project
- Gov Delivery email blast about the meeting to over 3881 stakeholders
- Project webpage was created: azdot.gov/pauldenstudy
- Information through the Paulden Post Office, Family Dollar store, local gas stations, McDonald's in Chino Valley, Town of Chino Valley

Contact information for collateral:

Email: tlewis@azdot.gov

Phone: 928.606.2420

Tricia Lewis

From: Daniel Gabiou
Sent: Friday, January 13, 2017 2:04 PM
To: Tricia Lewis; Jason Pagnard
Subject: SR89 Public Comments Summary

Paulden Meeting Comments (1/5/17)

Comments Responses

Respo

1) Why 4 lanes when Hell Canyon is 2 lanes?	Traffic volumes are lower at Hell Canyon. We'll only be looking at a passing lane further north.
2) Hope to see these turns in the near future.	
3) Why build a 16' wide median at Big Chino? How would a roundabout work there?	The roundabout would be ideal at this location. We need 16' width in order to add a median and turn-lane.
4) The section between Chino and Paulden is dangerous. Any improvements are appreciated.	
5) You should lower the speed limit to 55 all the way to Chino.	The assigned speed limit is based on most people's comfort level.
6) There are people passing on the right in the emergency areas (shoulders).	
7) There should be an additional paved road connecting Paulden to Chino.	Any work off of SR89 would be a County project.
8) At roundabouts, can the yield signs be converted to stop signs?	No, this would defeat the purpose of the roundabout.
9) If Phoenix has 30% of the population, do they get all the money [for transportation improvements]?	Phoenix has their own pot of money. Safety funds are something we compete for statewide.
10) Thanks for Little Ranch Rd; roundabouts are great.	
11) We should do a merging ramp instead of a lights or roundabouts.	
12) What are we doing at the railroad? There's not a lot of width there. Would you widen to 4 lanes, then squeeze back down to 2 lanes? What if people race to pass and hit the abutments?	Any widening of the Railroad overpass bridge would require significant costs. Adding the median helps to slow people down.
13) We need alternative transportation routes such as bike routes and sidewalks. Will cattle guards be removed?	Rd 3 N to Rd 5 N will include sidewalks. In rural areas, we'll have shoulder for bikes. At intersections it would be case by case. Cattle guards can be replaced when fencing is available.
14) You should just add a passing lane; not expand lanes. 4 Lanes open up development. Passing lanes are cheaper.	
15) When are we repaving? We don't need roundabouts; we need to preserve what we have.	
16) What's the total cost?	\$50M - \$60M range.
17) I like roundabouts. Put one at Big Chino.	
18) We need school bus pullouts.	
19) Why include access points at Frontier instead of Buffalo Run?	

20) Why no Left Turn lanes with construction at Little Ranch Rd? When will access to Little Ranch Rd be repaired?	We used Bridge Program funds for that project. Bridge funds have to be used for bridges, so we could add turn lanes at that time. We'll try to get maintenance funds and patch the potholes.
21) No traffic circle at Big Chino, but lighting is needed.	Roundabouts reduce conflicts points from 32 to 8 and reduce fatalities by over 90%.
22) Little Ranch Rd is very dangerous. Need Left Turn lane.	
23) Can we have a "No Passing" at Little Ranch Rd?	No passing is tied to sight distance.
24) Need a traffic signal at Big Chino and Bramble.	
25) Will Sedona take money away from the Northwest District?	All construction funds are competitive statewide.
26) What's more expensive, a signal or a roundabout?	It depends on the intersection. A 2-lane roundabout could be as cheap as \$1.5M - \$2M.
27) No more roundabouts. 18 wheelers don't fit. There are black marks in the roundabouts from where the trucks drive over them.	The aprons are intended for trucks to drive over them when they drive in the inner lane.
28) Can we get street lights?	Hopefully as part of the Paulden turn lane project.
29) Is it more economical to do yellow striping [instead of adding a raised median]?	It's a safety problem. Adding a median prevents crossover accidents.
30) You should clear the area near Little Ranch Rd to improve visibility.	
31) Thanks for lowering the speed limit.	
32) Roundabouts won't fix driver behavior. They'll still pass on the right in the shoulder when the buses are stopped.	We'll take bus stops into consideration.
33) What will the impacts be to the RV Park and Post Office?	We are close to having a couple of options that we will share with the businesses. Once we get them developed, we will meet with the businesses. As it stands, all improvements will be inside the right-of-way.

Chino Valley Meeting Comments (1/10/17)

Comments	Responses
1) Will there be a roundabout at Rd 5 N?	We're looking at the possibility, but it's currently unfunded
2) Does ADOT pave/maintain local roads in Paulden?	No, the town and county are responsible for maintaining local roads.
3) How does prioritization work for safety? There are a lot of accidents between Chino and Paulden.	We apply for federal funds. It's prioritized based on a benefit to cost calculation.
4) How wide is the current corridor?	Most of the corridor is 200', except it gets narrower in Paulden. This study is not looking at adding a new alignment. In the long term, we may have a parallel system, but that would be very far out.
5) Why roundabouts? We had them in a long time ago and took them out because they didn't work.	Back in the day we used traffic circles, but we took them out because they created more accidents. We're proposing roundabouts now. Roundabouts reduce the contact points from 32 to 8. Modern roundabouts have different design, eliminate serious accidents, and are more efficient.
6) Big Chino wash is very sensitive environmentally.	
7) There is a bald eagle nest near Rd 6 N. It's a very	As part of any future projects, we will complete a NEPA

sensitive area. We lost 3 eagle eggs due to loud noises in the area.	process and coordinate with AGFD and USFWS and incorporate any mitigation measures to reduce impacts to the eagles.
8) We need a wildlife crossing near Paulden.	

Dan Gabiou, CPM
 Planning Program Manager
 ADOT Multimodal Planning Division
 206 S. 17th Avenue, MD310B
 Phoenix, AZ 85007
 602-712-7025
azdot.gov



TITLE VI MEETING SUMMARY for:**The State Route 89 Chino Valley to Forest Boundary Transportation Study Road
3 North to two miles north of Bramble Drive in Paulden**

TO: Lucy Schrader

FROM: Tricia Lewis

DATE: January 9, 2017

Public Information Meeting:

Thursday, Jan. 5, 2017 at 7 p.m., at the Paulden Area Community Organization (PACO) monthly meeting located at the Paulden Christian Fellowship Church in Paulden. (Three more meetings are scheduled for this same study).

Total attendees that signed in at the meeting: 71 people attended the first outreach meeting in Paulden.

Accommodation Requests: None received for this meeting.

Accommodations Made: Church was relatively located in the center of Paulden area and was well-known and attended by local residents and business owners.

Self-Identification Surveys Returned: 2

Note: attach a copy of any advertisements and mailers that were used to publicize this meeting as well as a photo of the display. This cover sheet will become an appendix to the final meeting summary.

- Two print ads were placed for notification of the upcoming outreach schedule and were in the Chino Valley Review on Dec. 7 and again on Dec. 21.

**PAULDEN AREA COMMUNITY ORGANIZATION
GENERAL MEETING SIGN-IN
DATE: January 5, 2017**

BOARD MEMBERS - PLEASE INITIAL NEXT TO YOUR NAME

Betsy Terry	<u>BT</u>
Dave Chrazanowski	<u>DC</u>
Don Nowell	<u>DN</u>
Gary Hanby	<u>GH</u>
Gin Sullivan	<u> </u>
James Haley	<u>JH</u>
Judi Lewis	<u> </u>
Terri McPherson	<u> </u>
Tom Martens	<u>TM</u>

MEMBERS AND GUESTS - PLEASE PRINT

NAME	ADDRESS	EMAIL
NEVLS	N FEATHER MTN	ON FILE
Mark + Theresa Logan	N Feather mtn	theresla@live.com
Bonnie Kuhlman	Saddle Rd.	Neel.Bonnie@gmail.com
Karen	SAUFRAANSICO	
Blackhawk	Paulden, AZ	
Gary / Carol Hanby	PAULDEN, AZ	
John / Angel Benson	PAULDEN AZ	
Cathy Schutt	Paulden AZ	Wooten22@hotmail.com
Wes Lusher	Annie Rd	wlusher12@gmail.com
OLIVER THOMAS	BIA SPRINGS	
MITCHELL PETERSON	N. MITCHELL LANE	MITCHELL.PETERSON JRO@ash

NAME

ADDRESS

EMAIL

Matthew Peterson Mitchell Lane Matthew.81388@6ma:1

Craig Brown Yak. Co

SHIRLEY WOOD MAHAPAI CO.

Harvey Alan & Laurie W Reinway Rd. 3500 ewebabe@gmail.com

Albert & Patty Margus Big Springs Ranch Rd.

CASSIE NOWELL MAHAPAI CO

Peter & Terry

Margaret McKinnis Paulden

Doug McKinnis Paulden

Gisela Peterson Yakima County Little Harrah Rd.

Kathy Muttetal 22100 N Wolf Den Lane

Melody Roth 22100 N Wolf Den Ln Paulden

Richard & Mary Jo Biers 25495 16th St

DAN & KATHI DORF

Bob & Lynn Taylor 2655 Big Chino Rd

Steve & Beverly Young 410 W Big Chino Rd

John Bennett

STEVE FREY 25400 N. IRONWOOD DR. PAULDEN STFREY124@AOL.COM

Peter & Donna

Rob Weplers 26895 N Champagne Ln dsWALKERS283@GMAIL.COM

Mary Christensen 33712 W. Harvest Way Paulden

Joe Tone Daily Courier Stone@prescottaz.com.

Joe Zumbardo

Lisa Wills / Cliff Halyes 24925 N. Casino Del Reno Paulden wellstmr22@yahoo.com

8900 Stanton 270 E. Yogi Berra Park

visiting friends

NAME

ADDRESS

EMAIL

Jo Ann Hankey	22580 Malapai Ridge	jhankey@comcast.net
Dana Riddle	740 W. Willow Wind Tr	dana_riddle@msn.com
Starlyn Rupp	22340 Sunny Ln	starlyn555@gmail.com
Walter Rupp	PO Box 24 Chino	
Helen Rupp	PO Box 214 Chino	
Demi Thompson	22075 N Triple Lane	
Sam Thompson	"	Dusty1245@yahoo.com
Dyan Miller	240 W. Granada Dr.	dyanymiller@hotmail.com

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

Would problem areas
such as 179 into Sedona
take money away from
Northwest district?

12-181

ADOT

azdot.gov

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

No more roundabouts 18
wheelers DO NOT FIT!
Check out the
black rubber marks not on
the round button

12-181

ADOT

azdot.gov

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

Can we get a light at
Bugchimo & Bramble.
Please

12-181

ADOT

azdot.gov

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

What is more expensive to
install?
A. Traffic signals
B. Round-a-bouts.

12-181

ADOT

azdot.gov

answered at the end of the presentation,
pass it to an ADOT project representative.
We have limited the time for questions and
answers to allow you time to speak directly
with project staff. If we do not get to your
question, we encourage you to speak with a
project representative.

no passing
; Ranch

12-181

azdot.gov

answered at the end of the presentation,
pass it to an ADOT project representative.
We have limited the time for questions and
answers to allow you time to speak directly
with project staff. If we do not get to your
question, we encourage you to speak with a
project representative.

It has been an
dangerous Left
my years.
like to see a
There ASAP

azdot.gov

guntas

stare al final de la presentación, escribas
proyecto de ADOT. Hemos limitado el tiempo
o de que hable directamente con el personal
pregunta, le aconsejamos que hable con un
lir legiblemente.

douts
ne turn lane

12.01

adot.gov

answered at the end of the presentation,
I pass it to an ADOT project representative.
owers to allow you time to speak directly
estion, we encourage you to speak with a
3 legibly.

17-20-2014
LATS
US THE DOOR TO
DIVERSOPES

12.01

adot.gov

Question Card

If you have a question(s) that you would like answered at the end of the presentation,
please write your question(s) on this card and pass it to an ADOT project representative.
We have limited the time for questions and answers to allow you time to speak directly
with project staff. If we do not get to your question, we encourage you to speak with a
project representative. Thank you for printing legibly.

Why an access point at Drexler
Ad better then Buffalo Ranch
which has more traffic?

12.01

adot.gov

ADOT

Question Card

If you have a question(s) that you would like answered at the end of the presentation,
please write your question(s) on this card and pass it to an ADOT project representative.
We have limited the time for questions and answers to allow you time to speak directly
with project staff. If we do not get to your question, we encourage you to speak with a
project representative. Thank you for printing legibly.

I think we need school bus
pull off. Thought round about
were on intersections. +

12.01

adot.gov

ADOT

Question Card

If you have a question(s) that you would like answered at the end of the presentation,
please write your question(s) on this card and pass it to an ADOT project representative.
We have limited the time for questions and answers to allow you time to speak directly
with project staff. If we do not get to your question, we encourage you to speak with a
project representative. Thank you for printing legibly.

Why wasn't Left Turn Lane
installed with the recent highway
construction @ Little Rock?
Also when will access to Little
Rock be repaired?

12.01

adot.gov

ADOT

Question Card

If you have a question(s) that you would like answered at the end of the presentation,
please write your question(s) on this card and pass it to an ADOT project representative.
We have limited the time for questions and answers to allow you time to speak directly
with project staff. If we do not get to your question, we encourage you to speak with a
project representative. Thank you for printing legibly.

Comments you will probably see
universal opposition to a traffic
circle at Big Chico. Rather want
control traffic warrants are met for
a signal. However, lighting is

12.01

adot.gov

ADOT needed now at this
intersection

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

I hear "cost benefit" - is there a LIVES benefit analysis?
If Phoenix has 30% of the population
do they get 90% of highway
funds?

12.11.15

azdot.gov

ADOT

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

Can you ~~or~~ consider a merging ramp to join
Would consider a merging ramp to join
traffic to keep traffic moving on 89
rather than full intersections or many
roundabouts?

12.11.15

azdot.gov

ADOT

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

Can the yield signs be changed
to Stop Signs @ the roundabouts

12.11.15

azdot.gov

ADOT

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

Thank you for including Little Ranch
left turn plans - very dangerous
intersection - Roundabouts are
great! They allow traffic to keep
moving but also slow speed

12.11.15

azdot.gov

ADOT

answered at the end of the presentation,
pass it to an ADOT project representative.
We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

- lower the speed
11 All the way

12.11.15

azdot.gov

CONNECTING
VARIABLES TO
FOR LOCALS
NEW TRAFFIC

rd

like answered at the end of the presentation,
d and pass it to an ADOT project representative.
and answers to allow you time to speak directly
ur question, we encourage you to speak with a
ining legibly.

me people with
ve mantality -
ple being reasonable
co. Not tax payer

12.11.12

azdot.gov

Question Card

If you have a question(s) that you would like answered at the end of the presentation,
please write your question(s) on this card and pass it to an ADOT project representative.
We have limited the time for questions and answers to allow you time to speak directly
with project staff. If we do not get to your question, we encourage you to speak with a
project representative. Thank you for printing legibly.

The section of Hwy 89 between CV & 9
has been becoming more dangerous
by the day - anything that can be
done to improve road conditions
reduced speed, widening etc would
be appreciated

12.11.12

azdot.gov

ADOT

Question Card

If you have a question(s) that you would like answered at the end of the presentation,
please write your question(s) on this card and pass it to an ADOT project representative.
We have limited the time for questions and answers to allow you time to speak directly
with project staff. If we do not get to your question, we encourage you to speak with a
project representative. Thank you for printing legibly.

Why does the median by
Big Chino road need to be
16' wide? How does the
roundabout play into it?

Any plans for entry from old 89
ADOT when the 4 lane is
done?

12.11.12

azdot.gov

12.11.12

azdot.gov

answered at the end of the presentation,
pass it to an ADOT project representative.
answers to allow you time to speak directly
ition, we encourage you to speak with a
legibly.
ee the s. r 44 p. 1 of
- place in the

Question Card

If you have a question(s) that you would like answered at the end of the presentation,
please write your question(s) on this card and pass it to an ADOT project representative.
We have limited the time for questions and answers to allow you time to speak directly
with project staff. If we do not get to your question, we encourage you to speak with a
project representative. Thank you for printing legibly.

When is it planned for Hwy 89 to be
Repaired?

12.11.12

azdot.gov

ADOT

Question Card

If you have a question(s) that you would like answered at the end of the presentation,
please write your question(s) on this card and pass it to an ADOT project representative.
We have limited the time for questions and answers to allow you time to speak directly
with project staff. If we do not get to your question, we encourage you to speak with a
project representative. Thank you for printing legibly.



ADOT

12.11.12

azdot.gov

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

What about alternate transportation route - bicycles/walkers/horses?

Will side road cattle guards be removed?

What kind of safety lights?

Will turn lanes be equal @ intersections?
(currently just a N bound turn lane @ Verde by Kinnick Road)

Will you be working PRIMARILY N from CV or as needed or hit & miss between 3N & Bramble?

ADOT

azdot.gov

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

How can you make 4 ln when the Hell Canyon is 2 ln and make more problem and there are all ready two lanes

ADOT

azdot.gov

Completing this survey is voluntary. If you choose to respond, please mark all that apply.

ETHNICITY/RACE:

- ☐ American Indian/Alaskan Native
- ☐ Asian/Pacific Islander
- ☐ Hispanic/Latino
- ☐ African American/Black
- ☒ White
- ☐ Other

GENDER:

- ☒ Female
- ☐ Male

AGE:

- ☐ 1 - 20
- ☐ 21- 39
- ☐ 40 - 64
- ☒ 65+

DISABLED:

- ☐ Yes
- ☒ No

VETERAN STATUS:

- ☐ Yes
- ☒ No

Completing this survey is voluntary. If you choose to respond, please mark all that apply.

ETHNICITY/RACE:

- ☐ American Indian/Alaskan Native
- ☐ Asian/Pacific Islander
- ☐ Hispanic/Latino
- ☐ African American/Black
- ☒ White
- ☐ Other

GENDER:

- ☐ Female
- ☒ Male

AGE:

- ☐ 1 - 20
- ☐ 21- 39
- ☐ 40 - 64
- ☒ 65+

DISABLED:

- ☒ Yes
- ☐ No

VETERAN STATUS:

- ☒ Yes
- ☐ No

**State Route 89 Chino Valley to Forest Boundary Transportation Study
Road 3 North to two miles north of Bramble Drive in Paulden**

**Public Information Meeting Overview –
Town of Chino Valley council meeting**

TRACS: P8600 70P

Overview

Project: State Route 89 Chino Valley to Forest Boundary Transportation Study Road 3 North to two miles north of Bramble Drive in Paulden

Meeting Type: Council meeting

Intention: To introduce the transportation study to the local area, including residents and business owners. Explain the need, timeframe and intent behind the study.

Meeting Date and Location

Date/Time: Tuesday, Jan. 10, 2017 | 6 p.m.

Location: Town of Chino Valley Council meeting | 202 N. State Route 89, Chino Valley, AZ 86332

Intention: To engage the local community in a study that would eventually impact them greatly. To explain and highlight the areas ADOT feels need attention along the corridor. ADOT wants to explain how this study identifies several necessary improvements to address safety, access, mobility, and capacity issues.

Public Meeting

Format and Meeting Site Layout

Format: The Office of Community Relations coordinated with the Town of Chino Valley to get study information on the agenda. Tricia Lewis worked with Cecelia Gritman, the interim town manager to coordinate the study details and preparation for council. The meeting layout was as it is during a council meeting with a podium and screen at the front of the room with rows of chairs for audience members. Alvin Stump, the NW District Engineer did a presentation/slide show and then opened up the meeting to questions and answer session but was limited per the mayor. The presentation with questions was over at 6:15 p.m. but members of the public came out to the hallway to ask the project team questions. Many of the written questions were answered in the hallway with the members of the project team interacting with the public.

Meeting layout

- Chairs: 100 set up theater style with podium and head table at the front of the room
- Tables: No tables were set up
 - Registration and Title VI – setup in the back of the room
- A/V: One microphone
- Sign-in/orientation

- **Materials:** Sign-in sheets; Title VI information was provided and mentioned during beginning of presentation

Presentation:

The council meeting began with pledge of allegiance and call to the public. At approximately 6:00, Dan Gabiou asked the council if we could send around a sign-in sheet for people to sign in as part of our meeting. The sign-in sheets were distributed around the room and collected once everyone had a chance to fill them out. The council had a small agenda prior to Alvin Stump's presentation. Alvin introduced the team members (Dan Gabiou and Tricia Lewis). Alvin began with the study overview but before the presentation got into detail, he highlighted the Title VI materials. A detailed slide show was presented and then a very brief Q&A session followed).

- Presented by Alvin Stump (study overview)

Questions:

- Written comments/questions were answered during the presentation
- A Q&A session was not permitted during the council meeting, members of the public were asked to fill out comment cards and four were received

Meeting Schedule:

6:00 p.m.: Council meeting began

- Registration table and Title VI display in back of the room
- Screen at the front of the room, A/V equipment provided

6:00 p.m. – Meeting began with regular council agenda items and open to members of the public prior to ADOT getting the floor

7 p.m. – Project team discussed with a few residents and then were dismissed

Notifications:

- Newspaper ad published in the Chino Valley Review on Wednesday, Dec. 7 and Dec. 21 (both Wednesday since that is production day)
- Postcard mailed to 2,500 residents, business owners along the corridor that were within ¼ mile of the project
- Gov Delivery email blast about the meeting to over 3881 stakeholders
- Project webpage was created: azdot.gov/pauldenstudy
- Information through the Paulden Post Office, Family Dollar store, local gas stations, McDonald's in Chino Valley, Town of Chino Valley

Contact information for collateral:

Email: tlewis@azdot.gov

Phone: 928.606.2420



Civil Rights Office

15-0510 R12/16 azdot.gov

TITLE VI MEETING SUMMARY

TITLE VI MEETING SUMMARY FOR: SR 89 Chino Valley to Forest Boundary Transportation Study

TO: ADOT Civil Rights Office

FROM (Name, Title, Program Area/Unit):

Tricia Lewis, senior community relations officer, ADOT communications, NW District

Name and purpose of meeting:

Town of Chino Valley council meeting - purpose of meeting was to inform and update the Town of Chino Valley about the study and explain the short, mid and long-term recommendations for the corridor.

Date, location and summary of activities at meeting:

Tuesday, Jan. 10, council chambers 202 N. State Route 89, Chino Valley, AZ 86332
Alvin Stump provided a short presentation before council and members of the audience at their monthly meeting.

Number of public attendees: _____

Accommodation Request for Limited English Proficiency (LEP) and ADA:

Accommodations made in advance or requested? (ex. Interpretation, translation, listening device)	How was the request accommodated? (ex. Interpreter, Translator, renting of a listening device)	Estimated cost associated with accommodation? (\$)

of Self-Identification Surveys returned: _____

ADOT Self-Identification Survey - Title VI

CATEGORY	DESIGNATION	COUNT
Race/Ethnicity	African American/Black	
	American Indian/Alaskan Native	
	Asian	
	Hispanic/Latino	
	Native Hawaiian/Other Pacific Islander	
	White	
Sex	Female	
	Male	

Additional Information (Optional): Use the space below to provide any additional information about the meeting or accommodations

Note: attach a copy of any advertisements and mailers that were used to publicize this meeting as well as a photo of the Title VI display.

Please click the submit button when you have completed this form to open an email and send to CivilRightsOffice@azdot.gov.

Submit

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

Design in wildlife corridors
and bypass structures?
Don't harm our pronghorn!

12-181

ADOT

azdot.gov

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

Turn left lanes at Buffalo Run Road and Frontier road is needed. It is impossible for residents to turn left off of Hwy 89 onto these roads to go home without being run into. We need a facility at Frontier in 2016. Left turn lanes are desperately needed.

12-181

ADOT

azdot.gov

Turn Patrols 6550 N. Bison Walk Dr off Buffalo Run

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

What, if any, plans have been included for wildlife corridors in the widening plans?

Kate

Kateoem@cableone.net O'Connor-

12-181

ADOT

azdot.gov

Massie
9284204723

Question Card

If you have a question(s) that you would like answered at the end of the presentation, please write your question(s) on this card and pass it to an ADOT project representative. We have limited the time for questions and answers to allow you time to speak directly with project staff. If we do not get to your question, we encourage you to speak with a project representative. Thank you for printing legibly.

ADOT just finished a Right Turn Lane at Verde Ranch Rd. Why is it twice as long as the Right turn lane for north bound traffic at the south end of old Hwy 89 just North of marker 333?

12-181

ADOT

azdot.gov

**State Route 89 Chino Valley to Forest Boundary Transportation Study
Road 3 North to two miles north of Bramble Drive in Paulden**

**Public Information Meeting Overview –
Yavapai County Board of Supervisors monthly meeting**

TRACS: P8600 70P

Overview

Project: State Route 89 Chino Valley to Forest Boundary Transportation Study Road 3 North to two miles north of Bramble Drive in Paulden

Meeting Type: Study presentation during monthly board meeting

Intention: To introduce the transportation study to the Yavapai County Board of Supervisors and the general public. Explain the need, timeframe and intent behind the study.

Meeting Date and Location

Date/Time: Wednesday, Feb. 1, 2017 | 9 a.m.

Location: Yavapai County Board of Supervisors meeting | 1015 Fair Street, Prescott, AZ 86305

Intention: To explain and highlight the areas ADOT feels need attention along the corridor. ADOT wants to explain how this study identifies several necessary improvements to address safety, access, mobility, and capacity issues.

Public Meeting

Format and Meeting Site Layout

Format: ADOT was given the first item on the agenda for the monthly board meeting. The meeting site layout was rows of chairs with a podium at the front of the room. Alvin Stump, the NW District Engineer did a presentation/slide show and then answered questions from the board members. A few audience members asked questions about the study such as when this study would go into construction and also some suggestions about intersection improvements at Buffalo Run Road and SR 89.

Meeting layout

- The meeting was set up for a CYMPO board meeting and was in the Yavapai County Board of Supervisors chambers. There are rows of chairs set up facing the board members.
- Tables: No tables were set up
 - Registration and Title VI – setup on the table on the side of the room (photos provided)
- A/V: One microphone
- Sign-in/orientation
 - Materials: Sign-in sheets; Title VI information was provided and mentioned during beginning of presentation

Presentation:

ADOT was a guest at the Yavapai County Board of Supervisor's meeting and had ADOT study presentation at the beginning of the agenda. At approximately 9:10 p.m., Alvin Stump stood up and introduced him and Tricia Lewis. Alvin began with the study overview but before the presentation got into detail, he highlighted the Title VI materials. A detailed slide show was presented and then Alvin took questions from the BOS.

Even though the presentation was on the SR 89 study, many members of the BOS asked questions about I-17. The county administrator spoke up to remind the BOS the item was on the 89 study not improvements on I-17.

- Presented by Alvin Stump (study overview)

Questions:

- Written comments/questions were answered during the presentation

Meeting Schedule:

9:00 a.m.:

Screen at the front of the room, A/V equipment provided

9:10 a.m.: Meeting began with invocation and a few agenda items. ADOT did the presentation and then questions from the Yavapai County Board of Supervisors. The study presentation was familiar because a few of the BOS had seen the presentation prior to this meeting.

Notifications:

- Newspaper ad published in the Chino Valley Review on Wednesday, Dec. 7 and Dec. 21 (both Wednesday since that is production day)
- Postcard mailed to 2,500 residents, business owners along the corridor that were within ¼ mile of the project
- Gov Delivery email blast about the meeting to over 3881 stakeholders
- Project webpage was created: azdot.gov/pauldenstudy
- Information through the Paulden Post Office, Family Dollar store, local gas stations, McDonald's in Chino Valley, Town of Chino Valley

Contact information for collateral:

Email: tlewis@azdot.gov

Phone: 928.606.2420



Civil Rights Office

15-0510 R12/16 azdot.gov

TITLE VI MEETING SUMMARY

TITLE VI MEETING SUMMARY FOR: SR 89 Chino Valley to Forest Boundary Transportation Study

TO: ADOT Civil Rights Office

FROM (Name, Title, Program Area/Unit):

Tricia Lewis, senior community relations officer, ADOT communications, NW District

Name and purpose of meeting:

Yavapai County Board of Supervisors meeting - held during the monthly board meeting. The purpose of the meeting was to inform the BOS about the transportation study. Provide an opportunity for questions from BOS and general public.

Date, location and summary of activities at meeting:

Wednesday, Feb. 1 at the Yavapai County BOS board room at 1015 Fair Street, Prescott, AZ 86305
Alvin Stump provided a short presentation to the BOS and members of the audience during the monthly board meeting.

Number of public attendees: 35

Accommodation Request for Limited English Proficiency (LEP) and ADA:

Accommodations made in advance or requested? (ex. Interpretation, translation, listening device)	How was the request accommodated? (ex. Interpreter, Translator, renting of a listening device)	Estimated cost associated with accommodation? (\$)
A blind woman asked about attending a meeting and couldn't get transportation to a night meeting.	Community Relations offered the two day meetings, the Yavapai County BOS and the CYMPO board meeting would be held during the day.	\$0

Board of Supervisors - Sign in Sheet

113-7216
Feb. 1, 2017

ADOT Padden Study - Meeting #3

NAME	Company	Email
Cynthia Gentle	Yavapai County	Cynthia.gentle@yavapai.us
TERI DREW	NACOG	JDrew@nacog.org
Michael Holmes	Yavapai County	Michael.Holmes@yavapai.us
Sara Ekwall	Yavapai County	Sara.ekwall@yavapai.us
Marlyn Summers	Yavapai County	marlyn.summers@yavapai.us
Barbara Fox	Yavapai County	barbara.fox-thoms@yavapai.us
DeShannan Young	Yavapai County	deshannan.young@yavapai.us
Mary Comer	Yavapai Co.	mary.comer@yavapai.us
Ken VanHeur	Y.C.	Kenng.VanHeur@yavapai.us
David Rhodes	YCSO	david.rhodes@yavapai.us
Wendy Ross	Yavapai County	Wendy.ross@yavapai.us
Kevin Blake	Yavapai County	Kevin.Blake@yavapai.us
Kristy Kennedy	YCDS	Kristy.Kennedy@yavapai.us
Steven Mauk	YCDS	Steven.Mauk@yavapai.us
David Beau Boisvert	Yavapai County / Associate Office	David.boisvert@yavapai.us
Nicole Russell	YCDS	nicole.russell@yavapai.us
Tammy Dewitt	Yavapai Co	tammy.dewitt@yavapai.us
BYRON JOSEPH	YCPH	byron.joseph@yavapai.us
Randy Schenck		rtks_86@yahoo.com
Jim Ray		cowtinstrz@aol.com
PHILIP LAPLANTE		
KIRK MAILLON		KMAILON4401@aol.com
MARY MAILON		Kmailon2000@yahoo.com
CAZ WILKINSON		SUPERVISOR Smith office
Frank Vander Horst	YASD #59	frank.vander.horst@yavapai.us
MONTY MARR	YIA	m-marr@yavapai.us

Billie Orr
LARRY HASLEY

City of Prescott

billieorr@aol.com
larryhasley14@aol.com

Bob Betts
George Sheats

PAULIE
Prescott P4Z

pauliechair@gmail.com
gsheats@aol.com

Jim Peterson

Prescott, - citizen

JPeterson@comcast.net

GROB CAMPBELL PAULSON

DAN & DARCY DELEONARDIS PRESCOTT

Tachilles@gmail.com

dannydeleonardis@gmail.com

Steve & Penny Govedich Paulson

penny.govedich@gmail.com

**State Route 89 Chino Valley to Forest Boundary Transportation Study
Road 3 North to two miles north of Bramble Drive in Paulden**

**Public Information Meeting Overview –
Central Yavapai Metropolitan Planning Organization (CYMPO) Board meeting**

TRACS: P8600 70P

Overview

Project: State Route 89 Chino Valley to Forest Boundary Transportation Study Road 3 North to two miles north of Bramble Drive in Paulden

Meeting Type: Study presentation during monthly board meeting

Intention: To introduce the transportation study to the CYMPO, including residents and business owners. Explain the need, timeframe and intent behind the study.

Meeting Date and Location

Date/Time: Wednesday, Feb. 15, 2017 | 4 p.m. to 6 p.m.

Location: Yavapai County Board meeting | 1015 Fair Street, Prescott, AZ 86305

Intention: To engage the local community in a study that would eventually impact them greatly. To explain and highlight the areas ADOT feels need attention along the corridor. ADOT wants to explain how this study identifies several necessary improvements to address safety, access, mobility, and capacity issues.

Public Meeting

Format and Meeting Site Layout

Format: ADOT was given the first item on the agenda for the monthly board meeting. The meeting site layout was rows of chairs with a podium at the front of the room. Alvin Stump, the NW District Engineer did a presentation/slide show and then answered questions from the board members. A few audience members asked questions about the study such as when this study would go into construction and also some suggestions about intersection improvements at Buffalo Run Road and SR 89.

Meeting layout

- The meeting was set up for a CYMPO board meeting and was in the Yavapai County Board of Supervisors chambers. There are rows of chairs set up facing the board members.
- Tables: No tables were set up
 - Registration and Title VI – setup on the table on the side of the room (photos provided)
- A/V: One microphone
- Sign-in/orientation
 - Materials: Sign-in sheets; Title VI information was provided and mentioned during beginning of presentation

Presentation:

The CYMPO board meeting had their regular monthly agenda but put ADOT's study presentation at the beginning of the meeting. At approximately 4:10 p.m., Tricia Lewis and Alvin Stump stood up and introduced themselves.. Alvin began with the study overview but before the presentation got into detail, he highlighted the Title VI materials. A detailed slide show was presented and then a Q&A session (that included 2 questions). Alvin answered all the questions during the meeting.

- Presented by Tricia Lewis (welcome, introduction of study team, purpose of the meeting and Title VI information)
- Presented by Alvin Stump (study overview)

Questions:

- Written comments/questions were answered during the presentation
- Questions were addressed during the call to public portion of the meeting

Meeting Schedule:

4:00 p.m.: Set-up (Communications, Project Team)

- Registration table
- Screen at the front of the room, A/V equipment provided

4:05 p.m. – Meeting began with Opening remarks and approval of past meeting board meeting minutes. ADOT did the presentation and then answered two questions from the public. ADOT was complete with the study presentation by 4:25 p.m.

Notifications:

- Newspaper ad published in the Chino Valley Review on Wednesday, Dec. 7 and Dec. 21 (both Wednesday since that is production day)
- Postcard mailed to 2,500 residents, business owners along the corridor that were within ¼ mile of the project
- Gov Delivery email blast about the meeting to over 3881 stakeholders
- Project webpage was created: azdot.gov/pauldenstudy
- Information through the Paulden Post Office, Family Dollar store, local gas stations, McDonald's in Chino Valley, Town of Chino Valley

Contact information for collateral:

Email: tlewis@azdot.gov

Phone: 928.606.2420



Civil Rights Office

15-0510 R12/16 azdot.gov

TITLE VI MEETING SUMMARY

TITLE VI MEETING SUMMARY FOR: SR 89 Chino Valley to Forest Boundary Transportation Study

TO: ADOT Civil Rights Office

FROM (Name, Title, Program Area/Unit):

Tricia Lewis, senior community relations officer, ADOT communications, NW District

Name and purpose of meeting:

CYMPO board meeting - purpose of meeting was to inform and update the CYMPO board and general public about the study and explain the short, mid and long-term recommendations for the corridor.

Date, location and summary of activities at meeting:

Wednesday, Feb. 15 at 1015 Fair Street, Prescott, AZ 86305

Alvin Stump provided a short presentation to the CYMPO board and members of the public at the monthly board meeting.

Number of public attendees: 6

Accommodation Request for Limited English Proficiency (LEP) and ADA:

Accommodations made in advance or requested? (ex. Interpretation, translation, listening device)	How was the request accommodated? (ex. Interpreter, Translator, renting of a listening device)	Estimated cost associated with accommodation? (\$)
n/a	n/a	n/a

of Self-Identification Surveys returned: 0 _____

ADOT Self-Identification Survey - Title VI

CATEGORY	DESIGNATION	COUNT
Race/Ethnicity	African American/Black	
	American Indian/Alaskan Native	
	Asian	
	Hispanic/Latino	
	Native Hawaiian/Other Pacific Islander	
	White	
Sex	Female	
	Male	

Additional Information (Optional): Use the space below to provide any additional information about the meeting or accommodations

Note: attach a copy of any advertisements and mailers that were used to publicize this meeting as well as a photo of the Title VI display.

Please click the submit button when you have completed this form to open an email and send to CivilRightsOffice@azdot.gov.

Submit



CYMPO
Central Yuma Metropolitan
Planning Organization



CYMPO
Central Yuma Metropolitan
Planning Organization

Executive Board Meeting

DATE: February 15, 2017

PLEASE PRINT

SIGN-IN SHEET

NAME	ORGANIZATION (If Applicable)	E-Mail Address	Phone
CHIEF & Ron Ramsey	Yuma Regional Airport	R.Ramsey@aaol.com	928 210 9392
Kent Good Year		CSesinger@aol.com	928 710-5295
Dave Bobbitt			
Bill Hawkins			
Charles Andrews	COV	charles.andrews@prescott-az.gov	928-777-1300
Kirk Murray			
Tom Armstrong		Tom.Armstrong2@wm.com	
ANDREW WALLACE	CITIZEN		PRESCOTT, AZ
J.D. GREENBERG	UNIDUE CORP/DC	ON FILE	
Norm Davi.	Town of Prescott Valley	on file	
Michael Lopez	Town of Chino	—	—
Tricia Lewis	ADOT	Hewitt@aol.com	928-606-2420



Prescott Audubon Society

A Chapter of the National Audubon Society

© 2012

P. O. Box 4156; Prescott, Arizona 86302

Tricia Lewis
Arizona Department of Transportation
1109 Commerce Dr.
Prescott, AZ 86305

tlewis@az.dot.gov

RE: SR89 Chino-Paulden Transportation Study
January 26, 2017



To the AZ Department of Transportation:

On behalf of all members of the Prescott Audubon Society, we submit the following comments and concerns regarding the proposed widening of SR 89 between Chino Valley and Paulden, in Yavapai County.

For safety reasons, we support appropriate improvements to SR 89 between Paulden and Chino Valley, as traffic is increasing along the entire route from Ash Fork to Chino. We also support planning that integrates transportation and community, including "system preservation practices such as green corridor programs" (text from AZ law promising priority funding for plans that include these factors). We believe that coordinated plans that take into account all the types of corridors – water, wildlife, utilities, and community development – during the planning process will result in the most economic and social benefit at the lowest cost in the long term. Sustainable and low maintenance in design beats costly retrofitting. We at Prescott Audubon do not claim to be experts in the costs and complexities of transportation planning, but our 550 members are taxpayers with an interest in the best quality of life in the Yavapai County region.

- As commercial and retail buildings grow on the north end of Chino, and as residential traffic increases in Paulden, there will be more merging into traffic along this route. Roundabouts and

turning lanes, as well as slower speed limits seem reasonable here. Slower speeds also reduce bird and wildlife mortality.

- At Road 6 North in Chino, on the east side, the Del Rio Springs supports an active Bald Eagle nest site. Such nest sites are protected by the AZGFD, usually from December through April. Please consult with the AZGFD to ensure that construction in that region is not scheduled during that time of the year.
- Unfortunately, bright lights attract wildlife to highways. Highway lighting should be as modest as possible, with lights that face downwards only. Collisions with wildlife, especially raptors and owls, will be minimized. The lands along this stretch of road support hundreds of raptors, especially during the spring and fall migration seasons.
- What is the status of the planned "Great Western Drive", the highway that would bypass Chino to the east? If that is to be the roadway for through traffic, then SR 89 becomes the business district, which means more turning lanes will be needed for entering and exiting SR 89. Widening the entire section may not be as important, and wildlife corridor planning will be different.
- The Big Chino Wash flows below this segment of the road, and watercourses attract life of every sort, including human. Design should ensure that this major corridor is not adversely affected by highway changes.
- The region between Chino and Paulden still supports Pronghorn herds, and impact on their migratory corridors should be minimized. Pronghorn are a symbol of Arizona, of value to residents and visitors alike. Pronghorn will not cross paved roadways that carry as much traffic as SR 89 does.

We thank you for the opportunity to submit these comments and be a small part of the collaborative process. We have seen the successes of planning that minimizes adverse impacts to the environment in other parts of Arizona, and we have a strong interest in ensuring the same for our Yavapai County region.

Sincerely,

Board of Directors

PRESCOTT AUDUBON SOCIETY



Multimodal Planning

Douglas A. Ducey, Governor
John S. Halikowski, Director
Michael Kles, Division Director

February 9, 2017

Subject: SR89 Chino Valley to Forest Boundary Transportation Study Letter

Dear Prescott Audubon Society Board of Directors,

Thank you for your letter dated January 26, 2017. ADOT appreciates the Prescott Audubon Society's participation in the SR89, Chino Valley to Forest Boundary Transportation Study. Your input has been reviewed by the Study Team and taken into consideration. Please see the below response to your comments received:

- ADOT appreciates the Prescott Audubon Society's support of roundabouts within this corridor. Roundabouts are proven safety countermeasures which are being considered at several intersections throughout the corridor.
- ADOT has been made aware of the active Bald Eagle nest site off of Road 6 North. It will be noted within the study documents that any future design projects will further coordinate with the Arizona Game and Fish Department (AGFD) and US Fish and Wildlife Services (USFWS) to ensure compliance with the Bald and Golden Eagle Protection Act and the National Environmental Policy Act (NEPA).
- Roadway lighting is being considered as a future improvement near Sweet Valley Rd (near the Paulden Post Office). Your recommendation to use modest, downward-facing lighting will be considered during design and may be implemented if the recommendation meets state and federal design standards and is cost-effective.
- The "Great Western Expansion" is currently not programmed in ADOT's Tentative 10-year State Transportation Improvement Program. Likely a future study or design would be completed to address the Great Western Expansion when population growth, traffic needs, and funding permits.
- During design, coordination with the Army Corps of Engineers, AGFD, and USFWS would occur if any impacts were anticipated within the Big Chino Wash in order to comply with NEPA.
- Pronghorn antelope and other wildlife crossing improvements have been considered as part of this study. Although no wildlife overpass or underpass features were deemed feasible, wildlife crossing signs have been recommended as a near-term improvement to promote driver awareness.

Thanks again for your input and interest in the SR89, Chino Valley to Forest Boundary Transportation Study. Please visit the study website at azdot.gov/PauldenStudy for additional study details and contact Tricia Lewis (TLewis@azdot.gov or 928-606-2420) with any additional input or questions.

Sincerely,

Dan Gabiou, CPM
ADOT, Planning Program Manager
602-712-7025
DGabiou@azdot.gov



Paulden Area Community Organization
(a 501c3 organization)

**PO Box 735
Paulden, AZ 86334**

January 19, 2017

Mr. Alvin Stump
Arizona Dept. of Transportation
1109 E. Commerce Drive
Prescott, AZ 86305


Dear Mr. Stump:

On behalf of the Paulden Area Community Organization and Paulden residents, thank you for your presentation regarding the future of the Highway 89 corridor. As evidenced by the attendance, you can see that this matter is very important to our community residents and businesses. We appreciated the opportunity for questions and answers and believe that we were well informed by your thorough presentation. Thank you for your patience in answering our many questions. Please relay our appreciation to your team as well. We appreciate all you and they do for our community. We look forward to the future and continuing to work with you as a community partner as we continue to grow and thrive.

Sincerely,


Don Nowell, President





PAULDEN AREA COMMUNITY ORGANIZATION
BOARD OF DIRECTORS

Don Nowell, President
Dave Chrazanowski, Treasurer
James Haley, Director

Gin Sullivan, Vice President
Betsy Terry, Director
Judi Lewis, Director

Terri McPherson, Secretary
Gary Hanby, Director
Tom Martens, Director

*Daily
Courier - Jan 5.*

ADOT wants input on Highway 89 between Chino Valley, Paulden

Originally Published: January 5, 2017 6 a.m.

The Arizona Department of Transportation is studying a 13-mile segment of Highway 89 between Road 3 North in Chino Valley and two miles north of Bramble Drive in Paulden. The purpose of this long-range planning study is to identify future roadway improvements as funding becomes available.

ADOT is asking for public input. Four meetings are scheduled and the same information will be presented at each meeting.

- Paulden Area Community Organization (PACO) at 7 p.m., Thursday, Jan. 5, at the Paulden Christian Fellowship Church, 165 Aspen Road, Paulden.
- Chino Valley Town Council meeting at 6 p.m., Tuesday, Jan. 10, at council chambers, 202 N. Highway 89, Chino Valley.
- Yavapai County Board of Supervisors meeting at 9 a.m., Wednesday, Feb. 1, 1015 Fair St., Prescott.
- Central Yavapai Metropolitan Planning Organization (CYMPO) Board meeting, 4 p.m., Wednesday, Feb. 15, 1015 Fair St., Prescott.

Persons who require a reasonable accommodation based on language or disability should contact Tricia Lewis at 928-606-2420 or email tlewis@azdot.gov. Requests should be made as early as possible to ensure the state has an opportunity to address the accommodation.

This Week's Circulares

HOVER FOR CIRCULAR JCPenney

HOVER FOR CIRCULAR Mattress Firm

HOVER FOR CIRCULAR Dollar General

HOVER FOR CIRCULAR Walmart

Powered by



MOST READ

7 days

30 days

Unusual animals stop traffic in Williamson Valley

Need 2 Know: Prescott Valley Crossroads getting two new developments, Soldi Creative Cuisine closing, Mogies reopening

Body of missing Prescott Valley man found

2 stabbed in Prescott fight; Phoenix man arrested

Police activity shuts down Mobile Circle West in Prescott Valley

Missing man found dead

Governor ready to fight if Obama creates monument

Renting, photo radar, notices, fines, among new laws, a few started in August, some kicked in Jan. 1

2 storms to bring rain to much of Arizona, snow to Flagstaff

Prescott movie theater moves to reserved seating

Sign in to favorite
this

Discuss
3 comments

More like this story

Overnight paving work planned this weekend on Highway 89 between Prescott, Chino Valley
Paving work nears completion on Hwy 89 between Prescott, Chino: Project estimated to be complete by August
Study focuses on reconfiguration of Highway 89/Willow Creek
Review of ranch development shifts from water to traffic
Would impact I-40, Highway 89, Big Chino
Willow Creek realignment to begin by Thanksgiving

Sign in to comment

COMMENTS

Comments are not posted immediately. Submissions must adhere to our Use of Service Terms of Use agreement. Rambling or nonsensical comments may not be posted. Comment submissions may not exceed a 200 word limit, and in order for us to reasonably manage this feature we may limit excessive comment entries.



IH8Politics 6 hours, 42 minutes ago

0

Why is it that ADOT continues to put funding into roads that are not nearly as busy as others, roads like Hwy. 169 that have non-stop traffic for 15 miles on a 2 lane Hwy., and has a ton of semi traffic as well as passenger cars with fatal accidents weekly? ADOT owns the right of way to make 169 a 4 lane Hwy....

[Sign in to suggest removal](#)

[Sign in to reply](#)



pvtom 6 hours, 21 minutes ago

0

These ADOT public meetings are a joke. Behind the scenes it is the operation of unrecorded meetings/phone calls between political forces that decide "what" will happen. The "missing" arm of the 89-69 Interchange is a prime example. It was eliminated from final drawings without ANY comments as to "WHY". I found out why by digging.

[Sign in to suggest removal](#)

[Sign in to reply](#)



Yabbadabbadoo 5 hours, 59 minutes ago

0

Put at least 10 roundabouts in.

[Sign in to suggest removal](#)

[Sign in to reply](#)



williamgauslow 2 hours, 33 minutes ago

0

Should change Highway 89's name to Roundabout Way. Leave the two lane section thru the Delis "as is."

[Sign in to suggest removal](#)

[Sign in to reply](#)

CV Review - Jan. 11

ADOT: More roundabouts planned for Highway 89 203 accidents in five years in 13-mile stretch of road



Photo by Sue Tone

Alvin Stump speaks at the Thursday, Jan. 5 Paulden Area Community Organization meeting, explaining plans for improvements on Highway 89.



By Sue Tone

☒ Ionenotes

Originally Published: January 11, 2017 5:40 a.m.

Plans to widen Highway 89 to four lanes on a 13-mile segment of road between Chino Valley and Paulden came as welcome news to most of the more than 60 audience members attending the Jan. 5 Paulden Area Community Organization meeting.

Only one resident expressed concerns that a wider road would bring developers; he preferred building passing lanes instead a widening of the highway.

Alvin Stump, Northwest District engineer with the Arizona Department of Transportation (ADOT), presented plans and a rough timeline for proposed work on Highway 89 extending from Road 3 North at the north end of Chino Valley northward to past the Wishing Well intersection within the Kaibab National Forest boundary.

Traffic congestion and accident issues on this stretch have led ADOT to plan for widening the road to four lanes, adding turn lanes, and putting in roundabouts.

At the mention of roundabouts, some in the audience voiced their disappointment. However, as the meeting progressed, many defended the benefits of roundabouts.

"I can appreciate not everybody's a fan of roundabouts. I'm not a fan of signals," Stump said. "You put in a signal, it doesn't control the speed. Drivers still blow through the intersection. Roundabouts force you to slow down. Fatalities are reduced by 90 percent."

Most of the 203 accidents reported between 2010 and 2014 occurred between Road 3 North and Road 4 North, Stump said, with a significant number between Rolling Hills Road and Paulden.

CRASHING CONCERN

During five years, from 2010 through 2014, ADOT reported these incidents on Highway 89 for the 13 miles north of Perkinsville Road:

203 accidents

62 injury accidents

3 fatalities

Since 2014, there have been an additional two fatalities

This Week's Circulars



HOVER FOR CIRCULAR

MATTRESS FIRM



HOVER FOR CIRCULAR

SPOT



HOVER FOR CIRCULAR

Walmart



HOVER FOR CIRCULAR

DOLLAR GENERAL

Powered by

MOST READ

7 days

30 days

Yavapai College gives potential Chino speedway the silent treatment

School district deals with substitute crisis

3 injured in Friday Paulden crash

Chino Valley Police report Jan. 4, 2017

VIDEO: Chino Valley teen takes to blacksmithing

People & Places: Local residents express their hopes for 2017

Top Chino Valley stories of 2016

Missing man found dead

Letter: Sad but true

Editorial: Why we believe what we believe

Based on traffic count studies at intersections, ADOT plans to expand Highway 89 to four lanes with a raised 8-foot median and 5-foot sidewalks on both sides between Road 3 North and Road 5 North. From Road 5 North to Sweet Valley/Old 89, it also plans four lanes with an open median with 4-foot shoulders, and 10-foot shoulders on the outside, including turn lanes at key intersections.

Traffic at Big Chino Road is approaching the point of needing a signal, Stump said. Little Ranch Road and Bramble Road are good candidates for roundabouts.

ADOT will be adding turn lanes through Paulden where the Post Office and the Pink Store are located, and may drop the speed limit to 45. This is in the design stage now.

Based on attendees' comments, other proposals ADOT is looking at met with their approval. These include full intersections at Old 89, Frontier, Rolling Hills, Little Ranch and Sweet Valley roads; a passing lane between Old Highway 89 and Frontier Road; and passing lanes further north between the forest boundary and Hell Canyon.

The time frame for completing the work is based on availability of funds. County Supervisor Craig Brown said the county lost about \$13 million in Highway User Revenue

Funds (HURF). He supports taking "baby steps" by breaking the 13-mile segment into smaller projects, as ADOT is proposing.

"When there is a little bit of money left over from other (ADOT) projects, we'll fight for that money," Brown said.

The entire project could take up to 20 years and about \$60 million to complete.

ADOT representatives will make the same presentation and answer questions at three more venues:

- Chino Valley Town Council meeting at 6 p.m., Tuesday, Jan. 10, at council chambers, 202 N. Highway 89, Chino Valley.
- Yavapai County Board of Supervisors meeting at 9 a.m., Wednesday, Feb. 1, 1015 Fair St., Prescott.
- Central Yavapai Metropolitan Planning Organization (CYMPO) Board meeting, 4 p.m., Wednesday, Feb. 15, 1015 Fair St., Prescott.

Follow Sue Tone on Twitter @ToneNotes. Reach her at 928-445-3333 ext. 2043 or 928-642-7867.

Sign in to favorite
this

Discuss
Comment

More like this story

County considers Road 1 North traffic light by 2018

Three new roundabouts under review for Northern Chino Valley

Road 1 North traffic signal pushed back to 2022

ADOT says roundabout safer Residents tell ADOT their concerns on proposed Road 4 South roundabout

CV Council allows ADOT to proceed with design of roundabout at 89 and Road 4 South

Sign in to comment

COMMENTS

Comments are not posted immediately. Submissions must adhere to our Use of Service Terms of Use agreement. Rambling or nonsensical comments may not be posted. Comment submissions may not exceed a 200 word limit, and in order for us to reasonably manage this feature we may limit excessive comment entries.

Use the comment form below to begin a discussion about this content.

Daily Courier

January 11, 2017

ADOT unveils plans for Highway 89 between Chino Valley, Paulden

More planned roundabouts thrill (or not) Paulden residents



By Sue Tone
tonenotes

Originally Published January 11, 2017 5:55 a.m.

Plans to widen Highway 89 to four lanes on a 13-mile segment of road between Chino Valley and Paulden came as welcome news to most of the more than 60 audience members attending the Jan. 5 Paulden Area Community Organization meeting. Only one resident expressed concerns that a wider road would bring developers; he preferred building passing lanes instead a widening of the highway.

Alvin Stump, Northwest District engineer with the Arizona Department of Transportation, presented plans and a rough timeline for proposed work on Highway 89 extending from Road 3 North at the north end of Chino Valley northward to past the Wishing Well intersection within the Kaibab National Forest boundary.

Traffic congestion and accident issues on this stretch have led ADOT to plan for widening the road to four lanes, adding turn lanes, and putting in roundabouts.

At the mention of roundabouts, some in the audience voiced their disappointment. However, as the meeting progressed, many defended the benefits of roundabouts.

"I can appreciate not everybody's a fan of roundabouts. I'm not a fan of signals," Stump said. "You put in a signal, it doesn't control the speed. Drivers still blow through the intersection. Roundabouts force you to slow down. Fatalities are reduced by 90 percent."

Most of the 203 accidents reported between 2010 and 2014 occurred between Road 3 North and Road 4 North, Stump said, with a significant number between Rolling Hills Road and Paulden.

Based on traffic count studies at intersections, ADOT plans to expand Highway 89 to four lanes with a raised 8-foot median and 5-foot sidewalks on both sides between Road 3 North and Road 5 North. From Road 5 North to Sweet Valley/Old 89, it also plans four lanes with an open median with 4-foot shoulders, and 10-foot shoulders on the outside, including turn lanes at key intersections.

Traffic at Big Chino Road is approaching the point of needing a signal, Stump said. Little Ranch Road and Bramble Road are good candidates for roundabouts.

ADOT will be adding turn lanes through Paulden where the Post Office and the Pink Store are located, and may drop the speed limit to 45. This is in the design stage now.

Based on attendees' comments, other proposals ADOT is looking at met with their approval. These include full intersections at Old 89, Frontier, Rolling Hills, Little Ranch and Sweet Valley roads; a passing lane between Old Highway 89 and Frontier Road; and passing lanes further north between the forest boundary and Hell Canyon.

The time frame for completing the work is based on availability of funds. County Supervisor Craig Brown said the county lost about \$13 million in Highway User Revenue Funds (HURF). He supports taking "baby steps" by breaking the 13-mile segment into smaller projects, as ADOT is proposing.

During the five years between 2010 and 2014, 203 accidents have occurred on the 13-mile segment between Chino Valley and Paulden, including:

62 injury accidents

3 fatalities

Since 2014, there have been additional accidents, including at least two fatalities, according to ADOT.

This Week's Circulares

HOVER FOR CIRCULAR

HOVER FOR CIRCULAR

HOVER FOR CIRCULAR

HOVER FOR CIRCULAR

Powered by

MOST READ

7 days

30 days

Prescott man arrested, charged with sexual exploitation of a minor

Prescott man gets 30 years for child prostitution

Defendant being tried in 2014 homicide of Prescott Valley teen

Shooting range cleanup to cost Forest Service nearly \$1 million

NEED2KNOW: Free car washes; tri-city area gas prices stay low

71-year-old bucked off mule on Peavine Trail

Criminals' possessions benefit local police

Man survives 20-foot fall on Granite Mountain (VIDEO)

New registration requirements raises questions among business, rental owners

Child-sex trial underway for defendant from Prescott Valley

"When there is a little bit of money left over from other (ADOT) projects, we'll fight for that money," Brown said.

The entire project could take up to 20 years and about \$60 million to complete.

ADOT representatives will make the same presentation and answer questions at three more venues:

- Chino Valley Town Council meeting at 6 p.m., Tuesday, Jan. 10, at council chambers, 202 N. Highway 89, Chino Valley.
- Yavapai County Board of Supervisors meeting at 9 a.m., Wednesday, Feb. 1, 1015 Fair St., Prescott.
- Central Yavapai Metropolitan Planning Organization (CYMPO) Board meeting, 4 p.m., Wednesday, Feb. 15, 1015 Fair St., Prescott.

Sign in to favorite
this

Discuss
3 comments

More like this story

Chino Valley traffic signal could bump Highway 69 widening priority
Hwy 89 widening may be postponed
2016 will be year for new turn lanes, signals in ADOT's Prescott District
Going round and round - Prescott official: Roundabouts are 'safer choice'
Chino Valley/ Prescott route will be affected by construction well into 2015

Sign in to comment

COMMENTS

Comments are not posted immediately. Submissions must adhere to our [Use of Service](#) [Terms of Use](#) agreement. Rambling or nonsensical comments may not be posted. Comment submissions may not exceed a 200 word limit, and in order for us to reasonably manage this feature we may limit excessive comment entries.



BirdOfFire 2 hours, 45 minutes ago

0

I was excited to hear this road is finally, finally, going to be widened, until I read it will take 20 years to do it! What a joke. Are you kidding me? 20 years? This road needed to be widened 10 years ago. Imagine what it will be like in 20 years when complete! By then it will need to be 6 lanes. Wow, so ADOT just wasted our tax paying dollars to do a traffic study 20 years in the future. The study will be ineffective by then. What a waste this meeting, article and discussion are. Widen the road already! Do it in 5 years!

Sign in to suggest removal

Sign in to reply



DrSam 2 hours, 26 minutes ago

0

Seriously? Announcing the CV Town Council meeting the DAY AFTER it happens??? What a bush-league move.

-Roundabouts cause accidents. "Forcing" a slowdown on a long flat straight highway full of 20-ton trucks is an amateur thought process. This is a major commerce route alternate to I-17/Flagstaff!! I swear we need to drain the ADOT swamp next!

-How about fixing the worst high-speed highway in the state: the stretch north of Drake turnoff where pavement is broken, heaving and not flat nor graded to 65+ MPH vehicles.

-Maybe if ADOT officials tried driving these roads in any vehicle besides a new, state-maintained taxpayer paid car, they'd see/feel how unsafe these roads are at speed! UNSAFE! -add another circle, what morons. While they're at it, how about a high mound and statues to block any view of on-coming vehicles?!

Sign in to suggest removal

Sign in to reply


Public Involvement Photos




Picture 1



Picture 2



Picture 3



Picture 4



Picture 5

APPENDIX FR-1

Prescoping Reports, Field Review Reports, and Field Summary Notes



**Planning Assistance for Rural Areas
PRELIMINARY SCOPING REPORT**

GENERAL PROJECT INFORMATION

Date: March 29, 2017	ADOT Project Manager: Dan Gabiou
Project Name: Widen to Four-lane Section with Raised Median from Butterfield Road to Road 4N	
City/Town: Town of Chino Valley	County: Yavapai
COG/MPO: Central Yavapai Metropolitan Planning Organization	ADOT District: Northwest District
Primary Route/Street: State Route 89	
Beginning Limit: Butterfield Road (MP 328.95)	
End Limit: Road 4N (MP 330.18)	
Project Length: 1.23 miles	
Right-of-Way Ownership(s) (where proposed project construction would occur): <i>(Check all that apply)</i> <input type="checkbox"/> City/Town; <input type="checkbox"/> County; <input checked="" type="checkbox"/> ADOT; <input type="checkbox"/> Private; <input type="checkbox"/> Federal; <input type="checkbox"/> Tribal; <input type="checkbox"/> Other	
Adjacent Land Ownership(s): <i>(Check all that apply)</i> <input checked="" type="checkbox"/> City/Town; <input type="checkbox"/> County; <input type="checkbox"/> ADOT; <input checked="" type="checkbox"/> Private; <input type="checkbox"/> Federal; <input type="checkbox"/> Tribal; <input type="checkbox"/> Other	

LOCAL PUBLIC AGENCY (LPA) or TRIBAL GOVERNMENT INFORMATION
(If applicable)

LPA/Tribal Name: Town of Chino Valley	
LPA/Tribal Contact: Michael Lopez	
Email Address: mlopez@chinoaz.net	Phone Number: 928-636-7140
Administration: <input checked="" type="checkbox"/> ADOT Administered <input type="checkbox"/> Self-Administered <input type="checkbox"/> Certification Acceptance	

PROJECT NEED

Within the project area, the five year crash history indicates that crashes are generally clustered around intersections with a high number of left-turn crashes. Many of these appear to be attributable to a lack of access management. Driveway spacing within the corridor is dense and exceeds the recommended spacing in the Draft ADOT Access Management Guidelines.

The population in Chino Valley is anticipated to grow 73% over the next 25 years; employment will increase 100%. There is a development platted between Road 3N and Road 3½N, so traffic volumes along SR 89 are increasing due to general growth as well as additional commercial and recreational traffic to I-40 and beyond. The anticipated increase in traffic volumes will compound the existing safety and access management issues.

PROJECT PURPOSE

What is the Primary Purpose of the Project?	<input type="checkbox"/> Preservation	<input type="checkbox"/> Modernization	<input checked="" type="checkbox"/> Expansion
<p>The primary purpose of the project is to widen SR 89 from Butterfield Road to Road 4N to a four-lane typical urban section with a raised median. South of Road 3N, there is an existing two way left turn lane, which will be converted to a raised median to improve access management and reduce the number of conflict points. The existing section transitions to a two-lane road just north of Road 3N; this section will be widened to four lanes with a raised median to improve access management and reduce the number of conflict points. These improvements compliment the recently constructed roundabouts at Perkinsville Road and Road 4N.</p>			



Planning Assistance for Rural Areas PRELIMINARY SCOPING REPORT

PROJECT RISKS

Check any risks identified that may impact the project's scope, schedule, or budget:

<input checked="" type="checkbox"/> Access / Traffic Control / Detour Issues	<input checked="" type="checkbox"/> Right-of-Way
<input type="checkbox"/> Constructability / Construction Window Issues	<input checked="" type="checkbox"/> Environmental
<input type="checkbox"/> Stakeholder Issues	<input checked="" type="checkbox"/> Utilities
<input type="checkbox"/> Structures & Geotech	<input type="checkbox"/> Other

Right-of-way: Project improvements will be located within the existing right-of-way. Temporary Construction Easements (TCE)s may be required south of Road 3N on both sides of the roadway and at some driveways. TCEs may be required just north of Road 3N on the west side of SR 89. Driveways will be reconstructed per ADOT standard detail C-05.20.

Traffic control will be needed during construction to protect the work zone, and phasing will need to accommodate the Town of Chino Valley emergency services located west of SR 89 on Road 3N.

Environmental: There is a potential historic house structure on the northwest corner of Road 3N. This is an area that should be avoided if possible. If impacts are necessary, design should seek to mitigate impacts.

Utilities: Utility relocation is required for this widening project. Overhead power lines run along the east and/or west side(s) of SR 89 for the majority of the project limits which will need to be relocated prior to construction. There are locations where these power lines cross SR 89, which should be protected during construction. Various utility service lines may cross SR 89 or be within the disturbed limits, including gas, cable, electric, and irrigation. Existing drainage facilities will be impacted by the proposed project based on conceptual design, including extending a culvert just south of Commercial Way. There are roadside drainage ditches and a storm drain pipe under the southbound lane(s) north in the southern portion of the project. Utility investigation is required during design.

POTENTIAL FUNDING SOURCE(S)

Anticipated Project Design/Construction Funding Type: (Check all that apply)	<input type="checkbox"/> STBG	<input type="checkbox"/> TAP	<input checked="" type="checkbox"/> HSIP	<input checked="" type="checkbox"/> State
	<input checked="" type="checkbox"/> Local	<input type="checkbox"/> Private	<input type="checkbox"/> Tribal	<input type="checkbox"/> Other:

COST ESTIMATE

Preliminary Engineering \$128,000	Design \$385,000	Right-of-Way \$0	Construction \$5,857,000	Total \$6,371,000
--------------------------------------	---------------------	---------------------	-----------------------------	----------------------

RECOMMENDED PROJECT DELIVERY

Delivery: ☒ Design-Bid-Build ☐ Design-Build ☐ Other: Indefinite quantities contract


Design Program Year: FY 2020 – FY 2025

Construction Program Year: FY 2021 – FY 2026

ATTACHMENTS

- 1) State Location Map
- 2) Project Vicinity Map
- 3) Project Scope of Work
- 4) Project Schedule
- 5) Itemized Cost Estimate
- 6) Conceptual Design Plans (not to exceed 15% design)
- 7) Final Field Review Report

ATTACHMENT 1 – STATE LOCATION MAP



ATTACHMENT 2 – PROJECT VICINITY MAP



Project Limits: Butterfield Road to Road 4N

ATTACHMENT 3 – SCOPE OF WORK

SCOPE OF WORK

Widen SR 89 to four-lane facility, from Butterfield Road to the roundabout at Road 4N. Typical section per Urban Highway Typical Section UA as shown in Figure 306.4A of the ADOT Roadway Design Guidelines (RDG), modified to have an eight-foot raised median and 5-foot sidewalk on both sides.


- Remove approximately 2,800 feet of concrete curb and gutter.
- Remove approximately 28,100 square yards of existing asphaltic concrete pavement, including saw cutting.
- Construct approximately 33,100 square yards of new asphaltic concrete pavement.
- Construct approximately 11,200 feet of concrete curb and 9,600 feet of concrete curb and gutter.
- Construct 54,500 square feet of 5-foot wide concrete sidewalk.
- Reconstruct 19 driveways (ADOT standard detail C-05.20).
- Construct 22 PROWAG compliant sidewalk ramps.
- Provide approximately 650 square yards of median paving.
- Provide approximately 37,300 feet of pavement marking on new pavement.
- Provide landscaping, including decomposed granite in median and adjacent to sidewalk.
- Approximately 11,400 cubic yards of earthwork.

SCOPE ITEMS CONSIDERED, BUT NOT INCLUDED

- Construct two-lane roundabout at intersection of SR 89 and Road 3N. Instead, retiming the existing signal with a protected left-turn phase will be implemented. If the countermeasure underperforms, a roundabout may be reconsidered. If roundabout constructed at Road 3N, then construct raised median at Butterfield Road to make it right-in right-out only.
- Construct roundabout at Road 3 1/2N, which is to be considered with future development.
- Provide detached sidewalk in lieu of attached sidewalk (could be included during project design).
- Driveway consolidation was considered, but was not included due to anticipated implementation challenges.
- Driveway elimination was considered, but was not included due to anticipated implementation challenges.

Pursuant to 23 USC 409: Notwithstanding any other provision of law, reports, surveys, schedules, lists, or data compiled or collected for the purpose of identifying, evaluating, or planning the safety enhancement of potential accident sites, hazardous roadway conditions, or rail-way-highway crossings, pursuant to sections 130, 144, and 148 [152] of this title or for the purpose of developing any highway safety construction improvement project which may be implemented utilizing Federal-aid highway funds shall not be subject to discovery or admitted into evidence in a Federal or State court proceeding or considered for other purposes in any action for damages arising from any occurrence at a location mentioned or addressed in such reports, surveys, schedules, lists, or data.

ATTACHMENT 4 – PROJECT SCHEDULE



ATTACHMENT 5 – ITEMIZED COST ESTIMATE

Butterfield Road to Road 3N	MP	329.00	to MP	329.20
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	6,653	\$2.00	\$13,400
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	739	\$8.00	\$6,000
SAW CUTTING	L.FT.	1,130	\$1.50	\$1,700
EARTHWORK	L.SUM	1	\$3,856.00	\$3,900
ASPHALT SURFACE COURSE	SQ.YD.	6,653	\$6.00	\$40,000
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	277	\$50.00	\$13,900
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	6,864	\$0.50	\$3,500
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$20,000.00	\$20,000
CONCRETE CURB	L.FT.	1,219	\$20.00	\$24,400
CONCRETE CURB AND GUTTER	L.FT.	0	\$15.00	\$0
CONCRETE SIDEWALK	SQ.FT.	10,129	\$3.00	\$30,400
CONCRETE SIDEWALK RAMP	EACH	12	\$2,000.00	\$24,000
CONCRETE DRIVEWAY	SQ.FT.	815	\$15.00	\$12,300
MEDIAN PAVING	SQ.YD.	553	\$60.00	\$33,200
STORM SEWER ALLOWANCE	L.SUM	0	\$0.00	\$0
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL \$226,700

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$18,200.00	\$18,200
Quality Control (1%)	COST	1.00%	\$2,300.00	\$2,300
Construction Surveying (1.5%)	COST	1.50%	\$3,500.00	\$3,500
Erosion Control (1%)	COST	1.00%	\$2,300.00	\$2,300
Mobilization (12%)	COST	12.00%	\$27,300.00	\$27,300

PROJECTWIDE SUBTOTAL \$53,600

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$84,100.00	\$84,100
---	------	--------	-------------	----------

PROJECTWIDE TOTAL \$137,700

Construction Engineering (9%)	COST	9.00%	\$32,800.00	\$32,800
Construction Contingencies (5%)	COST	5.00%	\$18,300.00	\$18,300
Engineering Design (10%)	COST	10.00%	\$36,500.00	\$36,500
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL \$87,600

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$37,800.00	\$37,800
---	------	-------	-------------	----------

SUMMARY

ITEM TOTAL	\$226,700
PROJECTWIDE TOTAL	\$137,700
OTHER COST TOTAL	\$87,600
ICAP	\$37,800
TOTAL	\$490,000

Road 3N to Road 4N	MP	329.20	to MP	330.16
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	2,800	\$5.00	\$14,000
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	27,314	\$8.00	\$218,600
SAW CUTTING	L.FT.	301	\$1.50	\$500
EARTHWORK	L.SUM	1	\$87,100.00	\$87,100
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	32,820	\$50.00	\$1,641,000
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	30,413	\$0.50	\$15,300
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$25,000.00	\$25,000
CONCRETE CURB	L.FT.	10,000	\$20.00	\$200,000
CONCRETE CURB AND GUTTER	L.FT.	9,551	\$15.00	\$143,300
CONCRETE SIDEWALK	SQ.FT.	44,388	\$3.00	\$133,200
CONCRETE SIDEWALK RAMP	EACH	10	\$2,000.00	\$20,000
CONCRETE DRIVEWAY	SQ.FT.	9,268	\$15.00	\$139,100
MEDIAN PAVING	SQ.YD.	118	\$60.00	\$7,100
STORM SEWER ALLOWANCE	L.SUM	1	\$82,000.00	\$82,000
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL **\$2,726,200**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$218,100.00	\$218,100
Quality Control (1%)	COST	1.00%	\$27,300.00	\$27,300
Construction Surveying (1.5%)	COST	1.50%	\$40,900.00	\$40,900
Erosion Control (1%)	COST	1.00%	\$27,300.00	\$27,300
Mobilization (12%)	COST	12.00%	\$327,200.00	\$327,200

PROJECTWIDE SUBTOTAL **\$640,800**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$1,010,100.00	\$1,010,100
---	------	--------	----------------	-------------

PROJECTWIDE TOTAL **\$1,650,900**

Construction Engineering (9%)	COST	9.00%	\$394,000.00	\$394,000
Construction Contingencies (5%)	COST	5.00%	\$218,900.00	\$218,900
Engineering Design (10%)	COST	10.00%	\$437,800.00	\$437,800
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$1,050,700**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$453,800.00	\$453,800
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	<u>\$2,726,200</u>
PROJECTWIDE TOTAL	<u>\$1,650,900</u>
OTHER COST TOTAL	<u>\$1,050,700</u>
ICAP	<u>\$453,800</u>
TOTAL	<u>\$5,890,000</u>

Road 3N Roundabout	MP	329.20	to MP	329.20
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	2,600	\$5.00	\$13,000
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	7,200	\$8.00	\$57,600
SAW CUTTING	L.FT.	288	\$1.50	\$500
EARTHWORK	L.SUM	1	\$19,424.00	\$19,500
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	6,899	\$50.00	\$345,000
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	3,000	\$0.50	\$1,500
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$15,000.00	\$15,000
CONCRETE CURB	L.FT.	1,905	\$20.00	\$38,100
CONCRETE CURB AND GUTTER	L.FT.	2,400	\$15.00	\$36,000
CONCRETE SIDEWALK	SQ.FT.	10,685	\$3.00	\$32,100
CONCRETE SIDEWALK RAMP	EACH	16	\$2,000.00	\$32,000
CONCRETE DRIVEWAY	SQ.FT.	2,746	\$15.00	\$41,200
MEDIAN PAVING	SQ.YD.	948	\$60.00	\$56,900
STORM SEWER ALLOWANCE	L.SUM	1	\$200,000.00	\$200,000
TRUCK APRON	SQ.YD.	317	\$135.00	\$42,800

ITEM TOTAL **\$931,200**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$74,500.00	\$74,500
Quality Control (1%)	COST	1.00%	\$9,400.00	\$9,400
Construction Surveying (1.5%)	COST	1.50%	\$14,000.00	\$14,000
Erosion Control (1%)	COST	1.00%	\$9,400.00	\$9,400
Mobilization (12%)	COST	12.00%	\$111,800.00	\$111,800

PROJECTWIDE SUBTOTAL **\$219,100**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$345,100.00	\$345,100
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL **\$564,200**

Construction Engineering (9%)	COST	9.00%	\$134,600.00	\$134,600
Construction Contingencies (5%)	COST	5.00%	\$74,800.00	\$74,800
Engineering Design (10%)	COST	10.00%	\$149,600.00	\$149,600
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$359,000**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$155,100.00	\$155,100
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	\$931,200
PROJECTWIDE TOTAL	\$564,200
OTHER COST TOTAL	\$359,000
ICAP	\$155,100
TOTAL	\$2,010,000



PLANNING ASSISTANCE FOR RURAL AREAS PRELIMINARY SCOPING FIELD REVIEW REPORT

The purpose of Preliminary Scoping (Pre-Scoping) is to more accurately develop a project's Scope of Work (SOW), Schedule, and Itemized Cost Estimate prior to programming a project in a Transportation Improvement Program (TIP). This process will help to streamline project design by reducing upfront work, scope changes, project delays, and TIP Amendments.

The information gathered from the Pre-Scoping Field Review Report will be used to develop the project's SOW, Schedule, and Itemized Cost Estimate, which will be summarized in the Pre-Scoping Report.

Pre-Scoping Field Review Forms are to be completed by functional groups responsible for each area as needed (based on the project scope). Not all projects will require all Field Review Forms to be filled out.

Field Review Form	Name	Date Completed
Background Data	Benjamin Barkan	January 10, 2017
Bridge – Design		
Bridge – Hydraulics / Drainage	Dan Gabiou	January 25, 2017
District – Constructability		
District – Maintenance		
Environmental	Dan Gabiou and Justin Hoppmann	January 25, 2017
Geotechnical		
Pavement / Materials		
Right-of-Way		
Roadway / Drainage	Roger McCormick	January 25, 2017
Traffic / Safety	Dan Gabiou	January 25, 2017
Utilities		

The below 23 USC 409 disclaimer is to be included in the Final Pre-Scoping Report and Field Review Report:

23 USC 409 Disclaimer:

Notwithstanding any other provision of law, reports, surveys, schedules, lists, or data compiled or collected for the purpose of identifying, evaluating, or planning the safety enhancement of potential accident sites, hazardous roadway conditions, or rail-way-highway crossings, pursuant to sections 130, 144, and 148 [152] of this title or for the purpose of developing any highway safety construction improvement project which may be implemented utilizing Federal-aid highway funds shall not be subject to discovery or admitted into evidence in a Federal or State court proceeding or considered for other purposes in any action for damages arising from any occurrence at a location mentioned or addressed in such reports, surveys, schedules, lists, or data.

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

BACKGROUND DATA
(To be completed prior to KOM and Field Review)

Previous Projects

ADOT / LPA / Tribal Project Number	Begin Milepost / Cross Street	End Milepost / Cross Street	Length (miles)	As-Built Date	Description
H833001C				09/2016	Roundabout Construction at Perkinsville Road and SR 89
H827801C				09/2016	Roundabout Construction at Road 4 North and SR 89

ITEM	YES	NO	If Yes, Describe (or see below)
Past Study Completed?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<p>CYMPO Title VI Plan, June 2016 No protected populations identified.</p> <p>AASHTO U.S. Bicycle Route System, August 2015 U.S. Bicycle Route (USBR 79) recommended to go from Prescott to I-40 along SR 89.</p> <p>CYMPO Regional Transportation Plan Update 2040, April 2015 Reprioritization of transportation investments through the 2040 planning horizon. RTP indicates widening to six lanes from Deep Well Ranch Road to Center Street is included in the FY2025 to FY2040 planning horizon; this segment is south of the Study Area. The Great Western Extension is included in the FY2025 to FY 2040 planning horizon and is a new two-lane facility located north of SR 89A and will intersect SR 89 near Road 5 South.</p> <p>State Route 89 Access Management Plan, June 1997 One-mile spacing of major, signalized intersections and non-major intersections with right-in, right-out, and left-in access at half-mile spacing. Driveways with direct access to SR 89 consolidated or eliminated when possible.</p> <p>Chino Valley Extension Study, February 2009 New four-lane access controlled road, Chino Valley Extension, to serve as an alternate route for SR 89 in Chino Valley and Paulden areas (recommended intersection approximately 1 mile south of Big Chino Road).</p>
Project included in TIP?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not programmed
Is AADT available?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	See below
Is crash data available?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<p>Corridor Summary: SR 89, Perkinsville Road to Road 4N. 51 crashes reported in a 5-year study period (2011 thru 2015). 7 angle crashes, 6 left turn crashes, 16 rear end crashes, 5 run off the road crashes, 10 sideswipe crashes, 1 animal crash, 2 single vehicle crashes, and 4 other crashes that do not fall into these categories. No fatal injury, but 5 crashes resulted in incapacitating injury.</p>

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

Known Transit needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Known Freight needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Potential increase in freight traffic once Hell Canyon Bridge is replaced.
Known Railroad needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Known Airport needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Known Bike needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	SR 89 is identified as part of the Adventure Cycling Association Grand Canyon Connector.
Known Pedestrian / ADA needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide new sidewalks. Update pedestrian facilities to be PROWAG compliant. Investigate detached sidewalk.
Other needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Accommodate Town emergency services located west of SR89 on Road 3N, utility relocations, traffic signal retiming.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

BMP 328.20 Road 2 North			EMP 329.20 Road 3 North		
	NB AADT	SB AADT	AADT	T Factor %	Future 2035 AADT
2015	9,545	10,142	19,687	7.3	31,499
2014	9,168	9,730	18,898	6.5	N/A
2013	9,130	9,701	18,850	7.6	N/A
2012	9,174	9,567	18,599	7.9	N/A
2011	9,113	9,278	18,391	10.0	N/A

BMP 329.20 Road 3 North			EMP 330.20 Road 4 North		
	NB AADT	SB AADT	AADT	T Factor %	Future 2035 AADT
2015	6,006	6,028	12,034	8.0	19,254
2014	5,464	5,494	10,959	7.3	N/A
2013	5,504	5,532	11,035	7.9	N/A
2012	3,255	5,575	10,036	7.5	N/A
2011	5,378	5,316	10,695	12.0	N/A

Source: <https://www.azdot.gov/planning/DataandAnalysis/average-annual-daily-traffic>

Traffic Counts were conducted for this study March 23, 2016. Daily traffic volumes were approximately 12,900 just north of Road 3N.

Study forecast projected 2036 AADT of 16,538 vpd.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

BRIDGE DESIGN FIELD REVIEW FORM

BRIDGE NO. _____

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Replace Bridge	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Span Bridge	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Box Culvert	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Unique Structure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Replace Bridge Deck	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Widen	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Rail/Sidewalk Barrier	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Corrosion Protection	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Structural Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Deck	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Superstructure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Substructure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Concrete Wearing Course	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Expansion Joints	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Approach Panels	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Erosion/Scour Protection	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Painting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Over Water?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Utility accommodation	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Need Asbestos Assessed?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Removals	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Br Inventory Sheet indicates that Accelerated Bridge Construction (ABC) should be considered?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

--

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

BRIDGE HYDRAULICS / DRAINAGE FIELD REVIEW FORM

ITEM	ITEM NEEDED			Struc. # If any	RP	LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE			
Mainline Culverts <input type="checkbox"/> Repair <input type="checkbox"/> Line <input type="checkbox"/> Replace <input checked="" type="checkbox"/> Extend	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			Extend culvert between Road 3½N and Commercial Way to accommodate roadway widening.
Sideline Culverts <input type="checkbox"/> Replace <input type="checkbox"/> Extend	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>			Culverts under drives exist, but will likely not be disturbed. Depends on final grading.
Tile	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Storm Sewer	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>			Storm drain system identified under northbound lanes, north of Road 3N. Outlet may need adjusted to accommodate widening.
Erosion Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Waterway analysis	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Risk Assessment	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Ditch Hearing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Special Structures	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Weirs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Vortex	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Fish Passage	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Ponds	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Other:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project Limits: P1A and P2-Perkinsville Road to Road 4N

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

DISTRICT - CONSTRUCTION FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Detour ^a	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Temporary Construction ^a	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	TCEs may be required at existing roadway intersections, depending on limits of paving and sidewalk improvements.
Staging ^a	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Stockpiling	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Innovative Contracting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Control	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Construction phasing will be required to accommodate daily traffic and emergency services.
Other	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

--

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

DISTRICT - MAINTENANCE FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Striping	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Signing	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Lighting	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Curb & Gutter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Low gravel shoulder correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Guard Rail Repair	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Fencing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Noisewall	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Drainage Repair	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Basin on SB side of SR 89 in front of local business (Fix Bros Auto)
Erosion Area Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Flooding Area Correction	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Snow Trap, Storage, Icing Correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
RWIS	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Anti-Icing System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Frost Heave Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Rest Area Work	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Landscaping	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Millings needed	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Other salvage items	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

ENVIRONMENTAL FIELD REVIEW FORM

ITEM	YES	NO	MAYBE	LOCATION / NOTES / BUDGET-SCHEDULE IMPACTS
4(f) / 6(f) sites	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	A potentially historic house structure is located on the NW corner of Road 3N and SR 89.
Extensive Cultural/Historical Work	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Impacts to potentially historic adjacent properties would need to be evaluated to determine level of effort.
Title VI/Environmental Justice Populations	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The project area has a higher percentage of Hispanic residents than the surrounding county; however, no disproportionate impacts are anticipated.
Noise Concerns	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	There are several adjacent properties with noise sensitive uses (residential, churches, etc) Because the project would increase capacity, a noise analysis would need to be completed.
Jurisdictional Waters or Wetlands	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	None present in the project area.
Floodplain	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The project falls within Flood Zone X per FEMA mapping, or areas determined to be outside the 0.2% annual chance floodplain.
State/Federal T&E Species	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No suitable habitat is located in the project area.
Wildlife Crossing Concerns	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No known concerns in the project area.
Hazmat or Contaminated site	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	There are no known spills or incidents within the project area. Adjacent properties include uses such as automotive repair which frequently utilize solvent and petroleum products. Additionally, one property is occupied by numerous aboveground storage tanks.
Prime or Unique Farmland	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Soils within the project area are of a type which is considered Prime Farmland if irrigated. Currently no actively irrigated farming occurs adjacent to the project area.
Air Quality Nonattainment or Maintenance Area	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known concerns in the project area.
Noxious or Invasive Species	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known concerns in the project area.
Visual Quality Concerns	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known concerns in the project area.
Public Involvement Required	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Due to business/residential impacts of access management improvements.
Significant Environmental Impacts	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Avoidance Areas	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Avoidance of the potentially historic structure on the NW corner of Road 3N is recommended.
Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Anticipated NEPA Clearance Type	Categorical Exclusion (CE) <input checked="" type="checkbox"/>	Environmental Assessment (EA) <input type="checkbox"/>	Environmental Impact Statement (EIS) <input type="checkbox"/>	N/A (No federal funds anticipated) <input type="checkbox"/>
--	--	--	---	---

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

Anticipated Permits Needed	Section 404 Permit: Nationwide Permit <input type="checkbox"/> Individual Permit <input type="checkbox"/>	Individual Section 401 Certification <input type="checkbox"/>	Section 402 Permit: AZPDES <input checked="" type="checkbox"/> NPDES <input type="checkbox"/>
-----------------------------------	--	---	--

Comments and Risk Identification:

--

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

GEOTECHNICAL FIELD REVIEW FORM

ITEM	YES	NO	MAYBE	LOCATION / NOTES / BUDGET-SCHEDULE IMPACTS
Will geotechnical borings be required?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Est Drilling/Excavation Depth: unknown at this time.
Will rock coring be required?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Will test pits be required?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Est Drilling/Excavation Depth:
Is site accessible by a 4-wheel vehicle, backhoe, or trackhoe?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Will a seismic refraction survey be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will geologic mapping be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will soil/rock lab testing be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will geotechnical investigation require a separate Environmental Clearance?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

PAVEMENT / MATERIALS FIELD REVIEW FORM

ITEM		ITEM NEEDED			LOCATION / QUANTITY / NOTES
		YES	NO	MAYBE	
Hot Mix Asphaltic Concrete Pavement	Minor Rehab/Preventative Maint (Chip Seal, Slurry Seal, etc.)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	(include lane width)
	Major Rehab (Mill & Replace Only)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Through existing 4-lane section.
	Major Rehab (Mill, Replace & Overlay)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major Rehab (Overlay Only)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Reconstruction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	(include lane width)
	Widening/Adding Turn Lanes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Through 2-lane section and intersections.
	Pavement Core	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
	Falling Weight Deflectometer Test	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Portland Cement Concrete Pavement	Joint Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Dowel Bars	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major CPR	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Minor CPR	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Widening/Turn Lanes	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Pavement Core	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Other:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sub-surface	Aggregate Base Improvement	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
	Subgrade Improvement	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
	Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Shoulder	Shoulder Work	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	(include shoulder width)
	Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Edge Drains	Edge Drain Video Insp	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Edge Drain Flushing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	New Edge Drains	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

RIGHT-OF-WAY FIELD REVIEW FORM

Location	Existing ROW Width	Owner	Comments
South of Rd 3N	100 feet	ADOT	
North of Rd 3N	150 feet to 200 feet	ADOT	ROW on west side jogs over 750 feet north of Road 3N

List all adjacent land owners within the project limits	Private owners
---	----------------

ITEM	YES	NO	MAYBE	PARCEL # / LOCATION / QUANTITY / NOTES
Potential Full-Parcel ROW Take	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Potential Partial-Parcel ROW Take	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Access Issues	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Temporary Construction Easement (TCE) required	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Drainage Easement required	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Access Easement required	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Plats needed	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

ROADWAY / DRAINAGE FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Design Exception	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
CSS Design Flexibility	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Limit impacts to the NW corner of Road 3N intersection.
Hor. Curve Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Vert. Curve Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Crown Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Super Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Side Slope Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Shlder slope correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Flatten Entrance Slopes	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sight-line Obstr. Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Guardrail	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Curb & Gutter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Retaining Walls	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Spillway	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Downdrain	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Scuppers	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
69kV lines Steel Poles	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

When considering pavement widening, a few locations that have existing utility poles could possibly need relocation due to lying within the clear zone once the road is expanded.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

TRAFFIC / SAFETY FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Bicycle Countermeasures				
Bike Lane	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pavement Markings / Signs	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	SR 89 is identified as part of the Adventure Cycling Association Grand Canyon Connector.
Shared Use Path	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Route is part of National bike route. Maintain shoulder for design.
Curve Countermeasures				
Enhanced Delineation and Friction for Horizontal Curve	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curve Warning Signs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Intersection Countermeasures				
Access Control	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Raised median.
Pedestrian Phasing	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Pedestrian Signal/ Countdown Signal	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Offset/lengthen turn lane	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Phasing/protected left turn	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Adjust traffic signal phasing/timing.
Roundabout	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Long-term roundabout at Road 3N to allow business/residential access. Roundabout at 3 1/2N. If Road 3N roundabout is constructed, then close median at Butterfield Road.
Signal Backplates with Retroreflective Borders	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Stop Bar	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Loop boxes for through lanes on NB 89, south of intersection at Road 3N, are too far from intersection and need to be moved closer.
Lane / Roadway Departure Countermeasures				
Longitudinal Rumble Strips / Stripes on 2-Lane Roads (shoulder & centerline)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Raised Median Barrier	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Safety Edge	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Shoulder	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Pedestrian Countermeasures				
ADA Improvement	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Update ADA accommodations to be PROWAG compliant.
Crosswalk	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Median and Ped Xing Island (urban / suburban area)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Hybrid Beacon	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Warning Sign (Ped Xing, No Right on Red, Yield to Peds)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Road Diet	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sidewalk	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	New 5-foot sidewalks on both sides of the road to be paid for by Chino Valley.
Traffic Calming	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Widen Shoulder	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Railroad Crossing Countermeasures				
Active Advanced Warning Sign	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Flashing Light Signals	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Gates (Automated, Channelized, Four-Quadrant)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pavement Markings	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Signage	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Train Detection System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Signal	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Warning Bell	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Wayside Horn System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

UTILITIES FIELD REVIEW FORM

(1) Info Source	(2) FACILITY OWNER	(3) FACILITY TYPE	(4) LOCATION	(5) Impact	(6) ROW /TCE	(7) REMARKS/ REASON FOR CONFLICT
B&C- Bluestake	Arizona Public Services – Precott Carby Hrober (602) 493-4225	ELECTRIC	<p>Along SB SR 89, ranges from 10'-20' from EOP, Several 5" underground lines run across SR 89 about 55' north of Perkinsville Rd., Overhead lines cross SR 89 at Adams Dr., Road 3N, Road 3-1/2N, and Road 4N, Overhead line crosses SR 89 approximately 250' north of Road 3N, 200' of OH power along NB SR 89 beginning 250' north of Road 3N, Secondary overhead line crosses SR 89 approximately 750' north of Road 3N, Overhead primary line crosses SR 89 approximately 900' north of Road 3N, Overhead primary line crosses SR 89 approximately 100' south of Industrial Dr., Overhead primary along NB SR 89 from just south of Industrial Dr. to just south of Road 4N, 12 5" underground lines along NB SR 89 pick up where OH primary ends south of Road 4N and extends to Road 4N, 4 5" underground lines along NB SR 89 extend from Road 4N to just north of Road 4N</p>	Y		<p>Potential for pole relocation. OH utility pole relocation required on SB side of SR 89 from Road 3N to Road 4N.</p>

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

B&C- Bluestake	Arizona Department of Transportation – Maricopa Trevor Eltringham (928) 308-3361	ELECTRIC	New underground lighting conduit and pull boxes run around footprint of roundabout at Perkinsville Road, New underground lighting conduit runs along each side of SR 89 for about 200' north from Perkinsville Road, Underground conduit runs along SB SR 89 for about 400' south from Road 3N and along NB SR 89 for about 400' north from Road 3N, New underground lighting conduit and pull boxes run around footprint of roundabout at Road 4N, New underground lighting conduit runs along each side of SR 89 for about 200' north from Road 4N,	Y		Conflict north of Road 3N. Potential for utility relocation.
B&C- Bluestake	Arizona Department of Transportation – Maricopa Amber Galindo-Zarate (928) 759-2426 x3615	CULVERT, STORM DRAIN	Multiple culverts run parallel to SR 89 under driveways from Road 3N to Road 4N. Multiple culverts cross SR 89 between Perkinsville Road and Road 4N. Storm drain runs along SB SR 89 from south of Road 3N to north of Road 3N and connects at least 2 manholes, then outlets to ditch north of Road 3N on SB side.	Y		Conflict with roadway widening. Potential for utility relocation.
C- Bluestake	Cable One – Prescott Johnny Cedillo (928) 237-6874	CATV	3 cables ranging from 1/4" to 3/4" run along SB EOP of SR 89 from Perkinsville Road to Road 3N, 3/4" main carrier cable runs along SB EOP of SR 89 from Road 3N to Road 4N, 1/4"-1/2" fiber runs along center of SR 89 connecting manholes from Road 3N to Road 4N, 3/4" main carrier cable crosses SR 89 at Road 3N, 1/4" fiber crosses SR 89 at Road 3N, 1/2" feeder cable crosses SR 89 at Road 3N, 1/2" feeder cable crosses SR 89 just north of Road 3N, 3/4" main carrier cable crosses SR 89 just south of Palomino Rd., 2 3/4" main carrier cables cross SR 89 at Road 4N, All utilities underground in vicinity of new roundabout at SR 89/Perkinsville Rd., rise above ground after clearing roundabout construction limits.	Y		Conflict with roadway widening. Potential for utility relocation.
C- Bluestake	CTLQL – CenturyLink USIC DISPATCH CENTER (800) 778-9140	COAXIAL, FIBER	No response	N/A		No Response

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P1A and P2-Perkinsville Road to Road 4N

C- Bluestake	UniSource Energy Services – Prescott Aaron McCoy (928) 771-7233	GAS	4" underground gas line runs along NB SR 89 from Perkinsville Rd. to Adams Dr., 4" underground gas line crosses SR 89 at Butterfield Rd., 2" high pressure gas line runs along NB SR 89 from Butterfield Rd. to Road 3N, 2" gas main runs along NB SR 89 from Road 3N to about 1000' north of Road 3N,	Y		Potential conflict with roundabouts and subsequent utility relocation.
C- Bluestake	Chino Valley Irrigation District (928) 636-4535	IRRIGATION	No response	N/A		No Response

- 1) Use A – Permit Log, B – Field Observation, C – Utility/Other
- 2) Facility Owner (company/agency) name and contact information. Note: this does not include drainage features located underground
- 3) Type and Size of facility
- 4) Use Milepost or Stationing. Last resort describe
- 5) Y – Likely to impact facility with project N – Not likely to impact facility
- 6) Y – If relocation, likely to need TCE or ROW N- No
- 7) Pertinent Information include potential relocation cost, schedule impacts, coring requirements, potential Utility Agreement notes, or other risks

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW



**Planning Assistance for Rural Areas
PRELIMINARY SCOPING REPORT**

GENERAL PROJECT INFORMATION	
Date: March 29, 2017	ADOT Project Manager: Dan Gabiou
Project Name: Construct NB Left-Turn Lane and SB Right-Turn Lane at Little Ranch Road	
City/Town: Community of Paulden	County: Yavapai
COG/MPO: Central Yavapai Metropolitan Planning Organization	ADOT District: Northwest District
Primary Route/Street: State Route 89	
Beginning Limit: MP 335.65	
End Limit: MP 335.88	
Project Length: N/A	
Right-of-Way Ownership(s) (where proposed project construction would occur): <i>(Check all that apply)</i> <input type="checkbox"/> City/Town; <input type="checkbox"/> County; <input checked="" type="checkbox"/> ADOT; <input type="checkbox"/> Private; <input type="checkbox"/> Federal; <input type="checkbox"/> Tribal; <input type="checkbox"/> Other	
Adjacent Land Ownership(s): <i>(Check all that apply)</i> <input type="checkbox"/> City/Town; <input type="checkbox"/> County; <input type="checkbox"/> ADOT; <input checked="" type="checkbox"/> Private; <input type="checkbox"/> Federal; <input type="checkbox"/> Tribal; <input type="checkbox"/> Other	

LOCAL PUBLIC AGENCY (LPA) or TRIBAL GOVERNMENT INFORMATION <i>(If applicable)</i>	
LPA/Tribal Name: Town of Chino Valley	
LPA/Tribal Contact: Michael Lopez	
Email Address: mlopez@chinoaz.net	Phone Number: (928) 636-7140
LPA/Tribal Name: Yavapai County	
LPA/Tribal Contact: Byron Jaspers	
Email Address: Byron.jaspers@yavapai.us	Phone Number: (928) 771-3183
Administration: <input checked="" type="checkbox"/> ADOT Administered <input type="checkbox"/> Self-Administered <input type="checkbox"/> Certification Acceptance	

PROJECT NEED
There is a need to address safety at the intersection of SR 89 and Little Ranch Road. Within the five year analysis period, there were five crashes at this intersection; two single vehicle, one animal, one sideswipe, and one run off the road. Four of the five crashes occurred at night. The run off the road was an incapacitating crash; the other four had no injuries. There was a fatal crash (rear end collision) shortly after the analysis period. Many of these appear to be attributable to a lack of turn lanes for turning movements to Little Ranch Road to remove slow/stopped vehicles from the high-speed mainline. In general, there is a need to reduce the number of single vehicle and nighttime collisions.

PROJECT PURPOSE			
What is the Primary Purpose of the Project?	Preservation <input type="checkbox"/>	Modernization <input checked="" type="checkbox"/>	Expansion <input type="checkbox"/>
The primary purpose of the project is to provide a northbound left-turn lane and a southbound right-turn lane at Little Ranch Road, which will help to mitigate crashes near the intersection by providing a safe location for turning movements.			



Planning Assistance for Rural Areas PRELIMINARY SCOPING REPORT

PROJECT RISKS

Check any risks identified that may impact the project's scope, schedule, or budget:

<input type="checkbox"/> Access / Traffic Control / Detour Issues	<input type="checkbox"/> Right-of-Way
<input type="checkbox"/> Constructability / Construction Window Issues	<input checked="" type="checkbox"/> Environmental
<input type="checkbox"/> Stakeholder Issues	<input type="checkbox"/> Utilities
<input checked="" type="checkbox"/> Structures & Geotech	<input checked="" type="checkbox"/> Other: Drainage

Environmental: The proposed project limits fall within a known eagle nest area near Sullivan Lake. Wildlife crossing are in the project area. Appropriate measures should be taken to avoid impacting wildlife in the area.

Structures: Structure No. 979, Big Chino Wash Bridge, is less than 800 feet north of Little Ranch Road. The structure was reconstructed in 2014 and has a deck width of 47 feet, maximum span length of 78 feet, and is 290 feet long. Turn lane improvements should be configured to eliminate the need for bridge widening. Potential rock cut/blasting will be needed north of Little Ranch Road.

Drainage: A culvert crosses SR 89 approximately 200 feet south of the intersection. Based upon conceptual design, the culvert would not need to be extended to accommodate improvements. There is a small floodplain between Sweet Valley Road and Little Ranch Road. Final design will require further drainage investigation.

POTENTIAL FUNDING SOURCE(S)

Anticipated Project Design/Construction Funding Type: <i>(Check all that apply)</i>	<input type="checkbox"/> STBG	<input type="checkbox"/> TAP	<input checked="" type="checkbox"/> HSIP	<input checked="" type="checkbox"/> State
	<input type="checkbox"/> Local	<input type="checkbox"/> Private	<input type="checkbox"/> Tribal	<input type="checkbox"/> Other:

COST ESTIMATE

Preliminary Engineering \$28,000	Design \$85,000	Right-of-Way \$0	Construction \$1,295,000	Total \$1,410,000
-------------------------------------	--------------------	---------------------	-----------------------------	----------------------

RECOMMENDED PROJECT DELIVERY

Delivery: ☒ Design-Bid-Build ☐ Design-Build ☐ Other


Design Program Year: FY 2021-FY 2026

Construction Program Year: FY 2022 – FY 2027


ATTACHMENTS

- 1) State Location Map
- 2) Project Vicinity Map
- 3) Project Scope of Work
- 4) Project Schedule
- 5) Itemized Cost Estimate
- 6) Conceptual Design Plans (not to exceed 15% design)
- 7) Final Field Review Report

ATTACHMENT 1 – STATE LOCATION MAP



ATTACHMENT 2 – PROJECT VICINITY MAP




**Project Limits: Intersection at Little Ranch Road
(MP 335.65 to MP 335.88)**

ATTACHMENT 3 – SCOPE OF WORK

SCOPE OF WORK
<ul style="list-style-type: none">Construct a northbound left-turn lane and a southbound right-turn lane at the intersection of SR 89 and Little Ranch Road.<ul style="list-style-type: none">Remove 8,500 square yards of existing asphaltic concrete pavement, including saw cutting.Construct 10,400 square yards of new asphaltic concrete pavement.Provide 10,100 feet of pavement marking on new pavement.5000 CY earthwork will be required to accommodate the proposed improvements.Improvements extend north to Big Chino Wash Bridge (Bridge No. 979) to avoid short stretch of “old” pavement.
SCOPE ITEMS CONSIDERED, BUT <u>NOT</u> INCLUDED
Not applicable to this project.

Pursuant to 23 USC 409: Notwithstanding any other provision of law, reports, surveys, schedules, lists, or data compiled or collected for the purpose of identifying, evaluating, or planning the safety enhancement of potential accident sites, hazardous roadway conditions, or rail-way-highway crossings, pursuant to sections 130, 144, and 148 [152] of this title or for the purpose of developing any highway safety construction improvement project which may be implemented utilizing Federal-aid highway funds shall not be subject to discovery or admitted into evidence in a Federal or State court proceeding or considered for other purposes in any action for damages arising from any occurrence at a location mentioned or addressed in such reports, surveys, schedules, lists, or data.

ATTACHMENT 4 – PROJECT SCHEDULE

Manual Summary RollupManual SummaryStart-onlyFinish-onlyDeadlineProgress

Page 1

ATTACHMENT 5 – ITEMIZED COST ESTIMATE

Little Ranch Road Left-Turn Installation	MP	335.58	to MP	335.92
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	8,311	\$8.00	\$66,500
SAW CUTTING	L.FT.	118	\$1.50	\$200
EARTHWORK	L.SUM	1	\$26,481.48	\$26,500
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	9,766	\$50.00	\$488,300
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	8,800	\$0.50	\$4,400
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	0	\$0.00	\$0
CONCRETE CURB	L.FT.	0	\$20.00	\$0
CONCRETE CURB AND GUTTER	L.FT.	0	\$15.00	\$0
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	0	\$60.00	\$0
STORM SEWER ALLOWANCE	L.SUM	0	\$0.00	\$0
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL \$585,900

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$46,900.00	\$46,900
Quality Control (1%)	COST	1.00%	\$5,900.00	\$5,900
Construction Surveying (1.5%)	COST	1.50%	\$8,800.00	\$8,800
Erosion Control (1%)	COST	1.00%	\$5,900.00	\$5,900
Mobilization (12%)	COST	12.00%	\$70,400.00	\$70,400

PROJECTWIDE SUBTOTAL \$137,900

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$217,200.00	\$217,200
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL \$355,100

Construction Engineering (9%)	COST	9.00%	\$84,700.00	\$84,700
Construction Contingencies (5%)	COST	5.00%	\$47,100.00	\$47,100
Engineering Design (10%)	COST	10.00%	\$94,100.00	\$94,100
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL \$225,900

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$97,600.00	\$97,600
---	------	-------	-------------	----------

SUMMARY

ITEM TOTAL	\$585,900
PROJECTWIDE TOTAL	\$355,100
OTHER COST TOTAL	\$225,900
ICAP	\$97,600
TOTAL	\$1,270,000

Little Ranch Road Right-Turn Installation

	MP	335.78	to MP	335.92
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	148	\$8.00	\$1,200
SAW CUTTING	L.FT.	665	\$1.50	\$1,000
EARTHWORK	L.SUM	1	\$29,296.30	\$29,300
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	685	\$50.00	\$34,300
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	1,330	\$0.50	\$700
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	0	\$0.00	\$0
CONCRETE CURB	L.FT.	0	\$20.00	\$0
CONCRETE CURB AND GUTTER	L.FT.	0	\$15.00	\$0
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	0	\$60.00	\$0
STORM SEWER ALLOWANCE	L.SUM	0	\$0.00	\$0
TRUCK APRON	SQ.YD.	0	\$135.00	\$0

ITEM TOTAL **\$66,500**

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$5,400.00	\$5,400
Quality Control (1%)	COST	1.00%	\$700.00	\$700
Construction Surveying (1.5%)	COST	1.50%	\$1,000.00	\$1,000
Erosion Control (1%)	COST	1.00%	\$700.00	\$700
Mobilization (12%)	COST	12.00%	\$8,000.00	\$8,000

PROJECTWIDE SUBTOTAL **\$15,800**

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$24,700.00	\$24,700
---	------	--------	-------------	----------

PROJECTWIDE TOTAL **\$40,500**

Construction Engineering (9%)	COST	9.00%	\$9,700.00	\$9,700
Construction Contingencies (5%)	COST	5.00%	\$5,400.00	\$5,400
Engineering Design (10%)	COST	10.00%	\$10,700.00	\$10,700
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL **\$25,800**

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$11,200.00	\$11,200
---	------	-------	-------------	----------

SUMMARY

ITEM TOTAL	\$66,500
PROJECTWIDE TOTAL	\$40,500
OTHER COST TOTAL	\$25,800
ICAP	\$11,200
TOTAL	\$150,000



PLANNING ASSISTANCE FOR RURAL AREAS PRELIMINARY SCOPING FIELD REVIEW REPORT

The purpose of Preliminary Scoping (Pre-Scoping) is to more accurately develop a project's Scope of Work (SOW), Schedule, and Itemized Cost Estimate prior to programming a project in a Transportation Improvement Program (TIP). This process will help to streamline project design by reducing upfront work, scope changes, project delays, and TIP Amendments.

The information gathered from the Pre-Scoping Field Review Report will be used to develop the project's SOW, Schedule, and Itemized Cost Estimate, which will be summarized in the Pre-Scoping Report.

Pre-Scoping Field Review Forms are to be completed by functional groups responsible for each area as needed (based on the project scope). Not all projects will require all Field Review Forms to be filled out.

Field Review Form	Name	Date Completed
Background Data	Benjamin Barkan	January 10, 2017
Bridge – Design		
Bridge – Hydraulics / Drainage		
District – Constructability		
District – Maintenance	Dan Gabiou	January 25, 2017
Environmental	Dan Gabiou and Justin Hoppmann	January 25, 2017
Geotechnical		
Pavement / Materials		
Right-of-Way		
Roadway / Drainage	Roger McCormick	January 25, 2017
Traffic / Safety	Dan Gabiou	January 25, 2017
Utilities		

The below 23 USC 409 disclaimer is to be included in the Final Pre-Scoping Report and Field Review Report:

23 USC 409 Disclaimer:

Notwithstanding any other provision of law, reports, surveys, schedules, lists, or data compiled or collected for the purpose of identifying, evaluating, or planning the safety enhancement of potential accident sites, hazardous roadway conditions, or rail-way-highway crossings, pursuant to sections 130, 144, and 148 [152] of this title or for the purpose of developing any highway safety construction improvement project which may be implemented utilizing Federal-aid highway funds shall not be subject to discovery or admitted into evidence in a Federal or State court proceeding or considered for other purposes in any action for damages arising from any occurrence at a location mentioned or addressed in such reports, surveys, schedules, lists, or data.

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

BACKGROUND DATA
(To be completed prior to KOM and Field Review)

Previous Projects

ADOT / LPA / Tribal Project Number	Begin Milepost / Cross Street	End Milepost / Cross Street	Length (miles)	As-Built Date	Description

ITEM	YES	NO	If Yes, Describe (or see below)
Past Study Completed?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<p>CYMPO Title VI Plan, June 2016 No protected populations identified.</p> <p>AASHTO U.S. Bicycle Route System, August 2015 U.S. Bicycle Route (USBR 79) recommended to go from Prescott to I-40 along SR 89.</p> <p>CYMPO Regional Transportation Plan Update 2040, April 2015 Reprioritization of transportation investments through the 2040 planning horizon. RTP indicates widening to six lanes from Deep Well Ranch Road to Center Street is included in the FY2025 to FY2040 planning horizon; this segment is south of the Study Area. The Great Western Extension is included in the FY2025 to FY 2040 planning horizon and is a new two-lane facility located north of SR 89A and will intersect SR 89 near Road 5 South.</p> <p>State Route 89 Access Management Plan, June 1997 One-mile spacing of major, signalized intersections and non-major intersections with right-in, right-out, and left-in access at half-mile spacing. Driveways with direct access to SR 89 consolidated or eliminated when possible.</p> <p>Chino Valley Extension Study, February 2009 New four-lane access controlled road, Chino Valley Extension, to serve as an alternate route for SR 89 in Chino Valley and Paulden areas (recommended intersection approximately 1 mile south of Big Chino Road).</p>
Project included in TIP?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not programmed
Is AADT available?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	See next page
Is crash data available?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<p>Intersection Summary: SR 89/Little Ranch Road. 5 crashes reported in a 5-year study period (2011 thru 2015). 2 single vehicle crashes, 1 animal crash, 1 sideswipe crash, and 1 run off the road crash. The run off the road crash resulted in a fatality. Another fatal crash occurred after the analysis period (2/25/2016).</p>
Known Transit needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

Known Freight needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Potential increase in freight traffic once Hell Canyon Bridge is replaced.
Known Railroad needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Known Airport needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Known Bike needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	SR 89 is identified as part of the Adventure Cycling Association Grand Canyon Connector.
Known Pedestrian / ADA needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Other needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

BMP 330.20 Road 4 North			EMP 337.70 Big Chino Road		
	NB AADT	SB AADT	AADT	T Factor %	Future 2035 AADT
2015	4,760	4,590	9,200	8.3	14,628
2014	4,405	4,248	8,653	10.6	N/A
2013	4,220	4,076	8,296	9.2	N/A
2012	4,102	4,055	8,157	10.5	N/A
2011	3,921	3,941	7,862	17.0	N/A

Source: <https://www.azdot.gov/planning/DataandAnalysis/average-annual-daily-traffic>

Traffic Counts were conducted for this study March 23, 2016. Daily traffic volumes were approximately 9,200 just south of Rolling Hills Road, approximately 1/2 of a mile south of Little Ranch Road.

Study forecast projected 2036 AADT of 10,897 vpd.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

BRIDGE DESIGN FIELD REVIEW FORM

BRIDGE NO. _____

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Replace Bridge	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Span Bridge	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Box Culvert	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Unique Structure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Replace Bridge Deck	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Widen	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Rail/Sidewalk Barrier	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Corrosion Protection	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Structural Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Deck	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Superstructure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Substructure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Concrete Wearing Course	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Expansion Joints	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Approach Panels	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Erosion/Scour Protection	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Painting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Over Water?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Utility accommodation	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Need Asbestos Assessed?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Removals	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Br Inventory Sheet indicates that Accelerated Bridge Construction (ABC) should be considered?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

Bridge No. 979, which crosses over the Big Chino Wash, is to not be impacted by this project.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

BRIDGE HYDRAULICS / DRAINAGE FIELD REVIEW FORM

ITEM	ITEM NEEDED			Struc. # If any	RP	LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE			
Mainline Culverts <input type="checkbox"/> Repair <input type="checkbox"/> Line <input type="checkbox"/> Replace <input checked="" type="checkbox"/> Extend	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>			Existing CMP culvert crosses SR 89 just south of Little Ranch Road intersection.
Sideline Culverts <input type="checkbox"/> Replace <input checked="" type="checkbox"/> Extend	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>			Existing culvert crosses Little Ranch Road at the SR 89 intersection.
Tile	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Storm Sewer	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Erosion Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Waterway analysis	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>			Unknown at this time.
Risk Assessment	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Ditch Hearing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Special Structures	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Weirs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Vortex	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Fish Passage	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Ponds	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project Limits: P6-Little Ranch Road Intersection

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

DISTRICT - CONSTRUCTION FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Detour ^a	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Temporary Construction ^a	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time. Depends on rock cut limits on the west side of SR 89.
Staging ^a	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Stockpiling	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Innovative Contracting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Control	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Construction phasing will be required to accommodate daily traffic, including large trucks.
Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

DISTRICT - MAINTENANCE FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Striping	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Signing	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Lighting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curb & Gutter	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Low gravel shoulder correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Guard Rail Repair	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Fencing	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Noisewall	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Drainage Repair	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Erosion Area Correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Flooding Area Correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Snow Trap, Storage, Icing Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
RWIS	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Anti-Icing System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Frost Heave Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Rest Area Work	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Landscaping	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Millings needed	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other salvage items	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Replace cattle guards.

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

ENVIRONMENTAL FIELD REVIEW FORM

ITEM	YES	NO	MAYBE	LOCATION / NOTES / BUDGET-SCHEDULE IMPACTS
4(f) / 6(f) sites	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known properties within the project area.
Extensive Cultural/Historical Work	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	There is one site along the west side of SR 89 at MP 335.72 located within the ROW which has undetermined eligibility.
Title VI/Environmental Justice Populations	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No permanent impacts to residents are anticipated.
Noise Concerns	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The project will not add capacity or substantially alter the alignment.
Jurisdictional Waters or Wetlands	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	There are no anticipated impacts to jurisdictional waters.
Floodplain	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	The project is not located within a 100-year floodplain (panel 0425C1305G).
State/Federal T&E Species	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No anticipated impacts to listed species.
Wildlife Crossing Concerns	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Wildlife crossings in project area.
Hazmat or Contaminated site	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known sites within the project area.
Prime or Unique Farmland	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Soils within the project area are of a type which is considered Prime Farmland if irrigated. Currently no actively irrigated farming occurs adjacent to the project area.
Air Quality Nonattainment or Maintenance Area	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	None within the project area.
Noxious or Invasive Species	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known concerns in the project area.
Visual Quality Concerns	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known concerns in the project area.
Public Involvement Required	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No public controversy is anticipated.
Significant Environmental Impacts	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Avoidance Areas	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	The project area is within 2 miles of a bald eagle nest; therefore, seasonal construction restrictions may be applicable

Anticipated NEPA Clearance Type	Categorical Exclusion (CE) <input checked="" type="checkbox"/>	Environmental Assessment (EA) <input type="checkbox"/>	Environmental Impact Statement (EIS) <input type="checkbox"/>	N/A (No federal funds anticipated) <input type="checkbox"/>
--	--	--	---	---

Anticipated Permits Needed	Section 404 Permit: Nationwide Permit <input type="checkbox"/> Individual Permit <input type="checkbox"/>	Individual Section 401 Certification <input type="checkbox"/>	Section 402 Permit: AZPDES <input type="checkbox"/> NPDES <input type="checkbox"/>
-----------------------------------	--	---	---

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

GEOTECHNICAL FIELD REVIEW FORM

ITEM	YES	NO	MAYBE	LOCATION / NOTES / BUDGET-SCHEDULE IMPACTS
Will geotechnical borings be required?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Est Drilling/Excavation Depth: Unknown at this time.
Will rock coring be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will test pits be required?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Est Drilling/Excavation Depth:
Is site accessible by a 4-wheel vehicle, backhoe, or trackhoe?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Will a seismic refraction survey be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will geologic mapping be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will soil/rock lab testing be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will geotechnical investigation require a separate Environmental Clearance?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Rock cut likely in the northwest corner of the intersection.

Comments and Risk Identification:

--

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

PAVEMENT / MATERIALS FIELD REVIEW FORM

ITEM		ITEM NEEDED			LOCATION / QUANTITY / NOTES
		YES	NO	MAYBE	
Hot Mix Asphaltic Concrete Pavement	Minor Rehab/Preventative Maint (Chip Seal, Slurry Seal, etc.)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	(include lane width)
	Major Rehab (Mill & Replace Only)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major Rehab (Mill, Replace & Overlay)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major Rehab (Overlay Only)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Reconstruction	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	(include lane width)
	Widening/Adding Turn Lanes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
	Pavement Core	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
	Falling Weight Deflectometer Test	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Portland Cement Concrete Pavement	Joint Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Dowel Bars	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major CPR	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Minor CPR	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Widening/Turn Lanes	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Pavement Core	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Other:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sub- surface	Aggregate Base Improvement	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
	Subgrade Improvement	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
	Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Shl- der	Shoulder Work	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	4 foot inside and 8 foot outside.
	Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Edge Drains	Edge Drain Video Insp	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Edge Drain Flushing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	New Edge Drains	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

RIGHT-OF-WAY FIELD REVIEW FORM

Location	Existing ROW Width	Owner	Comments
Project limits	200 feet	ADOT	

List all adjacent land owners within the project limits	Private owners.
---	-----------------

ITEM	YES	NO	MAYBE	PARCEL # / LOCATION / QUANTITY / NOTES
Potential Full-Parcel ROW Take	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Potential Partial-Parcel ROW Take	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Access Issues	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Temporary Construction Easement (TCE) required	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Drainage Easement required	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Access Easement required	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Plats needed	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

Extents/width of rock cut in northwest corner of the intersection to accommodate widening is unknown.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

ROADWAY / DRAINAGE FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Design Exception	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
CSS Design Flexibility	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Hor. Curve Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Vert. Curve Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Crown Correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Consider roadway crown placement to match Bridge No. 979 cross slopes should final design extend limits further north to the bridge.
Super Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Side Slope Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Shlder slope correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Flatten Entrance Slopes	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sight-line Obstr. Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Guardrail	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Curb & Gutter	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Retaining Walls	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Spillway	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Downdrain	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Scuppers	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
69kV lines Steel Poles	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

When considering pavement widening, a few locations that have existing utility poles could possibly need relocation due to lying within the clear zone once the road is expanded.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

TRAFFIC / SAFETY FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Bicycle Countermeasures				
Bike Lane	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pavement Markings / Signs	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	SR 89 is identified as part of the Adventure Cycling Association Grand Canyon Connector.
Shared Use Path	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Route is part of National bike route. Maintain shoulder for design.
Curve Countermeasures				
Enhanced Delineation and Friction for Horizontal Curve	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curve Warning Signs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Intersection Countermeasures				
Access Control	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Phasing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Signal/ Countdown Signal	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Offset/lengthen turn lane	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Construct new northbound left and southbound right turn lanes.
Phasing/protected left turn	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Roundabout	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Signal Backplates with Retroreflective Borders	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stop Bar	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Eastbound Little Ranch Road.
Other:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Add southbound right-turn lane and northbound left-turn lane at Little Ranch Road.
Lane / Roadway Departure Countermeasures				
Longitudinal Rumble Strips / Stripes on 2-Lane Roads (shoulder & centerline)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Raised Median Barrier	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Safety Edge	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Shoulder	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Pedestrian Countermeasures				
ADA Improvement	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Crosswalk	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Median and Ped Xing Island (urban / suburban area)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Hybrid Beacon	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Warning Sign (Ped Xing, No Right on Red, Yield to Peds)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Road Diet	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sidewalk	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Calming	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Widen Shoulder	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Railroad Crossing Countermeasures				
Active Advanced Warning Sign	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Flashing Light Signals	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Gates (Automated, Channelized, Four-Quadrant)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pavement Markings	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Signage	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Train Detection System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Signal	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Warning Bell	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Wayside Horn System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P6-Little Ranch Road Intersection

UTILITIES FIELD REVIEW FORM

(1) Info Source	(2) FACILITY OWNER	(3) FACILITY TYPE	(4) LOCATION	(5) Impact	(6) ROW /TCE	(7) REMARKS/ REASON FOR CONFLICT
B&C- Bluestake	Arizona Public Services – Prescott Carby Hrober (602) 493-4225	ELECTRIC	Overhead power runs along NB SR 89 80' offset from EOP	Y		Potential conflict with proposed widening improvements.
C- Bluestake	Arizona Department of Transportation – Maricopa Tim Collins (928) 515-4035	ELECTRIC	No response	N/A		No Response
C- Bluestake	CTLQL – CenturyLink USIC DISPATCH CENTER (800) 778-9140	COAXIAL, FIBER	No response	N/A		No Response
B&C- Bluestake	Arizona Department of Transportation – Maricopa Amber Galindo-Zarate (928) 759-2426 x3615	CULVERT, STORM DRAIN	Culvert crosses SR 89 approximately 1000' south of Little Ranch Road. Culvert crosses Little Ranch Road just west of SR 89.	Y		Potential conflict with proposed widening improvements.

- 1) Use A – Permit Log, B – Field Observation, C – Utility/Other
- 2) Facility Owner (company/agency) name and contact information. Note: this does not include drainage features located underground
- 3) Type and Size of facility
- 4) Use Milepost or Stationing. Last resort describe
- 5) Y – Likely to impact facility with project N – Not likely to impact facility
- 6) Y – If relocation, likely to need TCE or ROW N- No
- 7) Pertinent Information include potential relocation cost, schedule impacts, coring requirements, potential Utility Agreement notes, or other risks

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW



**Planning Assistance for Rural Areas
PRELIMINARY SCOPING REPORT**

GENERAL PROJECT INFORMATION	
Date: March 29, 2017	ADOT Project Manager: Dan Gabiou
Project Name: Big Chino Road Roundabout	
City/Town: Community of Paulden	County: Yavapai
COG/MPO: Central Yavapai Metropolitan Planning Organization	ADOT District: Northwest District
Primary Route/Street: State Route 89	
Beginning Limit: MP 337.70	
End Limit: MP 337.70	
Project Length: N/A	
Right-of-Way Ownership(s) (where proposed project construction would occur): <i>(Check all that apply)</i> <input type="checkbox"/> City/Town; <input checked="" type="checkbox"/> County; <input checked="" type="checkbox"/> ADOT; <input checked="" type="checkbox"/> Private; <input type="checkbox"/> Federal; <input type="checkbox"/> Tribal; <input type="checkbox"/> Other:	
Adjacent Land Ownership(s): <i>(Check all that apply)</i> <input type="checkbox"/> City/Town; <input checked="" type="checkbox"/> County; <input type="checkbox"/> ADOT; <input checked="" type="checkbox"/> Private; <input type="checkbox"/> Federal; <input type="checkbox"/> Tribal; <input type="checkbox"/> Other:	

LOCAL PUBLIC AGENCY (LPA) or TRIBAL GOVERNMENT INFORMATION <i>(If applicable)</i>	
LPA/Tribal Name: Yavapai County	
LPA/Tribal Contact: Byron Jaspers	
Email Address: Byron.jaspers@yavapai.us	Phone Number: (928) 771-3183
Administration: <input checked="" type="checkbox"/> ADOT Administered <input type="checkbox"/> Self-Administered <input type="checkbox"/> Certification Acceptance	

PROJECT NEED
<p>There is a need to address safety at the intersection of SR 89 and Big Chino Road. Currently, the intersection is one lane in each direction, with dedicated left- and right-turn lanes onto Big Chino Road. Within the past five years, there have been five crashes at or near this intersection; three run off the road, one angle, and one rear end crash. Many of these appear to be a result of differing speeds for turning and through movements at Big Chino Road.</p> <p>There is a need to address connection (access point) density, location, and type near Big Chino Road, as well. There is a large development platted east of Big Chino Road, and commercial developments are underway. Provisions for access management for future development should be considered. Freight movement is also expected to grow, so improvements should be designed to accommodate an increase in truck traffic.</p>

PROJECT PURPOSE			
What is the Primary Purpose of the Project?	Preservation <input type="checkbox"/>	Modernization <input checked="" type="checkbox"/>	Expansion <input type="checkbox"/>
The primary purpose of the project is to provide a two-lane roundabout at Big Chino Road, which will help to mitigate crashes near the intersection and also address existing access management issues and increased traffic due to future developments east of Big Chino Road. Ultimately, the overall safety and operational efficiency of SR 89 will benefit. The proposed roundabout will be able to accommodate two WB-67 trucks side by side, as well as emergency vehicles.			

Planning Assistance for Rural Areas PRELIMINARY SCOPING REPORT

PROJECT RISKS	
Check any risks identified that may impact the project's scope, schedule, or budget:	
<input checked="" type="checkbox"/> Access / Traffic Control / Detour Issues	<input checked="" type="checkbox"/> Right-of-Way
<input type="checkbox"/> Constructability / Construction Window Issues	<input checked="" type="checkbox"/> Environmental
<input checked="" type="checkbox"/> Stakeholder Issues	<input checked="" type="checkbox"/> Utilities
<input checked="" type="checkbox"/> Structures & Geotech	<input checked="" type="checkbox"/> Other: Drainage
<p>Right-of-way: It is anticipated that most of the construction will be within the existing right-of-way; however, based on conceptual plans, additional right-of-way may be required on the southwest corner of the intersection of SR 89 and Big Chino Road. Right-of-way impacts may be mitigated or eliminated during final design. A Temporary Construction Easement (TCE) will likely be necessary on the east and west side of the roundabout footprint.</p> <p>Coordination with private owner(s) and with the Yavapai County Public Works Department will be required. Traffic control will be needed during construction to protect the work zone.</p> <p>Stakeholders: Project design should include coordination with Yavapai County, local developers, and impacted landowners.</p> <p>Environmental: The proposed project limits fall within a known eagle nest area near Sullivan Lake. Appropriate measures should be taken to avoid impacting wildlife in the area.</p> <p>Robert Wash, which is a 404 designated resource, also passes through the area, north of MP 338. This wash is protected by the Clean Water Act and will need to be considered during project development.</p> <p>Utilities: There are overhead power lines that run along each side of SR 89 approximately 80 feet from the existing edge of pavement. Approximately 250 feet of overhead powerline will need to be relocated to accommodate construction and to provide an adequate clear zone. Another overhead power line crosses SR 89 approximately 750 feet north of Big Chino Road, which will need to be protected during construction. Service utilities are present in the area; utility markers are present on the northwest corner of the intersection. Utility investigation is required during final design.</p> <p>Drainage: Two existing culverts cross SR 89 near Big Chino Road; Structure No. 4806 (3-10'x10'x77' RCB) located approximately 800 feet south of the intersection and a dual storm drain pipe crossing approximately 2,000 feet north of the intersection. Based upon conceptual design, these culverts would not need to be extended to accommodate improvements. Final design should consider existing culvert dimensions.</p> <p>There are small floodplains between the BNSF Railway Overpass and Big Chino Road and between Pittsburgh Road and Verde Ranch Road. Final design will require further drainage investigation.</p> <p>Structures: The BNSF Railway Overpass (Structure No. 1577) overpasses SR 89 approximately 1,800 feet south of Big Chino Road. This structure may impact the available length for the taper for the southern roundabout approach. Taper rate adjustments of the southern leg of the intersection or adjusting the position of the roundabout should be considered in final design to avoid impacts to the BNSF Railway Overpass.</p>	



**Planning Assistance for Rural Areas
PRELIMINARY SCOPING REPORT**


POTENTIAL FUNDING SOURCE(S)				
Anticipated Project Design/Construction Funding Type: <i>(Check all that apply)</i>	<input type="checkbox"/> STBG	<input type="checkbox"/> TAP	<input checked="" type="checkbox"/> HSIP	<input checked="" type="checkbox"/> State
	<input checked="" type="checkbox"/> Local	<input type="checkbox"/> Private	<input type="checkbox"/> Tribal	<input type="checkbox"/> Other:

COST ESTIMATE				
Preliminary Engineering \$91,000	Design \$274,000	Right-of-Way \$0	Construction \$4,167,000	Total \$4,540,000

RECOMMENDED PROJECT DELIVERY	
Delivery: <input checked="" type="checkbox"/> Design-Bid-Build	<input type="checkbox"/> Design-Build <input type="checkbox"/> Other
Design Program Year: FY 2021-FY 2026	
Construction Program Year: FY 2022-FY 2027	

ATTACHMENTS
<ol style="list-style-type: none">1) State Location Map2) Project Vicinity Map3) Project Scope of Work4) Project Schedule5) Itemized Cost Estimate6) Conceptual Design Plans (not to exceed 15% design)7) Final Field Review Report

ATTACHMENT 1 – STATE LOCATION MAP



ATTACHMENT 2 – PROJECT VICINITY MAP



Project Limits: BNSF Railway to just south of Verde Ranch Road


ATTACHMENT 3 – PROJECT SCOPE OF WORK

SCOPE OF WORK
<ul style="list-style-type: none">Construct a two-lane roundabout at the intersection of SR 89 and Big Chino Road.<ul style="list-style-type: none">Remove 20,200 square yards of existing asphaltic concrete pavement, including saw cutting.Construct 29,200 square yards of new asphaltic concrete pavement.Construct 3,700 feet of concrete curb and 1,600 feet of concrete curb and gutter.Provide 24,400 feet of pavement marking on new pavement.Approximately 7,100 cubic yards of earthwork.

SCOPE ITEMS CONSIDERED, BUT <u>NOT</u> INCLUDED
<ul style="list-style-type: none">Construct the roundabout in two phases, with a single lane roundabout as phase one.

Pursuant to 23 USC 409: Notwithstanding any other provision of law, reports, surveys, schedules, lists, or data compiled or collected for the purpose of identifying, evaluating, or planning the safety enhancement of potential accident sites, hazardous roadway conditions, or rail-way-highway crossings, pursuant to sections 130, 144, and 148 [152] of this title or for the purpose of developing any highway safety construction improvement project which may be implemented utilizing Federal-aid highway funds shall not be subject to discovery or admitted into evidence in a Federal or State court proceeding or considered for other purposes in any action for damages arising from any occurrence at a location mentioned or addressed in such reports, surveys, schedules, lists, or data.

ATTACHMENT 4 – PROJECT SCHEDULE



Page 1

ATTACHMENT 5 – ITEMIZED COST ESTIMATE

Big Chino Road Roundabout	MP	337.70	to MP	337.70
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	20,178	\$8.00	\$161,500
SAW CUTTING	L.FT.	124	\$1.50	\$200
EARTHWORK	L.SUM	1	\$56,480.00	\$56,500
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	29,198	\$50.00	\$1,459,900
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	24,400	\$0.50	\$12,200
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$15,000.00	\$15,000
CONCRETE CURB	L.FT.	3,723	\$20.00	\$74,500
CONCRETE CURB AND GUTTER	L.FT.	1,563	\$15.00	\$23,500
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	808	\$60.00	\$48,500
STORM SEWER ALLOWANCE	L.SUM	1	\$200,000.00	\$200,000
TRUCK APRON	SQ.YD.	363	\$135.00	\$49,100

ITEM TOTAL \$2,100,900

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$168,100.00	\$168,100
Quality Control (1%)	COST	1.00%	\$21,100.00	\$21,100
Construction Surveying (1.5%)	COST	1.50%	\$31,600.00	\$31,600
Erosion Control (1%)	COST	1.00%	\$21,100.00	\$21,100
Mobilization (12%)	COST	12.00%	\$252,200.00	\$252,200

PROJECTWIDE SUBTOTAL \$494,100

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$778,500.00	\$778,500
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL \$1,272,600

Construction Engineering (9%)	COST	9.00%	\$303,700.00	\$303,700
Construction Contingencies (5%)	COST	5.00%	\$168,700.00	\$168,700
Engineering Design (10%)	COST	10.00%	\$337,400.00	\$337,400
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL \$809,800

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$349,800.00	\$349,800
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	\$2,100,900
PROJECTWIDE TOTAL	\$1,272,600
OTHER COST TOTAL	\$809,800
ICAP	\$349,800
TOTAL	\$4,540,000



PLANNING ASSISTANCE FOR RURAL AREAS PRELIMINARY SCOPING FIELD REVIEW REPORT

The purpose of Preliminary Scoping (Pre-Scoping) is to more accurately develop a project's Scope of Work (SOW), Schedule, and Itemized Cost Estimate prior to programming a project in a Transportation Improvement Program (TIP). This process will help to streamline project design by reducing upfront work, scope changes, project delays, and TIP Amendments.

The information gathered from the Pre-Scoping Field Review Report will be used to develop the project's SOW, Schedule, and Itemized Cost Estimate, which will be summarized in the Pre-Scoping Report.

Pre-Scoping Field Review Forms are to be completed by functional groups responsible for each area as needed (based on the project scope). Not all projects will require all Field Review Forms to be filled out.

Field Review Form	Name	Date Completed
Background Data	Benjamin Barkan	January 10, 2017
Bridge – Design		
Bridge – Hydraulics / Drainage		
District – Constructability		
District – Maintenance	Dan Gabiou	January 25, 2017
Environmental	Dan Gabiou and Justin Hoppmann	January 25, 2017
Geotechnical		
Pavement / Materials		
Right-of-Way		
Roadway / Drainage	Roger McCormick	January 25, 2017
Traffic / Safety	Dan Gabiou	January 25, 2017
Utilities		

The below 23 USC 409 disclaimer is to be included in the Final Pre-Scoping Report and Field Review Report:

23 USC 409 Disclaimer:

Notwithstanding any other provision of law, reports, surveys, schedules, lists, or data compiled or collected for the purpose of identifying, evaluating, or planning the safety enhancement of potential accident sites, hazardous roadway conditions, or rail-way-highway crossings, pursuant to sections 130, 144, and 148 [152] of this title or for the purpose of developing any highway safety construction improvement project which may be implemented utilizing Federal-aid highway funds shall not be subject to discovery or admitted into evidence in a Federal or State court proceeding or considered for other purposes in any action for damages arising from any occurrence at a location mentioned or addressed in such reports, surveys, schedules, lists, or data.

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

BACKGROUND DATA
(To be completed prior to KOM and Field Review)

Previous Projects

ADOT / LPA / Tribal Project Number	Begin Milepost / Cross Street	End Milepost / Cross Street	Length (miles)	As-Built Date	Description

ITEM	YES	NO	If Yes, Describe (or see below)
Past Study Completed?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<p>CYMPO Title VI Plan, June 2016 No protected populations identified.</p> <p>AASHTO U.S. Bicycle Route System, August 2015 U.S. Bicycle Route (USBR 79) recommended to go from Prescott to I-40 along SR 89.</p> <p>CYMPO Regional Transportation Plan Update 2040, April 2015 Reprioritization of transportation investments through the 2040 planning horizon. RTP indicates widening to six lanes from Deep Well Ranch Road to Center Street is included in the FY2025 to FY2040 planning horizon; this segment is south of the Study Area. The Great Western Extension is included in the FY2025 to FY 2040 planning horizon and is a new two-lane facility located north of SR 89A and will intersect SR 89 near Road 5 South.</p> <p>State Route 89 Access Management Plan, June 1997 One-mile spacing of major, signalized intersections and non-major intersections with right-in, right-out, and left-in access at half-mile spacing. Driveways with direct access to SR 89 consolidated or eliminated when possible.</p> <p>Chino Valley Extension Study, February 2009 New four-lane access controlled road, Chino Valley Extension, to serve as an alternate route for SR 89 in Chino Valley and Paulden areas (recommended intersection approximately 1 mile south of Big Chino Road).</p>
Project included in TIP?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not programmed
Is AADT available?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	See below
Is crash data available?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Intersection Summary: SR 89/Big Chino Road. 5 crashes reported in a 5-year study period (2011 thru 2015). 3 run off the road crashes, 1 angle crash, and 1 rear-end crashes. No fatal or serious injury.
Known Transit needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Known Freight needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Potential increase in freight traffic once Hell Canyon Bridge is replaced.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

Known Railroad needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	BNSF Railway Overpass (Structure No. 1577) may impact roundabout southern leg taper lengths
Known Airport needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Known Bike needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	SR 89 is identified as part of the Adventure Cycling Association Grand Canyon Connector.
Known Pedestrian / ADA needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Other needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

BMP 330.20 Road 4 North			EMP 337.70 Big Chino Road		
	NB AADT	SB AADT	AADT	T Factor %	Future 2035 AADT
2015	4,760	4,590	9,200	8.3	14,628
2014	4,405	4,248	8,653	10.6	N/A
2013	4,220	4,076	8,296	9.2	N/A
2012	4,102	4,055	8,157	10.5	N/A
2011	3,921	3,941	7,862	17.0	N/A

BMP 337.70 Big Chino Road			EMP 338.80 San Francisco Street		
	NB AADT	SB AADT	AADT	T Factor %	Future 2035 AADT
2015	N/A	N/A	4,985	9.0	7,926
2014	N/A	N/A	4,690	10.6	N/A
2013	N/A	N/A	4,725	10.5	N/A
2012	N/A	N/A	5,752	12.0	N/A
2011	N/A	N/A	4,697	20.0	N/A

Source: <https://www.azdot.gov/planning/DataandAnalysis/average-annual-daily-traffic>

Traffic Counts were conducted for this study March 23, 2016. Daily traffic volumes were approximately 9,200 just south of Rolling Hills Road, approximately 2 miles south of Big Chino Road.

Study forecast projected 2036 AADT of 10,897 vpd.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

BRIDGE DESIGN FIELD REVIEW FORMBRIDGE NO. 4806

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Replace Bridge	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Span Bridge	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Box Culvert	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Unique Structure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Replace Bridge Deck	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Widen	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time. It appears that widening the structure could be avoided during design.
Rail/Sidewalk Barrier	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Corrosion Protection	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Structural Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Deck	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Superstructure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Substructure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Concrete Wearing Course	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Expansion Joints	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Approach Panels	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Erosion/Scour Protection	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Painting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Over Water?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Utility accommodation	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Need Asbestos Assessed?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Removals	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Br Inventory Sheet indicates that Accelerated Bridge Construction (ABC) should be considered?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	For roadway widening, barrier and crash attenuators will need installed on the structure over the headwalls.

Comments and Risk Identification:

Project intent is to design improvements to not impact Bridge No. 1577. Adjust roadway pavement tapers on the southern leg of the roundabout intersection, or shift the position of the roundabout, to not impact Bridge No. 1577. The northbound shoulder is approximately 6 feet to 7 feet wide; the southbound shoulder is approximately 9 feet wide under the bridge. Face-of-curb to face-of-curb is approximately 40 feet under the bridge.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

BRIDGE HYDRAULICS / DRAINAGE FIELD REVIEW FORM

ITEM	ITEM NEEDED			Struc. # If any	RP	LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE			
Mainline Culverts <input type="checkbox"/> Repair <input type="checkbox"/> Line <input type="checkbox"/> Replace <input checked="" type="checkbox"/> Extend	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	4806		See bridge summary above.
Sideline Culverts <input type="checkbox"/> Replace <input type="checkbox"/> Extend	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Tile	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Storm Sewer	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Erosion Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Waterway analysis	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Risk Assessment	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Ditch Hearing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Special Structures	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Weirs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Vortex	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Fish Passage	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Ponds	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Other:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project Limits: P8-Big Chino Road Intersection

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

DISTRICT - CONSTRUCTION FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Detour ^a	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Temporary Construction ^a	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Staging ^a	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Stockpiling	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Innovative Contracting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Control	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Construction phasing will be required to accommodate daily traffic, including large trucks.
Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

--

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

DISTRICT - MAINTENANCE FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Striping	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Signing	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Lighting	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Possible for roundabout.
Curb & Gutter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Along roundabout perimeter.
Low gravel shoulder correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Guard Rail Repair	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Fencing	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Noisewall	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Drainage Repair	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Erosion Area Correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Flooding Area Correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Snow Trap, Storage, Icing Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
RWIS	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Anti-Icing System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Frost Heave Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Rest Area Work	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Landscaping	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Millings needed	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other salvage items	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Replace cattle guards.

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

ENVIRONMENTAL FIELD REVIEW FORM

ITEM	YES	NO	MAYBE	LOCATION / NOTES / BUDGET-SCHEDULE IMPACTS
4(f) / 6(f) sites	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No known properties within the project area.
Extensive Cultural/Historical Work	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No resources in the project area.
Title VI/Environmental Justice Populations	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No permanent impacts to residents are anticipated.
Noise Concerns	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The project will not add capacity or substantially alter the alignment.
Jurisdictional Waters or Wetlands	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	There are no known jurisdictional waters of the US within the project area.
Floodplain	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	There is a Zone AE 100-year floodplain on the east side of SR89 (panel 0425C0990G).
State/Federal T&E Species	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No suitable habitat present.
Wildlife Crossing Concerns	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	The project area is in a corridor identified for wildlife connectivity.
Hazmat or Contaminated site	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known spills, incidents, or concerns.
Prime or Unique Farmland	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Portions of the project area are of a soil type which is considered Prime Farmland if irrigated. Currently no actively irrigated farming occurs adjacent to the project area.
Air Quality Nonattainment or Maintenance Area	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Noxious or Invasive Species	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known concerns.
Visual Quality Concerns	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known concerns.
Public Involvement Required	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Due to business/residential impacts of access management improvements.
Significant Environmental Impacts	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Avoidance Areas	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Other	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	The project area is within 2 miles of a bald eagle nest; therefore, seasonal construction restrictions may be applicable.

Anticipated NEPA Clearance Type	Categorical Exclusion (CE) <input checked="" type="checkbox"/>	Environmental Assessment (EA) <input type="checkbox"/>	Environmental Impact Statement (EIS) <input type="checkbox"/>	N/A (No federal funds anticipated) <input type="checkbox"/>
--	--	--	---	---

Anticipated Permits Needed	Section 404 Permit: Nationwide Permit <input type="checkbox"/> Individual Permit <input type="checkbox"/>	Individual Section 401 Certification <input type="checkbox"/>	Section 402 Permit: AZPDES <input checked="" type="checkbox"/> NPDES <input type="checkbox"/>
-----------------------------------	--	---	--

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

GEOTECHNICAL FIELD REVIEW FORM

ITEM	YES	NO	MAYBE	LOCATION / NOTES / BUDGET-SCHEDULE IMPACTS
Will geotechnical borings be required?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Est Drilling/Excavation Depth: Unknown at this time.
Will rock coring be required?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Will test pits be required?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Est Drilling/Excavation Depth:
Is site accessible by a 4-wheel vehicle, backhoe, or trackhoe?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Will a seismic refraction survey be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will geologic mapping be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will soil/rock lab testing be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will geotechnical investigation require a separate Environmental Clearance?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

Existing SR 89 is on fill, above the surrounding existing ground. Widening will require earth fill.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

PAVEMENT / MATERIALS FIELD REVIEW FORM

ITEM		ITEM NEEDED			LOCATION / QUANTITY / NOTES
		YES	NO	MAYBE	
Hot Mix Asphaltic Concrete Pavement	Minor Rehab/Preventative Maint (Chip Seal, Slurry Seal, etc.)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	(include lane width)
	Major Rehab (Mill & Replace Only)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major Rehab (Mill, Replace & Overlay)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major Rehab (Overlay Only)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Reconstruction	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	(include lane width)
	Widening/Adding Turn Lanes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Roundabout
	Pavement Core	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
	Falling Weight Deflectometer Test	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Portland Cement Concrete Pavement	Joint Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Dowel Bars	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major CPR	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Minor CPR	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Widening/Turn Lanes	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Pavement Core	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Sub-surface	Aggregate Base Improvement	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
	Subgrade Improvement	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
	Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Shoulder	Shoulder Work	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	4 foot inside and 8 foot outside.
	Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Edge Drains	Edge Drain Video Insp	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Edge Drain Flushing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	New Edge Drains	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

RIGHT-OF-WAY FIELD REVIEW FORM

Location	Existing ROW Width	Owner	Comments
Project limits	200 feet	ADOT	

List all adjacent land owners within the project limits	Private owners.
---	-----------------

ITEM	YES	NO	MAYBE	PARCEL # / LOCATION / QUANTITY / NOTES
Potential Full-Parcel ROW Take	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Potential Partial-Parcel ROW Take	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Depending on the ultimate roundabout design, it is possible.
Access Issues	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Temporary Construction Easement (TCE) required	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Drainage Easement required	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Access Easement required	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Plats needed	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

ROADWAY / DRAINAGE FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Design Exception	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Depending on the ultimate roundabout design, a design exception for taper rate may be needed in order to avoid impacting the railroad overpass (Bridge No. 1577) with the southern leg of the intersection.
CSS Design Flexibility	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	See design exception above.
Hor. Curve Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Vert. Curve Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Crown Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Super Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Side Slope Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Shlder slope correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Flatten Entrance Slopes	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sight-line Obstr. Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Guardrail	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Curb & Gutter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Along roundabout perimeter.
Retaining Walls	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time. Depends on height of fill and potential impacts to adjacent lands.
Spillway	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Downdrain	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Scuppers	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
69kV lines Steel Poles	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

When considering pavement widening, a few locations that have existing utility poles could possibly need relocation due to lying within the clear zone once the road is expanded.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

TRAFFIC / SAFETY FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Bicycle Countermeasures				
Bike Lane	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pavement Markings / Signs	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	SR 89 is identified as part of the Adventure Cycling Association Grand Canyon Connector.
Shared Use Path	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Route is part of National bike route. Maintain shoulder for design.
Curve Countermeasures				
Enhanced Delineation and Friction for Horizontal Curve	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curve Warning Signs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Intersection Countermeasures				
Access Control	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Phasing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Signal/ Countdown Signal	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Offset/lengthen turn lane	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Phasing/protected left turn	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Roundabout	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Two-lane roundabout.
Signal Backplates with Retroreflective Borders	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stop Bar	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Lane / Roadway Departure Countermeasures				
Longitudinal Rumble Strips / Stripes on 2-Lane Roads (shoulder & centerline)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Raised Median Barrier	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Safety Edge	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Shoulder	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Pedestrian Countermeasures				
ADA Improvement	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Crosswalk	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Median and Ped Xing Island (urban / suburban area)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Hybrid Beacon	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Warning Sign (Ped Xing, No Right on Red, Yield to Peds)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Road Diet	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sidewalk	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Calming	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Widen Shoulder	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Railroad Crossing Countermeasures				
Active Advanced Warning Sign	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Flashing Light Signals	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Gates (Automated, Channelized, Four-Quadrant)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pavement Markings	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Signage	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Train Detection System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Signal	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Warning Bell	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Wayside Horn System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: SR 89 Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P8-Big Chino Road Intersection

UTILITIES FIELD REVIEW FORM

(1) Info Source	(2) FACILITY OWNER	(3) FACILITY TYPE	(4) LOCATION	(5) Impact	(6) ROW /TCE	(7) REMARKS/ REASON FOR CONFLICT
B&C- Bluestake	Arizona Public Services – Prescott Carby Hrober (602) 493-4225	ELECTRIC	Overhead power runs along SB SR 89 80' offset from EOP, Overhead power runs along NB SR 89 just north of Big Chino Road 80' offset from EOP, Overhead line crosses SR 89 approximately 750' north of Big Chino Road	Y		Potential conflict with proposed widening improvements. Low Crossing. Protect during construction. Potential for pole relocation. OH utility pole relocation required on NW corner of intersection of Big Chino Road and SR 89.
B-Field Observati on, C- Bluestake	CTLQL – CenturyLink USIC DISPATCH CENTER (800) 778-9140	COAXIAL, FIBER	No response. Orange utility marker spotted on NW corner of SR 89 and Big Chino Road during Field Review.	Y		Potential conflict with proposed widening improvements.
B&C- Bluestake	Arizona Department of Transportation – Maricopa TJ Soto (928) 759-2426	CULVERT, STORM DRAIN	Culvert crosses SR 89 approximately 800' south of Big Chino Road. Culvert crosses SR 89 approximately 2000' north of Big Chino Road.	Y		Potential conflict with proposed widening improvements. Culvert extension may be required.

- 1) Use A – Permit Log, B – Field Observation, C – Utility/Other
- 2) Facility Owner (company/agency) name and contact information. Note: this does not include drainage features located underground
- 3) Type and Size of facility
- 4) Use Milepost or Stationing. Last resort describe
- 5) Y – Likely to impact facility with project N – Not likely to impact facility
- 6) Y – If relocation, likely to need TCE or ROW N- No
- 7) Pertinent Information include potential relocation cost, schedule impacts, coring requirements, potential Utility Agreement notes, or other risks

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW



**Planning Assistance for Rural Areas
PRELIMINARY SCOPING REPORT**

GENERAL PROJECT INFORMATION	
Date: March 29, 2017	ADOT Project Manager: Dan Gabiou
Project Name: Bramble Drive Roundabout	
City/Town: Community of Paulden	County: Yavapai
COG/MPO: Central Yavapai Metropolitan Planning Organization	ADOT District: Northwest District
Primary Route/Street: State Route 89	
Beginning Limit: MP 338.81	
End Limit: MP 338.81	
Project Length: N/A	
Right-of-Way Ownership(s) (where proposed project construction would occur): <i>(Check all that apply)</i> <input type="checkbox"/> City/Town; <input type="checkbox"/> County; <input checked="" type="checkbox"/> ADOT; <input type="checkbox"/> Private; <input type="checkbox"/> Federal; <input type="checkbox"/> Tribal; <input checked="" type="checkbox"/> Other: Arizona State Land	
Adjacent Land Ownership(s): <i>(Check all that apply)</i> <input type="checkbox"/> City/Town; <input type="checkbox"/> County; <input type="checkbox"/> ADOT; <input checked="" type="checkbox"/> Private; <input type="checkbox"/> Federal; <input type="checkbox"/> Tribal; <input checked="" type="checkbox"/> Other: Arizona State Land Department	

LOCAL PUBLIC AGENCY (LPA) or TRIBAL GOVERNMENT INFORMATION <i>(If applicable)</i>	
LPA/Tribal Name: Yavapai County	
LPA/Tribal Contact: Byron Jaspers	
Email Address: Byron.jaspers@yavapai.us	Phone Number: (928) 771-3183
Administration: <input checked="" type="checkbox"/> ADOT Administered <input type="checkbox"/> Self-Administered <input type="checkbox"/> Certification Acceptance	

PROJECT NEED
<p>There is a need to address safety at the intersection of SR 89 and Bramble Drive. Within the past five years, there have been five crashes at or near this intersection; four left turn crashes and one head on crash. Many of these appear to be a result of differing speeds for turning and through movements at Bramble Drive.</p> <p>There is a need to address connection (access point) density, location, and type near Bramble Drive.</p> <p>This segment of the corridor has a large volume of freight traffic, reaching as high as 14% north of Bramble Drive. The roundabout design must accommodate heavy freight movement.</p>

PROJECT PURPOSE			
What is the Primary Purpose of the Project?	Preservation <input type="checkbox"/>	Modernization <input checked="" type="checkbox"/>	Expansion <input type="checkbox"/>
The primary purpose of the project is to provide a two-lane roundabout at Bramble Drive, which will help to mitigate crashes near the intersection and also address access management issues within the project area. A second northbound lane is extended a distance north of the roundabout to serve as a passing lane as SR 89 climbs grade. The proposed roundabout will be able to accommodate two WB-67 trucks side by side, as well as emergency vehicles.			



Planning Assistance for Rural Areas PRELIMINARY SCOPING REPORT

PROJECT RISKS

Check any risks identified that may impact the project's scope, schedule, or budget:

<input checked="" type="checkbox"/> Access / Traffic Control / Detour Issues	<input checked="" type="checkbox"/> Right-of-Way
<input type="checkbox"/> Constructability / Construction Window Issues	<input checked="" type="checkbox"/> Environmental
<input checked="" type="checkbox"/> Stakeholder Issues	<input checked="" type="checkbox"/> Utilities
<input type="checkbox"/> Structures & Geotech	<input checked="" type="checkbox"/> Other: Drainage

Right-of-way: It is anticipated that most of the construction will be within existing right-of-way; however, Temporary Construction Easements (TCE)s may be required on the northwest and southeast corners of the intersection between SR 89 and Bramble Drive. Coordination with the Arizona State Land Department will be necessary. Right-of-way impacts may be mitigated or eliminated during final design.

Coordination with the Yavapai County Public Works Department will be required. Traffic control will be needed during construction to protect the work zone.

Stakeholders: Additional research, analysis, coordination, and/or permitting will be required prior to construction, so as future design and construction begins, it will be necessary to coordinate with stakeholders, as well as local.

Environmental: A portion of the proposed project limits fall within a known eagle nest area near Sullivan Lake. Appropriate measures should be taken to avoid impacting wildlife in the area.

Utilities: There is a 6-inch water line that crosses SR 89 approximately 600 feet south of Bramble Drive. There is an overhead power line that crosses SR 89 approximately 300 feet north of Bramble Drive, which will need to be protected during construction. Service utilities are present in the area; utility markers were observed at the southwest and northeast corners of the intersection. Utility investigation is required during final design.

Drainage: Two existing culverts cross Bramble Drive on both the east and west legs at the intersection; a pipe culvert crosses Bramble Drive just outside the eastern edge of traveled way along SR 89, and another one crosses Bramble Drive just outside the western edge of traveled way. These small pipe culverts will need to be extended to accommodate the proposed roundabout.

POTENTIAL FUNDING SOURCE(S)

Anticipated Project Design/Construction Funding Type: <i>(Check all that apply)</i>	<input type="checkbox"/> STBG	<input type="checkbox"/> TAP	<input checked="" type="checkbox"/> HSIP	<input checked="" type="checkbox"/> State
	<input checked="" type="checkbox"/> Local	<input type="checkbox"/> Private	<input type="checkbox"/> Tribal	<input type="checkbox"/> Other:

COST ESTIMATE

Preliminary Engineering \$103,000	Design \$308,000	Right-of-Way \$0	Construction \$4,685,000	Total \$5,100,000
--------------------------------------	---------------------	---------------------	-----------------------------	----------------------

RECOMMENDED PROJECT DELIVERY

Delivery: ☒ Design-Bid-Build ☐ Design-Build ☐ Other

Design Program Year: FY 2021-2026

Construction Program Year: FY 2022-FY 2027




**Planning Assistance for Rural Areas
PRELIMINARY SCOPING REPORT**


ATTACHMENTS

- 1) State Location Map
- 2) Project Vicinity Map
- 3) Project Scope of Work
- 4) Project Schedule
- 5) Itemized Cost Estimate
- 6) Conceptual Design Plans (not to exceed 15% design)
- 7) Final Field Review Report

ATTACHMENT 1 – STATE LOCATION MAP



ATTACHMENT 2 – PROJECT VICINITY MAP



Project Limits: north of Verde Ranch Road to north of intersection of SR 89 Los Angeles Street


ATTACHMENT 3 – SCOPE OF WORK

SCOPE OF WORK
<ul style="list-style-type: none">Construct a two-lane roundabout at the intersection of SR 89 and Bramble Drive.<ul style="list-style-type: none">Remove 24,000 square yards of existing asphaltic concrete pavement, including saw cutting.Construct 33,400 square yards of new asphaltic concrete pavement.Construct 4,100 feet of concrete curb and 1,650 feet of concrete curb and gutter.Provide 25,900 feet of pavement marking on new pavement.Approximately 6,100 cubic yards of earthwork.

SCOPE ITEMS CONSIDERED, BUT <u>NOT</u> INCLUDED
<ul style="list-style-type: none">Construct the roundabout in two phases, with a single lane roundabout as phase one. Not implemented due to ADOT preference and potential future costs.

Pursuant to 23 USC 409: Notwithstanding any other provision of law, reports, surveys, schedules, lists, or data compiled or collected for the purpose of identifying, evaluating, or planning the safety enhancement of potential accident sites, hazardous roadway conditions, or rail-way-highway crossings, pursuant to sections 130, 144, and 148 [152] of this title or for the purpose of developing any highway safety construction improvement project which may be implemented utilizing Federal-aid highway funds shall not be subject to discovery or admitted into evidence in a Federal or State court proceeding or considered for other purposes in any action for damages arising from any occurrence at a location mentioned or addressed in such reports, surveys, schedules, lists, or data.

ATTACHMENT 4 – PROJECT SCHEDULE



Project: SR 89 Bramble Dr Roundabout
Date: Fri 3/31/17

Task

Split

Milestone

Summary

Project Summary

External Tasks

External Milestone

Inactive Task

Inactive Milestone

Inactive Summary

Manual Task

Duration-only

Manual Summary Rollup

Manual Summary

Start-only

Finish-only

Deadline

Progress

ATTACHMENT 5 – ITEMIZED COST ESTIMATE

Bramble Drive Roundabout	MP	338.81	to MP	338.81
Description	Unit	Quantity	Unit Price	Amount
REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	0	\$5.00	\$0
MILL EXISTING PAVEMENT	SQ.YD.	0	\$2.00	\$0
GRADING ROADWAY FOR PAVEMENT	SQ.YD.	24,000	\$8.00	\$192,000
SAW CUTTING	L.FT.	160	\$1.50	\$300
EARTHWORK	L.SUM	1	\$48,960.00	\$49,000
ASPHALT SURFACE COURSE	SQ.YD.	0	\$6.00	\$0
ASPHALTIC CONCRETE PAVEMENT SECTION	SQ.YD.	33,383	\$50.00	\$1,669,200
PAVEMENT MARKINGS (THERMOPLASTIC)	L.FT.	25,900	\$0.50	\$13,000
ROADWAY LIGHTING	L.SUM	0	\$10,000.00	\$0
LANDSCAPING ALLOWANCE	L.SUM	1	\$15,000.00	\$15,000
CONCRETE CURB	L.FT.	4,115	\$20.00	\$82,300
CONCRETE CURB AND GUTTER	L.FT.	1,627	\$15.00	\$24,400
CONCRETE SIDEWALK	SQ.FT.	0	\$3.00	\$0
CONCRETE SIDEWALK RAMP	EACH	0	\$2,000.00	\$0
CONCRETE DRIVEWAY	SQ.FT.	0	\$15.00	\$0
MEDIAN PAVING	SQ.YD.	1,124	\$60.00	\$67,500
STORM SEWER ALLOWANCE	L.SUM	1	\$200,000.00	\$200,000
TRUCK APRON	SQ.YD.	363	\$135.00	\$49,100

ITEM TOTAL \$2,361,800

Maintenance and Protection of Traffic (8%)	COST	8.00%	\$189,000.00	\$189,000
Quality Control (1%)	COST	1.00%	\$23,700.00	\$23,700
Construction Surveying (1.5%)	COST	1.50%	\$35,500.00	\$35,500
Erosion Control (1%)	COST	1.00%	\$23,700.00	\$23,700
Mobilization (12%)	COST	12.00%	\$283,500.00	\$283,500

PROJECTWIDE SUBTOTAL \$555,400

Unidentified Items (30% of Item Total and Projectwide Subtotal)	COST	30.00%	\$875,200.00	\$875,200
---	------	--------	--------------	-----------

PROJECTWIDE TOTAL \$1,430,600

Construction Engineering (9%)	COST	9.00%	\$341,400.00	\$341,400
Construction Contingencies (5%)	COST	5.00%	\$189,700.00	\$189,700
Engineering Design (10%)	COST	10.00%	\$379,300.00	\$379,300
Right-of-Way (Unknown at this time)	COST		\$0.00	\$0
Environmental Mitigation (Unknown at this time)	COST		\$0.00	\$0

OTHER COST TOTAL \$910,400

Indirect Cost Allocation (ICAP) (8.36%)	COST	8.36%	\$393,200.00	\$393,200
---	------	-------	--------------	-----------

SUMMARY

ITEM TOTAL	\$2,361,800
PROJECTWIDE TOTAL	\$1,430,600
OTHER COST TOTAL	\$910,400
ICAP	\$393,200
TOTAL	\$5,100,000



PLANNING ASSISTANCE FOR RURAL AREAS PRELIMINARY SCOPING FIELD REVIEW REPORT

The purpose of Preliminary Scoping (Pre-Scoping) is to more accurately develop a project's Scope of Work (SOW), Schedule, and Itemized Cost Estimate prior to programming a project in a Transportation Improvement Program (TIP). This process will help to streamline project design by reducing upfront work, scope changes, project delays, and TIP Amendments.

The information gathered from the Pre-Scoping Field Review Report will be used to develop the project's SOW, Schedule, and Itemized Cost Estimate, which will be summarized in the Pre-Scoping Report.

Pre-Scoping Field Review Forms are to be completed by functional groups responsible for each area as needed (based on the project scope). Not all projects will require all Field Review Forms to be filled out.

Field Review Form	Name	Date Completed
Background Data	Benjamin Barkan	January 10, 2017
Bridge – Design		
Bridge – Hydraulics / Drainage		
District – Constructability		
District – Maintenance	Dan Gabiou	January 25, 2017
Environmental	Dan Gabiou and Justin Hoppmann	January 25, 2017
Geotechnical		
Pavement / Materials		
Right-of-Way		
Roadway / Drainage	Roger McCormick	January 25, 2017
Traffic / Safety	Dan Gabiou	January 25, 2017
Utilities		

The below 23 USC 409 disclaimer is to be included in the Final Pre-Scoping Report and Field Review Report:

23 USC 409 Disclaimer:

Notwithstanding any other provision of law, reports, surveys, schedules, lists, or data compiled or collected for the purpose of identifying, evaluating, or planning the safety enhancement of potential accident sites, hazardous roadway conditions, or rail-way-highway crossings, pursuant to sections 130, 144, and 148 [152] of this title or for the purpose of developing any highway safety construction improvement project which may be implemented utilizing Federal-aid highway funds shall not be subject to discovery or admitted into evidence in a Federal or State court proceeding or considered for other purposes in any action for damages arising from any occurrence at a location mentioned or addressed in such reports, surveys, schedules, lists, or data.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

BACKGROUND DATA
 (To be completed prior to KOM and Field Review)

Previous Projects

ADOT / LPA / Tribal Project Number	Begin Milepost / Cross Street	End Milepost / Cross Street	Length (miles)	As-Built Date	Description

ITEM	YES	NO	If Yes, Describe (or see below)
Past Study Completed?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<p>CYMPO Title VI Plan, June 2016 No protected populations identified.</p> <p>AASHTO U.S. Bicycle Route System, August 2015 U.S. Bicycle Route (USBR 79) recommended to go from Prescott to I-40 along SR 89.</p> <p>CYMPO Regional Transportation Plan Update 2040, April 2015 Reprioritization of transportation investments through the 2040 planning horizon. RTP indicates widening to six lanes from Deep Well Ranch Road to Center Street is included in the FY2025 to FY2040 planning horizon; this segment is south of the Study Area. The Great Western Extension is included in the FY2025 to FY 2040 planning horizon and is a new two-lane facility located north of SR 89A and will intersect SR 89 near Road 5 South.</p> <p>State Route 89 Access Management Plan, June 1997 One-mile spacing of major, signalized intersections and non-major intersections with right-in, right-out, and left-in access at half-mile spacing. Driveways with direct access to SR 89 consolidated or eliminated when possible.</p> <p>Chino Valley Extension Study, February 2009 New four-lane access controlled road, Chino Valley Extension, to serve as an alternate route for SR 89 in Chino Valley and Paulden areas (recommended intersection approximately 1 mile south of Big Chino Road).</p>
Project included in TIP?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not programmed
Is AADT available?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	See below
Is crash data available?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Intersection Summary: SR 89/Bramble Drive. 5 crashes reported in a 5-year study period (2011 thru 2015). 4 left turn crashes and 1 head on crash. 1 crash resulted in fatal injury, and 1 resulted in an incapacitating injury.
Known Transit needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Known Freight needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Potential increase in freight traffic once Hell Canyon Bridge is replaced.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

Known Railroad needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Known Airport needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Known Bike needs?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	SR 89 is identified as part of the Adventure Cycling Association Grand Canyon Connector.
Known Pedestrian / ADA needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Other needs?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

BMP 337.70 Big Chino Road		EMP 338.80 San Francisco Street	
	AADT	T Factor %	Future 2035 AADT
2015	4,985	9.0	7,926
2014	4,690	10.6	N/A
2013	4,725	10.5	N/A
2012	5,752	12.0	N/A
2011	4,697	20.0	N/A

BMP 338.80 San Francisco Street		EMP 346.52 Drake Road	
	AADT	T Factor %	Future 2035 AADT
2015	3,263	9.5	3,622
2014	3,070	12.0	N/A
2013	3,078	11.3	N/A
2012	3,405	12.8	N/A
2011	3,175	23.0	N/A

Source: <https://www.azdot.gov/planning/DataandAnalysis/average-annual-daily-traffic>

Traffic Counts were conducted for this study March 23, 2016. Daily traffic volumes were approximately 9,200 just south of Rolling Hills Road, approximately 3.5 miles south of Bramble Drive.

Study forecast projected 2036 AADT of 10,897 vpd.

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

BRIDGE DESIGN FIELD REVIEW FORM

BRIDGE NO. _____

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Replace Bridge	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Span Bridge	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Box Culvert	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Unique Structure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Replace Bridge Deck	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Widen	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Rail/Sidewalk Barrier	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Corrosion Protection	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Structural Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Deck	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Superstructure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Substructure	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Concrete Wearing Course	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Expansion Joints	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Approach Panels	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Erosion/Scour Protection	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Painting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Over Water?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Utility accommodation	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Need Asbestos Assessed?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Removals	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Br Inventory Sheet indicates that Accelerated Bridge Construction (ABC) should be considered?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

BRIDGE HYDRAULICS / DRAINAGE FIELD REVIEW FORM

ITEM	ITEM NEEDED			Struc. # If any	RP	LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE			
Mainline Culverts <input type="checkbox"/> Repair <input type="checkbox"/> Line <input type="checkbox"/> Replace <input type="checkbox"/> Extend	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			
Sideline Culverts <input type="checkbox"/> Replace <input checked="" type="checkbox"/> Extend	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			Two existing culverts cross Bramble Drive on the east and west legs of the intersection.
Tile	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Storm Sewer	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Erosion Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Waterway analysis	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Risk Assessment	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Ditch Hearing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Special Structures	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Weirs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Vortex	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Fish Passage	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Ponds	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Other:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>			

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project Limits: P9-Bramble Drive Intersection

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

DISTRICT - CONSTRUCTION FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Detour ^a	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Temporary Construction ^a	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Staging ^a	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Stockpiling	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Innovative Contracting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Control	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Construction phasing will be required to accommodate daily traffic, including large trucks.
Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

--

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

DISTRICT - MAINTENANCE FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Striping	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Signing	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Lighting	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Possible for roundabout.
Curb & Gutter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Along roundabout perimeter.
Low gravel shoulder correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Guard Rail Repair	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Fencing	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Noisewall	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Drainage Repair	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Erosion Area Correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Flooding Area Correction	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Snow Trap, Storage, Icing Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
RWIS	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Anti-Icing System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Frost Heave Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Rest Area Work	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Landscaping	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Millings needed	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other salvage items	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Replace cattle guards.

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

ENVIRONMENTAL FIELD REVIEW FORM

ITEM	YES	NO	MAYBE	LOCATION / NOTES / BUDGET-SCHEDULE IMPACTS
4(f) / 6(f) sites	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known properties within the project area.
Extensive Cultural/Historical Work	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No resources present.
Title VI/Environmental Justice Populations	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No permanent impacts to residents are anticipated.
Noise Concerns	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The project will not add capacity or substantially alter the alignment.
Jurisdictional Waters or Wetlands	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	There are no anticipated impacts to jurisdictional waters.
Floodplain	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	The project is not located within a 100-year floodplain (panel 0425C0990G).
State/Federal T&E Species	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No anticipated impacts to listed species.
Wildlife Crossing Concerns	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Wildlife crossings in project area.
Hazmat or Contaminated site	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known sites within the project area.
Prime or Unique Farmland	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Soils within the project area are of a type which is considered Prime Farmland if irrigated. Currently no actively irrigated farming occurs adjacent to the project area.
Air Quality Nonattainment or Maintenance Area	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known concerns in the project area.
Noxious or Invasive Species	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known concerns in the project area.
Visual Quality Concerns	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No known concerns in the project area.
Public Involvement Required	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No public controversy is anticipated.
Significant Environmental Impacts	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Avoidance Areas	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Anticipated NEPA Clearance Type	Categorical Exclusion (CE) <input checked="" type="checkbox"/>	Environmental Assessment (EA) <input type="checkbox"/>	Environmental Impact Statement (EIS) <input type="checkbox"/>	N/A (No federal funds anticipated) <input type="checkbox"/>
--	--	--	---	---

Anticipated Permits Needed	Section 404 Permit: Nationwide Permit <input type="checkbox"/> Individual Permit <input type="checkbox"/>	Individual Section 401 Certification <input type="checkbox"/>	Section 402 Permit: AZPDES <input checked="" type="checkbox"/> NPDES <input type="checkbox"/>
-----------------------------------	--	---	--

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

GEOTECHNICAL FIELD REVIEW FORM

ITEM	YES	NO	MAYBE	LOCATION / NOTES / BUDGET-SCHEDULE IMPACTS
Will geotechnical borings be required?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Est Drilling/Excavation Depth:
Will rock coring be required?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Will test pits be required?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Est Drilling/Excavation Depth:
Is site accessible by a 4-wheel vehicle, backhoe, or trackhoe?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Will a seismic refraction survey be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will geologic mapping be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will soil/rock lab testing be required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Will geotechnical investigation require a separate Environmental Clearance?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

PAVEMENT / MATERIALS FIELD REVIEW FORM

ITEM		ITEM NEEDED			LOCATION / QUANTITY / NOTES
		YES	NO	MAYBE	
Hot Mix Asphaltic Concrete Pavement	Minor Rehab/Preventative Maint (Chip Seal, Slurry Seal, etc.)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	(include lane width)
	Major Rehab (Mill & Replace Only)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major Rehab (Mill, Replace & Overlay)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major Rehab (Overlay Only)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Reconstruction	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	(include lane width)
	Widening/Adding Turn Lanes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Roundabout. Continue second northbound departure lane from the roundabout to permit vehicles to pass slower heavier vehicles heading upgrade.
	Pavement Core	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
	Falling Weight Deflectometer Test	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Portland Cement Concrete Pavement	Joint Repairs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Dowel Bars	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Major CPR	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Minor CPR	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Widening/Turn Lanes	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Pavement Core	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Sub-surface	Aggregate Base Improvement	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
	Subgrade Improvement	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
	Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Shoulder	Shoulder Work	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	4 foot inside and 8 foot outside.
	Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Edge Drains	Edge Drain Video Insp	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	Edge Drain Flushing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	New Edge Drains	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

RIGHT-OF-WAY FIELD REVIEW FORM

Location	Existing ROW Width	Owner	Comments
Project Limits	200 feet	ADOT	

List all adjacent land owners within the project limits	Private owners and Arizona State Land Department.
---	---

ITEM	YES	NO	MAYBE	PARCEL # / LOCATION / QUANTITY / NOTES
Potential Full-Parcel ROW Take	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Potential Partial-Parcel ROW Take	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Depending on the ultimate roundabout design, it is possible.
Access Issues	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Temporary Construction Easement (TCE) required	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Drainage Easement required	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Access Easement required	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Unknown at this time.
Plats needed	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

ROADWAY / DRAINAGE FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Design Exception	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
CSS Design Flexibility	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Hor. Curve Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Vert. Curve Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Crown Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Super Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Side Slope Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Shlder slope correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Flatten Entrance Slopes	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sight-line Obstr. Correction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Guardrail	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Curb & Gutter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Along roundabout perimeter.
Retaining Walls	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Spillway	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Downdrain	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Scuppers	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
69kV lines Steel Poles	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

When considering pavement widening, a few locations that have existing utility poles could possibly need relocation due to lying within the clear zone once the road is expanded.

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

TRAFFIC / SAFETY FIELD REVIEW FORM

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Bicycle Countermeasures				
Bike Lane	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pavement Markings / Signs	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	SR 89 is identified as part of the Adventure Cycling Association Grand Canyon Connector.
Shared Use Path	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Route is part of National bike route. Maintain shoulder for design.
Curve Countermeasures				
Enhanced Delineation and Friction for Horizontal Curve	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curve Warning Signs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Intersection Countermeasures				
Access Control	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Phasing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Signal/ Countdown Signal	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Offset/lengthen turn lane	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Phasing/protected left turn	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Roundabout	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Two-lane roundabout.
Signal Backplates with Retroreflective Borders	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stop Bar	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Lane / Roadway Departure Countermeasures				
Longitudinal Rumble Strips / Stripes on 2-Lane Roads (shoulder & centerline)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Raised Median Barrier	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Safety Edge	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Unknown at this time.
Shoulder	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

Project #: MPD 0034-16

Name: Chino Valley to Forest Boundary Transportation Study

Date: January 11, 2017

Project Limits: P9-Bramble Drive Intersection

ITEM	ITEM NEEDED			LOCATION / QUANTITY / NOTES
	YES	NO	MAYBE	
Pedestrian Countermeasures				
ADA Improvement	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Crosswalk	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Median and Ped Xing Island (urban / suburban area)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Hybrid Beacon	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pedestrian Warning Sign (Ped Xing, No Right on Red, Yield to Peds)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Road Diet	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sidewalk	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Calming	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Widen Shoulder	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Railroad Crossing Countermeasures				
Active Advanced Warning Sign	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Flashing Light Signals	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Gates (Automated, Channelized, Four-Quadrant)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pavement Markings	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Signage	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Train Detection System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Traffic Signal	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Warning Bell	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Wayside Horn System	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Comments and Risk Identification:

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

**UTILITIES
FIELD REVIEW FORM**

(1) Info Source	(2) FACILITY OWNER	(3) FACILITY TYPE	(4) LOCATION	(5) Impact	(6) ROW /TCE	(7) REMARKS/ REASON FOR CONFLICT
B&C- Bluestake	Arizona Public Services – Prescott Carby Hrober (602) 493-4225	ELECTRIC	Overhead power crosses SR 89 just north of Bramble Drive	N		Unmarked – No locate required contractually
C- Bluestake	Abra Water Company Rod Yarbro (928) 925-1049	WATER	6" main line extension crosses SR 89 just south of Bramble Drive Existing service line (currently unused) crosses SR 89 between 6" main line and Bramble Drive	Y		Potential conflict with proposed improvements. Further utility investigation is required.
B&C- Bluestake	CTLQL – CenturyLink USIC DISPATCH CENTER (800) 778-9140	COAXIAL, FIBER	No response. Orange utility marker spotted on SW corner of SR 89 and Bramble Drive during Field Review. Orange utility marker spotted on NE corner of SR 89 and Bramble Drive during Field Review.	Y		Potential conflict with proposed widening improvements.
C- Bluestake	Arizona Department of Transportation – Maricopa Amber Galindo-Zarate (928) 759-2426 x3615	CULVERT	Culverts cross Bramble Drive on both east and west leg at intersection of SR 89.	Y		Potential conflict with proposed widening improvements. Culvert extension may be required.

- 1) Use A – Permit Log, B – Field Observation, C – Utility/Other
- 2) Facility Owner (company/agency) name and contact information. Note: this does not include drainage features located underground
- 3) Type and Size of facility
- 4) Use Milepost or Stationing. Last resort describe
- 5) Y – Likely to impact facility with project N – Not likely to impact facility
- 6) Y – If relocation, likely to need TCE or ROW N- No
- 7) Pertinent Information include potential relocation cost, schedule impacts, coring requirements, potential Utility Agreement notes, or other risks

RETURN FORM TO PROJECT MANAGER FOLLOWING THE FIELD REVIEW

State Route 89 Chino Valley to Forest Boundary Transportation Study

Field Review Meeting Summary

Date: January 11, 2017
Time: 9:00 am
Location: Project Site
1978 N SR 89
Chino Valley, AZ 86323

Participants:

Dan Gabiou – ADOT	Roger McCormick – Yavapai County
Andy Roth – ADOT	Jason Pagnard – B&N
Chris Bridges – CYMPO	Benjamin Barkan – B&N
Michael Lopez – Chino Valley, Town of	

Handouts:

Agenda, Field Review forms for four recommended projects, relevant Working Paper 2 Plan Sheets,

Meeting began at 9:05 a.m.

Notes:

➤ INTRODUCTIONS AND PRE-SCOPING PROCESS

- **Process** – A field review, meeting documentation, and Preliminary Scoping Report (PSR) will be completed. The PSR will better define project scope, schedule, and budget as well as identify engineering and environmental constraints and overall project development process concerns.
 - *Jason Pagnard welcomed attendees and provided a general overview, including an overview of the project and process.*
 - *It was discussed that this Pre-scoping Process is intended to provide insight to facilitate the scoping and programming process. Historically, projects are programmed without much background, which has caused issues during project scoping, including over or under funding projects within programs. This pre-scoping process is intended to provide an initial review of project issues, identify potential red flags and cost drivers that will ultimately help mitigate and provide better information for the formal scoping and*

programming of projects. It is not intended to replace the formal, traditional scoping process, but provide information to help facilitate future project development efforts.

➤ PROJECT OVERVIEW

- **Widening to four-lane section with raised median from Perkinsville Road to Road 4N – SR 89, from Perkinsville Road to Road 4N, is approximately 6,800' in length.**
 - *Jason provided an overview of the project, site issues, and scope of potential improvements that originated from Working Paper 2.*
 - *Convert existing TWLTL to a raised median from Perkinsville Road to Road 3N.*
 - *Widen the road and add a median between Road 3N and Road 4N.*
 - *Improve capacity on SR 89 from Perkinsville Road to Road 4N.*
 - *Manage access points along SR 89 from Perkinsville Road to Road 4N.*
 - *Add sidewalk and ADA facilities.*
 - *It was asked whether all NB movements would be protected, and concerns were raised regarding increased U-turn movements as a result of raised medians.*
 - *Jason reminded the group that all curb ramps through the corridor will need to meet ADA requirements.*
 - *Jason asked how far along side streets, driveways, etc., to include in cost estimate.*
 - *Andy mentioned all drive aprons at driveways need to be incorporated into cost estimate.*
 - *Concern was expressed about access to and from Butterfield Road with a new raised median.*
 - *Raised median would encourage cut-through traffic at Road 3N since there is not another good nearby access point.*
 - *U-turns at Road 3N are not practical without roundabout.*
 - *It was suggest that there should be two options:*
 - *Maintain full access at Butterfield Road if no roundabout is constructed at Road 3N.*
 - *Construct raised median at Butterfield Road (convert it to RIRO) and construct roundabout at Road 3N.*
 - *It was pointed out that the potentially historic building at northwest corner of Road 3N could be constraint for the roundabout idea at Road 3N.*
 - *There is new business development anticipated along SR 89 from Road 3N to Road 3½N.*
 - *Access point should be decided sooner than later at Road 3½N. Roundabout should be considered at the location.*
 - *Everyone agreed that it made the most sense to keep SR 89 at 45 mph between Road 3N and Road 4N.*
 - *It was advised to not change vertical profile significantly, if at all. In general, SR 89 is elevated above surrounding ground.*

- **Left-turn lane at Little Ranch Road** – Intersection between SR 89 and Little Ranch Road. The proposed project is approximately 1,500' in length.
 - *Jason provided an overview of the project, site issues, and scope of potential improvements that originated from Working Paper 2.*
 - *Add left-turn lane at Little Ranch Road*
 - *Improve safety at intersection of Little Ranch Road and SR 89.*
 - *Adding a southbound right-turn lane was discussed.*
 - *Support was offered toward widening to the west and cutting into rock on the northwest corner of intersection of Little Ranch Road and SR 89 to provide room for a southbound right-turn lane.*
 - *It was stated that if the right-turn lane can be added without impacting the bridge, then it should be done.*
 - *It was suggest to widen/shift SR 89 slightly eastward to align with the bridge (Bridge No. 979) alignment just north of Little Ranch Road.*
 - *It was stated that a project goal is to reduce driver decision points at this location.*

- **Roundabout at Big Chino Road** – Intersection between SR 89 and Big Chino Road. The proposed project is approximately 4,500' in length.
 - *Jason provided an overview of the project, site issues, and scope of potential improvements that originated from Working Paper 2.*
 - *Construct roundabout at intersection of Big Chino Road and SR 89.*
 - *Improve safety at intersection of Big Chino Road and SR 89.*
 - *All agreed that BNSF Railway Bridge (Bridge No. 1577) impacts should be avoided.*
 - *There are 6-foot shoulders to face-of-curb underneath the railroad bridge on east side and 9-foot shoulders to face-of-curb on west side (approximately 40 feet from face-of-curb to face-of-curb).*
 - *It was suggested to use narrow medians leading up to roundabout at Big Chino Road.*
 - *SR 89 sits on fill substantially above grade of surrounding ground.*

- **Roundabout at Bramble Drive** – Intersection between SR 89 and Bramble Drive. The proposed project is approximately 4,000' in length.
 - *Jason provided an overview of the project, site issues, and scope of potential improvements that originated from Working Paper 2.*
 - *Construct roundabout at intersection of Bramble Drive and SR 89.*
 - *Improve safety at intersection of Big Chino Road and SR 89.*
 - *It was stated that the northbound grade climb leading to and through the Prescott National Forest just north of Bramble Drive is causing excessive passing movements due to slow moving, heavier vehicles heading northbound.*

- *Concern was stated that if a roundabout were constructed, then this could exacerbate the issue.*
- *It was suggested that a second northbound lane should be carried further north from the proposed roundabout to permit passing.*
- *Cattle guards that may be compromised by recommended improvements should be replaced.*

➤ **FIELD REVIEW FORMS** – complete forms and return to Jason Pagnard.

- **BRIDGE**

- *See above. No additional bridge comments were made.*

- **ROADWAY/PAVEMENT**

- *Widening to four-lane section with raised median from Perkinsville Road to Road 4N.*
 - *Pavement exhibits significant cracking, as well as potholes in locations.*
 - *Pavement exhibits transverse cracking*
 - *Two options between Perkinsville Road and Road 3N:*
 - *Raised median with left-turn pocket at Butterfield Road combined with left-turn pocket at Road 3N*
 - *Raised median from with no left-turn pockets and a roundabout at Road 3N*
 - *Michael asked that detached sidewalks along SR 89 be considered between Road 3N and Road 4N.*
 - *Provide temporary left-turn access at Road 3½N (intermediate solution). Ultimately, construct roundabout to provide for expanding businesses in this area.*
- *Left-turn lane at Little Ranch Road.*
 - *Consider including a southbound right-turn lane.*
- *Roundabout at Big Chino Road.*
 - *Curb is present along southbound side of SR 89.*

- **DRAINAGE**

- *Widening to four-lane section with raised median from Perkinsville Road to Road 4N.*
 - *With proposed earthwork and grading, drainage solutions will need to be investigated and therefore, incorporated into the cost estimate.*
 - *Drainage will flow down from properties along NB SR 89.*
 - *Culverts will need to be extended to accommodate wider roadway section, including culvert just south of Commercial Way and possibly culvert just south of Industrial Drive.*
 - *A new basin may be required on SB side of SR 89 in front of Fix Bros Auto.*

- *Substantial drainage features near recent roundabout construction at Perkinsville Road and Road 4N.*
 - *Left-Turn lane at Little Ranch Road.*
 - *Culvert under Little Ranch Road is in very poor condition.*
 - *A corrugated metal pipe crosses SR 89 just south of Little Ranch Road.*
 - *Roundabout at Big Chino Road*
 - *No existing drainage issues were identified within this project's limits.*
 - *Roundabout at Bramble Drive*
 - *No existing drainage issues within this project's limits.*
- **CONSTRUCTABILITY/MAINTENANCE**
 - *There was no discussion of constructability/maintenance issues.*
- **ENVIRONMENTAL**
 - *Widening to four-lane section with raised median from Perkinsville Road to Road 4N.*
 - *Potential historic property on northwest corner of intersection with Road 3N. It appears that a roundabout could potentially fit at Road 3N. There is a noticeable elevation difference between SR 89 (above) and the property and fill or wall may be required to limit impacts if a roundabout were constructed.*
 - *Old car dealership is located on east side of SR 89 from Palomino Road.*
 - *Left-turn at Little Ranch Road.*
 - *No environmental constraints discussed.*
 - *Roundabout at Big Chino Road.*
 - *No environmental constraints discussed.*
 - *Roundabout at Bramble Drive.*
 - *No environmental constraints discussed.*
- **RIGHT-OF-WAY**
 - *Widening to four-lane section with raised median from Perkinsville Road to Road 4N.*
 - *Town of Chino Valley owns right-of-way at Adams Drive.*
 - *Private property is in public right-of-way on northeast corner of Road 3N intersection.*
 - *Left-turn at Little Ranch Road.*
 - *There is ADOT right-of-way at Little Ranch Road intersection with SR 89.*
 - *Roundabout at Big Chino Road.*
 - *No R/W conflicts discussed at this location.*
 - *Roundabout at Bramble Drive.*
 - *Potential R/W acquisition needed on NW corner of Bramble Drive and SR 89.*

- **UTILITIES**

- *Widening to four-lane section with raised median from Perkinsville Road to Road 4N.*
 - *Storm drain runs under SR 89 southbound lanes from south of Road 3N to north of Road 3N. Two manholes and storm drain outlet location to ditch northwest of end of four-lane section (north side of church), just north of Road 3N.*
 - *Gas line identified on Road 3N, just west of SR 89.*
 - *Overhead utilities will need to be relocated on southbound side of SR 89 between Road 3N and Road 4N.*
 - *Cost for agreements with the utility companies needs to be considered.*
 - *There are potential utility conflicts with power, cable, communication, gas, and water.*
 - *Utility designation is recommended.*
- *Left-turn lane at Little Ranch Road.*
 - *There are potential utility conflicts with power and cable.*
- *Roundabout at Big Chino Road.*
 - *Overhead utility poles are very close to northern edge of pavement of Big Chino Road west of SR 89.*
 - *Unknown underground utility runs along southbound SR 89; utility marker can be seen on northwest corner of intersection of Big Chino Road and SR 89.*
 - *Overhead power lines on northwest corner at intersection of Big Chino Road and SR 89 are very close to Big Chino Road north edge of pavement, may require relocation.*
 - *There are potential utility conflicts with power and communication.*
- *Roundabout at Bramble Drive.*
 - *Unknown underground utility marker was spotted on southwest corner of intersection of Bramble Drive and SR 89.*
 - *A number of utilities are identified in the area, including fiber, which appears to cross SR 89 just south of Bramble Drive.*
 - *There are potential utility conflicts with power, water, and communication.*

- **TRAFFIC / SAFETY**

- *Widening to four-lane section with raised median from Perkinsville Road to Road 4N.*
 - *Advanced loop detectors are present for northbound and southbound thru traffic.*
 - *Old sign foundations are located throughout the corridor.*
- *Left-turn lane at Little Ranch Road.*
 - *Must reduce driver decision points within this project's limits.*
- *Roundabout at Big Chino Road.*
 - *Must reduce driver decision points within this project's limits.*
- *Roundabout at Bramble Drive.*
 - *Must reduce driver decision points within this project's limits.*

**SITE PHOTOS FROM FIELD
REVIEW AVAILABLE CD**